

Scale: N 1" = 40'

NOTE

EXISTING LANDSCAPING AND UNDERGROUND
SPRINKLER SYSTEM IN MEDIAN.
CONTACT ROY SOOTER, PARK MAINTENANCE
FOR DISPOSITION. TEL. 766-7760

LOCATION MAP

"NOTICE TO CONTRACTORS"

- 1) New Mexico Standard Specification for Public Works Construction - 1979 Edition will be referred to hereon as the "Standard Specification."
- 2) All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with "Contract Documents for City-Wide Utilities and Cash Paving No. 30 and the Standard Specification."
- 3) Two working days prior to any excavation, contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
- 4) Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

THE FOLLOWING NOTES APPLY WHEN CHECKED

- ☐ All utilities and utility service lines shall be installed prior to paving.
- ☒ Backfill compaction shall be according to specified street use. (Arterial)
- ☒ Tack coat requirements shall be determined by the City Engineer.
- ☐ Sidewalks and wheelchair ramps within the curb return shall be constructed wherever a new curb return is constructed.
- ☐ If curb is depressed for a driveway, the driveway shall be constructed prior to acceptance of the curb and gutter.
- ☐ All storm drainage facilities shall be completed prior to final acceptance.
- ☒ Coordinate construction with Project 1279

APPROVAL OF AS BUILT DRAWINGS
ASST. CITY ENGINEER - FIELD
DATE 3-17-89

CITY OF ALBUQUERQUE
MUNICIPAL DEVELOPMENT DEPARTMENT
ENGINEERING DIVISION

TITLE: MEDIAN REVISIONS ON UPTOWN BLVD. WEST
OF JEANNEDALE DR. FOR CRISWELL
DEVELOPMENT CO.

APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer	ROSA	11/11/81	Liquid Waste		
A.C.E. - Design	Phuket	12/20/81	Traffic	ROSA	10/13/81
A.C.E. - Hydrology			Water		

DRAWING NO. 1286 MAP NO. H-13 SHEET 1 OF 1

△ CURVE DATA
Δ = 49° 04' 30"
R = 991.44'
T = 452.61'
L = 849.19'

LEGEND

- AREA TO BE REMOVED & PAVED
- NEW CONCRETE MEDIAN CURB TO BE CONSTRUCTED
- RAISED PATTERNED CONCRETE TO MATCH EXISTING PATTERN & COLOR
- EXISTING TOP OF CURB ELEVATION
- PROPOSED TOP OF CURB ELEVATION

TRAFFIC HANDLING NOTES

1. CONTRACTOR MUST SUBMIT A CONSTRUCTION SIGNING AND BARRICADING PLAN TO TRAFFIC ENGINEERING DIVISION AND RECEIVE A BARRICADING PERMIT PRIOR TO CONSTRUCTION
2. ALL CONSTRUCTION SIGNING AND BARRICADING TO COMPLY WITH MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, 1978 EDITION.
3. CONTRACTOR'S OPERATION, BARRICADING AND SIGNING SHALL NOT AFFECT THRU LANES OF UPTOWN BLVD. BETWEEN 7 AM AND 9 AM OR 4 PM AND 6 PM.

CURVE DATA

	Δ	R	T	L
1.	15° 23' 16"	150'	20.26'	40.23'
2.	12° 55' 30"	150'	16.49'	33.94'
3.	33° 30' 00"	50'	17.46'	33.60'
4.	141° 30' 00"	4'	11.45'	9.88'
5.	19° 25' 08"	150'	25.67'	50.84'
6.	13° 20' 04"	150'	17.53'	34.31'
7.	49° 04' 30"	991.44'	452.61'	849.19'
8.	37° 25' 52"	800'	271.03'	522.64'
9.	180° 00' 00"	2.00'	-	6.28'

1 2 3 4 5 6 7 8 9 10 11 12
26 12860182

APPROVED FOR
CONSTRUCTION

CITY ENGINEER DATE 4/2/82