



	T.C.	F.L.
1	43.65	42.98
2	43.77	43.10
3	43.89	43.22

EXISTING CURB & GUTTER

NEW CURB & GUTTER

NEW 4' SIDEWALK

EXISTING POWER POLE

NEW LOCATION OF POWER POLE (BY OTHERS)

AREA TO BE REMOVED & PAVED WITH RESIDENTIAL PAVING (SEE CITY STD. P-7-1)

1. New Mexico Standard Specifications for Public Works Construction - 1979 Edition will be referred to hereon as the "Standard Specification."
2. All work detailed on these plans to be performed under contract shall, except as otherwise stated, be performed under and for hereon, be constructed in accordance with Contract Documents for City-Wide Utilities and Cosh Paving No. 30 and the Standard Specification.
3. Two working days prior to any excavation, Contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
4. Prior to construction, the Contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the Contractor shall notify the Engineer or Surveyor so that the conflict can be resolved with minimum amount of delay.

☐ All utilities and utility service lines shall be installed prior to paving.

☐ Backfill compaction shall be according to specified street use. (Arterial)

☐ Sidewalk requirements shall be determined by the City Engineer.

☐ Tack coats and wheelchair ramps within the curb return shall be constructed wherever a new curb return is constructed.

☐ If curb is depressed for a driveway, the driveway shall be constructed prior to acceptance of the curb and gutter.

☐ All storm drainage facilities shall be completed prior to final acceptance.

Revision No. 1		
Revision Approval	Engineer	Date
City Engineer	<i>[Signature]</i>	3/31/82
Traffic	<i>[Signature]</i>	3/31/82

GD 78-13

8-11-78
8-11-78

R.L.
RCB



FOR LETTERED CONSTRUCTION NOTES SEE CITY STD. DWG. K-4-I.



4