



NOTICE TO CONTRACTORS

- 1) New Mexico Standard Specification for Public Works Construction - 1979 Edition will be referred to hereon as the "Standard Specification."
- 2) All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with "Contract Documents for City-Wide Utilities and C&S Paving No. 30 and the Standard Specification."
- 3) Two working days prior to any excavation, contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
- 4) Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

THE FOLLOWING NOTES APPLY WHEN CHECKED

- ☐ All utilities and utility service lines shall be installed prior to paving.
- ☐ Backfill compaction shall be according to specified street use.
- ☐ Tack coat requirements shall be determined by the City Engineer.
- ☐ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.
- ☐ If curb is depressed for a driveway, the driveway shall be constructed prior to acceptance of the curb and gutter.
- ☐ All storm drainage facilities shall be completed prior to final acceptance.

NOTES:

1. REMOVE ALL PAVEMENT IN AREA MARKED [Hatched Area].
2. COMPACT SUBGRADE TO 90% COMPACTION WITH TOP 4" TO 95%.
3. CONSTRUCT 3" ASPHALT PAVING USING ASPHALT CONCRETE BASE COURSE MATERIAL.
4. MATCH EXISTING ELEVATIONS AT JOIN LINES.
5. CONTRACTOR MUST SUBMIT A CONSTRUCTION SIGNING AND BARRICADING PLAN TO TRAFFIC ENGINEERING DIVISION AND RECEIVE A BARRICADING PERMIT PRIOR TO CONSTRUCTION.
6. ALL CONSTRUCTION SIGNING AND BARRICADING TO COMPLY WITH MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, 1978 EDITION.



1320 11-25-81

APPROVED FOR CONSTRUCTION  
[Signature]  
CITY ENGINEER

CITY OF ALBUQUERQUE MUNICIPAL DEVELOPMENT DEPARTMENT ENGINEERING DIVISION					
REMOVAL & TEMPORARY PAVING REPLACEMENT ON SOUTH SIDE OF CENTRAL AND WEST SIDE SAN PEDRO BLVD. S.E.					
APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer	[Signature]	11/18/81	Traffic	[Signature]	11-25-81
Liquid Waste			STREET MAINTENANCE		
A.C.E. - Design	[Signature]	11/18/81	1320	SHEET 1	OF 1
A.C.E. - Hydrology					