

LEGEND

EXIST. CONTOUR	5236
FINISH CONTOUR	36
EXIST. ELEVATION	38.3
FINISH ELEVATION	38.3
NEW ASPHALT PAVEMENT	
NEW STANDARD OR MEDIAN C & G	
EXIST. C & G	
NEW 4" SIDEWALK	
NEW 2" P.V.C.	

CONSTRUCTION NOTES

- SIDEWALKS TO HAVE A LIGHT BROOM FINISH. HANDY CAP RAMP TO HAVE A HEAVY BROOM FINISH (TEXTURE DEPTH .035")
- PAINT 4" STRIPING LINES WHERE INDICATED (PARKING SPACES, HANDICAP PARKING SPACES, AND NO PARKING AREAS) PAINT TO CONFORM WITH AASHTO M72, TYPE 1. (BY TRAFFIC ENGINEER)
- 2" CLASS 200 PVC PIPE LOCATE 24" BELOW FINISH GRADE.

Handrail Fabricated From 2" ϕ Steel Pipe All joints Welded and Ground Smooth Prime And Paint.

WESTGATE PARK

SECTION B-B
SCALE: 1/2" = 1'-0"

Grade Area Back Of Curb Away From Parking Lot Keep Flow From Alley From Entering Parking Lot.

Horizontal Sliding Chain Link Gate

Rem f Return Exist Chainlink Gates

Rem. C & G And 4" Sidewalk Repl. C & G and Driveway As Shown.

Install New 6" Chainlink Fence

New Fence Posts 5' O.C.

Grade Area Between Exist Sidewalk And New C & G Smooth Flush With Top Of Sidewalk And Top Of Curb

AMOLE DRAIN

CONCRETE RUNDOWN DETAIL

SCALE: 1" = 2'

SECTION C C

(SECTION AT E. OF RUNDOWN)
HORIZ. SCALE: 1" = 20'
VERT. SCALE: 1" = 2'

SECTION A-A

SCALE: 1" = 4' HORIZ. & VERT.

CONCRETE RUNDOWN

1'-0" Rip Rap On 6" Filter Material

Exist. Ground @ E Rundown

Slope To Match Exist.

30.5

36.5 E

36.0 E

35.5

30.5

36.5 E

36.0 E

35.5

30.5

36.5 E

36.0 E

35.5

30.5

36.5 E

36.0 E

35.5

30.5

36.5 E

36.0 E

35.5

30.5

LOCATION MAP

ZONE ATLAS M-8

NOTICE TO CONTRACTORS

- All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for herein, be constructed in accordance with the New Mexico Standard Specifications for Public Works Construction-1979 Edition (referred to herein as the Standard Specifications) and the Contract Documents for Public Works Contract 84-3
- Two (2) working days prior to any excavation, the contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
- Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

THE FOLLOWING NOTES ALSO APPLY WHEN CHECKED

- ☐ All utilities and utility service lines shall be installed prior to paving.
- ☒ Backfill compaction shall be according to specified street use.
- ☐ Tack coat requirements shall be determined by the City Engineer.
- ☐ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.
- ☐ If curb is depressed for a driveway or a handicap ramp, the driveway or ramp shall be constructed prior to acceptance of the curb and gutter.
- ☐ All storm drainage facilities shall be completed prior to final acceptance.

APPROVAL OF CITY ENGINEER
W. S. McNamee
1/11/85

26 2169 0185

APPROVED FOR CONSTRUCTION
S. A. Chapman 9/16/84

CITY OF ALBUQUERQUE
MUNICIPAL DEVELOPMENT DEPARTMENT
ENGINEERING DIVISION

TITLE: WESTGATE PARK PARKING LOT

APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
CITY ENGINEER	S. A. Chapman	9/16/84	Liquid Waste	R. Pata	8/6/84
A.C.E. Design	W. S. McNamee	8/6/84	Traffic	W. S. McNamee	8/6/84
A.C.E. Hydrology	B. J. Bookley	8/6/84	Water	R. Pata	8/6/84
PARKS & RECREATION	W. S. McNamee	8/6/84			
DRAWING NO.	2169		MAP NO.	M-8	
			SHEET	1	OF 1

SCANNED BY LAYON

5102