

# ORIGINAL TOWNSITE OF ALBUQUERQUE

NOTE: IF CONTRACTOR CAN PLACE THE INVERTED CROWN TO THE GRADES SHOWN AT THE CENTER LINE OF THE ALLEY DURING ONE CONCRETE POUR, THE ENTIRE PORTION OF THE ALLEY TO BE REMOVED AND REPLACED MAY BE POURED AS A UNIFORM 6" SECTION WITHOUT ALLEY GUTTER AND NO LONGITUDINAL JOINTS. OTHERWISE THE NEW PORTION MUST CONFORM TO SECTION A-A. 26'x14' PAVING.

SCALE: 1" = 20'

DETAIL

SCALE: 1" = 10'

## SECTION A-A

CONSTRUCT COMMERCIAL ALLEY SECTION AS PER CITY STD. DWG. P-6, MATCH EXISTING IMPROVEMENTS AS NOTED. SCALE: 1" = 4'

LOCATION KEY MAP K-14

### LEGEND

- MH EXISTING MANHOLE
- PP EXISTING POWER POLE
- Gas Ser. EXISTING GAS SERVICE
- D.I. EXISTING DROP INLET
- T — TELEPHONE LINE
- SAS — SANITARY SEWER
- W — WATER LINE

### NOTICE TO CONTRACTORS

- All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with the City of Albuquerque Interim Standard Specifications for Construction 1985.
- Two (2) working days prior to any excavation, the contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
- Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

### THE FOLLOWING NOTES ALSO APPLY WHEN CHECKED

- ☒ All utilities and utility service lines shall be installed prior to paving.
- ☐ Backfill compaction shall be according to specified street use.
- ☐ Tack coat requirements shall be determined by the City Engineer.
- ☐ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.
- ☐ If curb is depressed for a driveway or a handicap ramp, the driveway or ramp shall be constructed prior to acceptance of the curb and gutter.
- ☐ All storm drainage facilities shall be completed prior to final acceptance.

### CONSTRUCTION NOTES:

- CONSTRUCT ALLEY CONC. SECTION TO MATCH EXISTING RIM ELEVATION AT MAN HOLE
- MATCH EXISTING
- BARRICADE TO RESTRICT PEDESTRIAN AND VEHICULAR TRAFFIC DURING CONSTRUCTION AND WHILE CONCRETE CURES & HARDENS.

CITY OF ALBUQUERQUE  
MUNICIPAL DEVELOPMENT DEPARTMENT  
ENGINEERING DIVISION

TITLE: ALLEY BETWEEN FOURTH STREET AND THIRD STREET, NORTH OF CENTRAL.

| APPROVALS          | ENGINEER           | DATE     | APPROVALS    | ENGINEER           | DATE     |
|--------------------|--------------------|----------|--------------|--------------------|----------|
| City Engineer      | <i>[Signature]</i> | 12/23/85 | Liquid Waste | <i>[Signature]</i> | 12/23/85 |
| A.C.E. - Design    | <i>[Signature]</i> | 12/23/85 | Traffic      | <i>[Signature]</i> | 12/23/85 |
| A.C.E. - Hydrology | <i>[Signature]</i> | 12/23/85 | Water        | <i>[Signature]</i> | 12/23/85 |

DRAWING NO. 2451 MAP NO. K-14 SHEET 1 OF 1

SCANNED BY