



**LOCATION MAP** M-15

**NOTICE TO CONTRACTORS**

- All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided hereon, be constructed in accordance with the City of Albuquerque Interim Standard Specifications for Construction 1985.
- Two (2) working days prior to any excavation, the contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
- Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

**THE FOLLOWING NOTES ALSO APPLY WHEN CHECKED**

- ☒ All utilities and utility service lines shall be installed prior to paving.
- ☒ Backfill compaction shall be according to specified street use.
- ☒ Tack coat requirements shall be determined by the City Engineer.
- ☐ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.
- ☐ If curb is depressed for a driveway or a handicap ramp, the driveway or ramp shall be constructed prior to acceptance of the curb and gutter.
- ☐ All storm drainage facilities shall be completed prior to final acceptance.

**CONSTRUCTION NOTES:**

- BUILD 8" PVC SANITARY SEWER LINE.
- BUILD NEW MH TYPE "E" AS PER CITY STANDARD DRAWING S-2.
- PLUS AND ABANDON EXISTING 8" SAS LINE.
- BUILD TYPE "E" DROP MH AS PER CITY STANDARD S-4. MATCH EXISTING INV. ELEV'S N. & S.
- REMOVE & REPLACE CURB AND GUTTER AS NECESSARY FOR SEWER LINE REPLACEMENT. REFER TO STD. DRWG. P-8.
- ABANDON EXISTING MH, REMOVE MH COVER, BREAK BASE TO ALLOW DRAINAGE, PLUS INVERTS AND FILL MH WITH SAND COMPACTING TO 95% MAX. DENSITY IN 6" LIFTS.
- INSTALL NEW MH TYPE "E" IN EXIST. 8" SAS MAIN.
- REMOVE AND REPLACE PAVEMENT FOR INSTALLATION OF SAS LINE. REF. DRWG. P-25.
- 20' EASEMENT REQUIRED PRIOR TO CONSTRUCTION OF SANITARY SEWER LINE.
- LANDSCAPING WILL HAVE TO BE REPLACED TO IT'S ORIGINAL CONDITION AFTER CONSTRUCTION.
- ENCASE SAS LINE 10' EACH SIDE OF WATER MAIN AS PER STD. DRWG. S-10.

**AS BUILT INFORMATION**

CONTRACTOR	INSPECTOR	DATE
SUNDANCE MECHANICAL	By: BACA	DATE: 10/16/85

**BENCH MARKS**

TBM	CUT TOP SW N.W. QUAD.	UNIVERSITY	ELEV.
8	5112.56		

**SURVEY INFORMATION**

NO.	DATE	BY
05 # 47 P. AQU/AR	8/85	

**ENGINEER'S SEAL**

NO.	DATE	BY	REVISIONS
1	10/16/85	Philip Fischer	DESIGN
2	10/16/85	D. Zamora	DATE
3	10/16/85	Philip Fischer	CHECKED BY

**CITY OF ALBUQUERQUE**  
MUNICIPAL DEVELOPMENT DEPARTMENT  
ENGINEERING DIVISION

**TITLE: SAS LINE RELOCATION THROUGH LOT I-A**  
**NZ COMMERCIAL OFFICE CENTER - UNIVERSITY BLVD - RANDOLPH CT.**

APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer	William J. Burch	10/16/85	Liquid Waste	William J. Burch	10/16/85
A C E - Design	NA		Traffic	D. Zamora	10/16/85
A C E - Hydrology	NA		Water	William J. Burch	10/16/85

**DRAWING NO. 2578** **MAP NO. M-15** **SHEET 1 OF 1**

**DATE** 10/16/85