



1. All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with the City of Albuquerque Interim Standard Specifications for Construction 1985.

2. Two (2) working days prior to any excavation, the contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
3. Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

THE FOLLOWING NOTES ALSO APPLY
WHEN CHECKED

- ☐ All utilities and utility service lines shall be installed prior to paving.
- ☒ Backfill compaction shall be according to specified street use. (*Residential*)
- ☒ Tack coat requirements shall be determined by the City Engineer.
- ☐ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.
- ☐ If curb is depressed for a driveway or a handicap ramp, the driveway or ramp shall be constructed prior to acceptance of the curb and gutter.
- ☒ All storm drainage facilities shall be completed prior to final acceptance.

NOTES:

- ① LOCATION OF EXISTING UTILITY LINES AND SERVICE CONNECTIONS MUST BE VERIFIED PRIOR TO CONSTRUCTION OF NEW STORM DRAIN.
- ② WHERE CLEARANCE BETWEEN NEW 24" RCP AND EXISTING SERVICE LINE IS LESS THAN 1 FOOT, SERVICE LINE SHALL BE RELOCATED PER DETAIL THIS SHEET.
- ③ SLOPE NEW 2" A.C. PAVEMENT TO DRAIN TO NEW CATCH BASIN, MATCH EXISTING PAVING ON JOBS AND ALTA VISTA CT. CUT EXIST. ASPH. PAVING TO EVEN EDGE BEFORE BUILDING NEW PAVING. COMPACT SUBGRADE TO 95%.
- ④ IF WATER SERVICE IS REPLACED, LINE MUST BE REPLACED FROM MAIN TO WATER METER.
- ⑤ REMOVE 22" OF EXIST. 18" RCP CONNECTOR PIPE.
- ⑥ REMOVAL & REPLACEMENT OF EXIST. PAVING SHALL BE DONE PER STD. ONE P-25.

CITY OF ALBUQUERQUE
MUNICIPAL DEVELOPMENT DEPARTMENT
ENGINEERING DIVISION

TITLE: DRAINAGE IMPROVEMENTS ALTA VISTA CT. S.W. AT
COORS BLVD. S.W.

APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer	<i>[Signature]</i>	4/23/06	Liquid Waste	<i>[Signature]</i>	3/5/06
A.C.E - Design	<i>[Signature]</i>	3/5/06	Traffic	<i>[Signature]</i>	3/5/06
A.C.E - Hydrology	<i>[Signature]</i>	3/5/06	Water	<i>[Signature]</i>	2/5/06

DRAWING NO.	2657	MAP NO.	L-11	SHEET	OF	1
----------------	------	---------	------	-------	----	---