



NOTICE TO CONTRACTORS:

- 1) City of Albuquerque Interim Standards Specifications Public Works Construction 1985 Edition will be referred to herein as the standard specifications.
- 2) All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with City of Albuquerque Interim Standard Specifications Public Works Construction 1985 Edition.
- 3) Two working days prior to any excavation the contractor must contact line location service, 765-1234, for location of existing utilities.
- 4) Prior to construction, the contractor shall excavate and verify the horizontal and vertical location of all obstructions. Should a conflict exist the contractor shall notify the engineer or surveyor so that the conflict can be resolved with a minimum of delay.

THE FOLLOWING NOTES APPLY IF CHECKED:

- [] All utilities and utility service lines shall be installed prior to paving.
- [x] Backfill compaction shall be according to arterial street use.
- [x] Tack coat requirements shall be determined by the City Engineer.
- [x] Sidewalks and wheelchair ramps within the curb returns shall be constructed where ever a new curb return is constructed.
- [] If a curb is depressed for a drive pad, the drive pad shall be constructed prior to acceptance of the curb and gutter.

TRAFFIC HANDLING NOTES:

- 1) Contractor must submit a construction signing and barricading plan to Traffic Engineering Division and receive a barricading permit prior to construction.
- 2) All construction signing and barricading to comply with manual on Uniform Traffic Control Devices, 1978 Edition and subsequent revisions.

NOTE:

- ① Contractor to remove existing concrete curb and gutter and existing 6" sidewalk sta. 0+23 to sta. 2+38. Build standard valley gutter intersection, construct turn bay area, build arterial pavement sta. 0+23 to sta. 2+11 as shown. Contractor to build standard curb and gutter and 6" concrete sidewalk sta. 0+23 to sta. 1+89, as shown. Remove and replace additional 2' ± arterial pavement as required for construction.
- ② Contractor to build standard wheelchair ramps according to city standard drawing P-17 as shown.

SURVEY INFORMATION		BENCH MARKS		AS BUILT INFORMATION	
NO.	DATE	THE STATION IS A STANDARD N.M.S.H.C. BRASS TABLET, STAMPED "NM-367-1", SET IN TOP OF A CONCRETE POST FLASH WITH THE GROUND ON THE NORTH MEDIAN AT INTERSECTION OF SAN MATEO BLVD. AND OSUNA RD. EL. 5210.60	NO.	NO.	NO.

ENGINEER'S SEAL		REVISIONS		DESIGN	
		NO.	DATE	PE	DATE
		1	11/6/85	PE	11/6/85
		NO.	DATE	PE	DATE
		2	11/7/85	PE	11/7/85

CITY OF ALBUQUERQUE MUNICIPAL DEVELOPMENT DEPARTMENT ENGINEERING DIVISION					
TITLE: FIESTA DEL NORTE'S RIGHT TURNBAY ON SAN MATEO N.E.					
APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer	<i>[Signature]</i>	12/22/85	Liquid Waste	<i>[Signature]</i>	12/22/85
A.C.E. - Design	<i>[Signature]</i>	12/16/85	Traffic	<i>[Signature]</i>	12/16/85
A.C.E. - Hydrology	<i>[Signature]</i>	12/16/85	Water	<i>[Signature]</i>	12/16/85

DRAWING NO.	MAP NO.	SHEET	OF
2702	E-17	1	1