



SIDEWALKS EASTSIDE OF BROADWAY						DRIVEPADS EASTSIDE OF BROADWAY						
NO.	APPROXIMATE LOCATION	LENGTH	SIZE (WIDTH)	TYPE	OBSERVATIONS	LETTER	APPROXIMATE LOCATION	LENGTH	SIZE (WIDTH)	TYPE	OBSERVATIONS	
①	STARTS AT SOUTH R. OF HOUSE 914	108'	6'	BACK OF CURB	BUILD SDWK. AROUND EX. TREES BUILD SDWK. AROUND EX. STEPS	Ⓐ	DRIVEPAD IN FRONT OF ADDRESS 1402	14'				
②	STARTS AT SOUTH R. OF HOUSE 1004	50'	6'	SET BACK		Ⓑ	DRIVEPAD IN FRONT OF ADDRESS 1714	17'				
③	STARTS AT SOUTH R. LEWIS	63'	6'	SET BACK		Ⓒ	DRIVEPAD IN FRONT OF ADDRESS 1716	14'				
④	STARTS AT NORTH R. OF HOUSE 1402	89'	6'	BACK OF CURB		Ⓓ	DRIVEPAD IN FRONT OF ADDRESS 1718	15'				
⑤	STARTS AT SOUTH R. OF HOUSE 1610	111'	6'	BACK OF CURB		Ⓔ	DRIVEPAD IN FRONT OF ADDRESS 1838	13'				
⑥	STARTS AT NORTH R. OF HOUSE 1716	121'	6'	BACK OF CURB		Ⓕ	DRIVEPAD IN FRONT OF ADDRESS 1900	19'				
⑦	STARTS AT NORTH R. OF HOUSE 1838	140'	6'	BACK OF CURB		Ⓖ	DRIVEPAD IN FRONT OF ADDRESS 1904					
⑧	STARTS AT SOUTH R. OF HOUSE 1920	35'	6'	BACK OF CURB								
SIDEWALKS WESTSIDE OF BROADWAY						DRIVEPADS WESTSIDE OF BROADWAY						
⑨	STARTS AT SOUTH R. CROMWELL	130'	6'	SET BACK		Ⓗ	DRIVEPAD IN FRONT OF ADDRESS 1005	17'				
⑩	STARTS AT SOUTH R. OF HOUSE 1015	51'	6'	SET BACK		Ⓘ	DRIVEPAD IN FRONT OF ADDRESS 1007	16'				
⑪	STARTS AT SOUTH R. GARFIELD	13'	6'	SET BACK		Ⓣ	DRIVEPAD IN FRONT OF ADDRESS 1015	14'				
⑫	STARTS AT SOUTH R. OF HOUSE 1121	40'	6'	SET BACK		Ⓚ	DRIVEPAD IN FRONT OF ADDRESS 1307	16'				
⑬	STARTS AT SOUTH R. OF LEWIS	164'	4.5'	SET BACK		Ⓛ	DRIVEPAD IN FRONT OF ADDRESS 1309	17'				
⑭	STARTS AT NORTH R. OF 1217	64'	4.5'	SET BACK		Ⓜ	DRIVEPAD IN FRONT OF ADDRESS 1403	10'				
⑮	STARTS AT NORTH R. OF HOUSE 1301	152'	6'	BACK OF CURB		Ⓝ	DRIVEPAD IN FRONT OF ADDRESS 1405	13'				
⑯	STARTS AT BROADWAY END OF RETURN OF INTERSECTION W/STADIUM	121'	6'	BACK OF CURB		Ⓞ	DRIVEPAD IN FRONT OF ADDRESS 1719	18'				
⑰	STARTS AT SOUTH R. OF HOUSE 1617	63'	6'	BACK OF CURB		Ⓟ	DRIVEPAD IN FRONT OF ADDRESS 1723	17'				
⑱	STARTS AT SOUTH R. OF HOUSE 1701	225'	6'	BACK OF CURB		Ⓠ	DRIVEPAD IN FRONT OF ADDRESS 1723	16'				
⑲	STARTS AT SOUTH R. KATHRYN	51'	6'	BACK OF CURB		Ⓡ	DRIVEPAD IN FRONT OF ADDRESS 1919	16'				
⑳	STARTS AT SOUTH R. OF HOUSE 1913	50'	6'	BACK OF CURB		Ⓢ	DRIVEPAD IN FRONT OF ADDRESS 2105	18'				
㉑	STARTS AT SOUTH R. OF HOUSE 2001	250'	6'	BACK OF CURB		Ⓣ	DRIVEPAD IN FRONT OF ADDRESS 2223	30'				
㉒	STARTS AT SOUTH R. OF HOUSE 2105	55'	6'	BACK OF CURB		Ⓤ	DRIVEPAD FOR ALLEY JUST NORTH OF ETHLYN	30'				
㉓	STARTS AT SOUTH R. OF HOUSE 2215	350'	6'	BACK OF CURB		Ⓥ	DRIVEPAD IN FRONT OF ADDRESS 2301	24'				
						Ⓦ	DRIVEPAD IN FRONT OF ADDRESS 2301	14'				
						LEGEND: ■ NEW SIDEWALK □ NEW DRIVEPAD R. PROPERTY LINE R. FLOWLINE SDWK. SIDEWALK EX. EXISTING						
						CONSTRUCTION CITY ENGINEER DATE						

NOTICE TO CONTRACTORS

1. All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for herein, be constructed in accordance with the City of Albuquerque Interim Standard Specifications for Public Works Construction 1985.

2. Two (2) working days prior to any excavation, the contractor must contact Line Locating Service, 765-1234 for location of existing utilities.

3. Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.

THE FOLLOWING NOTES ALSO APPLY WHEN CHECKED

☐ All utilities and utility service lines shall be installed prior to paving.

☐ Backfill compaction shall be according to specified street use.

☐ Tack coat requirements shall be determined by the City Engineer.

☐ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.

☐ If curb is depressed for a drivepad or a handicap ramp, the drivepad or ramp shall be constructed prior to acceptance of the curb and gutter.

☐ All storm drainage facilities shall be completed prior to final acceptance.

**CITY OF ALBUQUERQUE
MUNICIPAL DEVELOPMENT DEPARTMENT
ENGINEERING DIVISION**

**TITLE: CONSTRUCT MISSING SIDEWALKS & DRIVEPADS
SOUTH BROADWAY FROM PACIFIC TO ETHLYN**

APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer	<i>[Signature]</i>	1/29/86	Liquid Waste	<i>[Signature]</i>	
A.C.E. - Design	<i>[Signature]</i>		Traffic TRANS.	<i>[Signature]</i>	1/29/86
A.C.E. - Hydrology			Water	<i>[Signature]</i>	

DRAWING NO. **2742** MAP NO. **K,L-14** SHEET **1** OF **1**

LEGEND:
— NEW SIDEWALK
□ NEW DRIVEPAD
R. PROPERTY LINE
R. FLOWLINE
SDWK. SIDEWALK
EX. EXISTING

CONSTRUCTION
[Signature]
CITY ENGINEER
DATE