

**VICINITY MAP J-14**

**NOTICE TO CONTRACTOR**

- All work detailed on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with the City of Albuquerque Interim Standard Specifications for Public Works Construction 1985.
- Two (2) working days prior to any excavation, contractor must contact Line Locating Service, 765-1234, for location of existing utilities.
- Prior to construction, the contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the contractor shall notify the engineer or surveyor so that the conflict can be resolved with minimum amount of delay.
- Two (2) working days prior to construction, contractor shall obtain a Barricading Plan and Permit through Traffic Engineering Division at 768-2780.

**THE FOLLOWING NOTES ALSO APPLY WHEN CHECKED**

- ☒ All utilities and utility service lines shall be installed prior to paving.
- ☒ Backfill compaction shall be according to specified street use.
- ☒ Tack coat requirements shall be determined by the City Engineer.
- ☒ Sidewalks and wheelchair ramps within the curb returns shall be constructed wherever a new curb return is constructed.
- ☒ If curb is depressed for a driveway or a handicap ramp, the driveway or ramp shall be constructed prior to acceptance of the curb and gutter.
- ☒ All storm drainage facilities shall be completed prior to final acceptance.

**BENCH MARK**  
2-J-14 R NORTHWEST COR.  
FOURTH & LOMAS. ELEV.  
4954.40

INSR. RAYBACA 8/2/87 J.P. HALE

APPROVED FOR RECORD DRAWINGS  
*Robert B. Smith* 9-3-87

ASST. CITY ENGINEER FIELD DATE

APPROVED FOR CONSTRUCTION  
*David J. Hummer* 10/22/86

CITY ENGINEER DATE

CITY OF ALBUQUERQUE			
APPROVALS	ENGINEER	DATE	TITLE:
D.R.C. CHAIRPERSON	<i>John H. Harte</i>	10/22/86	HANDICAPPED RAMP, SOUTHWEST CORNER THIRD & LOMAS
TRANS. DEV.	<i>David J. Hummer</i>	10/22/86	
UTILITY DEV.	<i>W.J. Williamson</i>	10/10/86	
PARKS & RECREATION	<i>Andrea Criley</i>	10/22/86	
USER DEPT.			

PROJECT NO. **3047**

MAP NO. J-14  
SHEET 1 OF 3

**LOMAS BLVD., N.W.**

Scale: 1"=10'

T.C.	E.
1	54.56 53.89
2	53.80
3	54.54 53.65

**NOTE:** All new conduit to be 2" except as noted. Tie existing conduit to P.B. as shown.

**LEGEND**

- HANDICAPPED RAMP
- NEW ARTERIAL PAVING
- EXISTING CURB & GUTTER
- NEW CONCRETE CURB & GUTTER

**NOTES:**

- DESIGN SHOWN ABOVE DOES NOT REQUIRE SIGN RELOCATION.
- CUT EXISTING IRRIGATION LINE AT INTERSECTION WITH NEW CONSTRUCTION AND RECONNECT NEW LINE AS SHOWN.
- SIGNAL EQUIPMENT RELOCATION SHOULD BE COORDINATED THROUGH TRAFFIC ENGINEERING AT 823-4008.
- ANY QUESTIONS REGARDING SUNWEST IRRIGATION LINES SHOULD BE DIRECTED TO HARVEY HENNIGAN AT 765-2322. CALLED 7/78
- CONSTRUCT SINGLE STORM INLET TYPE 'C'. MODIFY AT NORTHWEST SIDE TO PROVIDE 3/4" DROP TO GRATE INSTEAD OF 2 3/4".

**CITY OF ALBUQUERQUE**

GP 84-2

APPROVALS	ENGINEER	DATE	TITLE:
D.R.C. CHAIRPERSON	<i>John H. Harte</i>	10/22/86	HANDICAPPED RAMP, S.W. COR. THIRD & LOMAS
UTILITY DEV.	<i>W.J. Williamson</i>	10/10/86	
TRANS. DEV.	<i>David J. Hummer</i>	10/22/86	
PARKS & REC. DEPT.	<i>Andrea Criley</i>	10/22/86	

PROJECT NO. **3047**

MAP NO. J-14  
SHEET 2 OF 3

**SPLICE CABINET FOUNDATION (GAYLORD)**

3 OR MORE CONDUITS TO BE PLACED IN A LINE

WEATHERCAP CONDUIT  
2" MIN. 4" MAX.  
1/2" EXPANSION JOINT  
SIDEWALK  
3/4" X 1/6" ANCHOR BOLTS  
2" CONDUIT  
NO. 6 AT CORNERS  
4-#4 TIES

3/4" X 10' COPPERWELD GROUND ROD

CONDUIT SHALL BE GALVANIZED STEEL FROM 6" WITHIN THE FOUNDATION TO THE 8" EXTENSION ABOVE THE FOUNDATION. FOUNDATION TO BE FLUSH WITH SURFACE OF SIDEWALK.

**CITY OF ALBUQUERQUE**

APPROVALS	ENGINEER	DATE	TITLE:
D.R.C. CHAIRPERSON	<i>John H. Harte</i>	10/22/86	HANDICAPPED RAMP, SOUTHWEST CORNER THIRD & LOMAS
TRANS. DEV.	<i>David J. Hummer</i>	10/22/86	
UTILITY DEV.	<i>W.J. Williamson</i>	10/10/86	
PARKS & REC. DEPT.	<i>Andrea Criley</i>	10/22/86	
USER DEPT.			

PROJECT NO. **3047**

MAP NO. J-14  
SHEET 3 OF 3

26 30470187