

[illegible]

- ① **SoFITE®** (See Specifications for Depth and Color).
- ② **1/2" (12mm) Diameter Continuous Bead of PL Premium at Each KrasLOCK® or Channellock® Joint.**
- ③ **Apply PL Premium Adhesive to Concrete and SoFITE® Edge.**
- ④ **Optional Concrete Retainer Lip.**
- ⑤ **Concrete Depth and Strength to Specifications.**
- ⑥ **Minimum 1/2" (12mm) Fine Crushed Limestone Screenings (As Required) to Max 1/4" (6mm) Variation in Planarity When Measured With a 10' (3m) Straight Edge in any Direction.**
- ⑦ **Compacted Granular A (Type I) to 95% S.P.D. (See Specifications for Depth).**
- ⑧ **4" (100mm) Perforated Plastic or PVC Drain Tile at 16' (4.9m) On Center.**
- ⑨ **3/4" (20mm) Clear Stone.**
- ⑩ **Compacted Subgrade.**
- ⑪ **Geotextile Terrafix 200R (or Equivalent) Overlay by 12" (300mm) and Tape Joints.**
- ⑫ **Minimum 2.0% Slope - 1/4" / 12" (6mm / 300mm).**


1. Ensure subsoil drains towards perforated drain tile.
2. Install perforated drain tile at 16" (4.8m) on center as well as around the perimeter of the SoftMLE® installation
Drain to nearest storm collection system.
3. Back fill around perforated drain tile with 3/4" (20mm) clear stone to 6" (150mm) radius around drain tile.

- ① SOFT TILE KROSLOCK SAFETY SURFACING AVAILABLE THRU THE PLAYWELL GROUP. SEE DETAIL 'D' CONCRETE EDGER COLOR: TERRA COTTA
- ② PLAYWORLD SYSTEMS PLAY EQUIPMENT AVAILABLE THRU THE PLAYWELL GROUP PHONE # 899-1762. CUSTOM PLAYMAKER P22307D

COLORS:

- PLASTICS - BEIGE
- PRISMCOAT POSTS - SATINWOOD
- POWDER-COATING WALL BARRIERS - FOREST GREEN

- ③ REMOVE EXISTING PLAY EQUIPMENT, SALVAGE TO PARK MANAGEMENT. PLEASE CONTACT LEROY LUCER 857-8650.
- ④ AGE APPROPRIATE SIGN 2 TO 5 AGE GROUP.
- ⑤ AGE APPROPRIATE SIGN 5 TO 12 AGE GROUP.
- ⑥ SAFETY AREA.



CITY OF ALBUQUERQUE
PARKS & RECREATION - DESIGN & DEVELOPMENT DIVISION

NO.	DATE	REMARKS	BY
REVISIONS			
DESIGN			
DESIGNED BY	JSP	DATE	1/23/03
DRAWN BY	JSP	DATE	1/23/03
CHECKED BY	GAH	DATE	1/23/03

CITY OF ALBUQUERQUE PARKS & RECREATION DEPARTMENT DESIGN & DEVELOPMENT			
TITLE: ACADEMY HILLS PARK PLAY AREA RENOVATION CONSTRUCTION PLAN			
Design Review Committee	City Engineer Approval	Last Design Updates	Mo/Day/yr. Mo/Day/yr.
CITY PROJECT NO. 488891		ZONE MAP NO. K-22-Z	SHEET 1 OF 1

[illegible]