



LEGEND

TC=TOP CONC. CURB
FL=FLOW LINE CONC. CURB
TAC = TOP ASPHALT CURB
FLA = FLOW LINE ASPHALT CURB
FIREHYDRANT
FIREHYDRANT
SANITARY SEWER MANHOLE
CONTROL VALVE
TREE
DROP INLET
WATER METER
EXISTING GATE VALVE
NEW GATE VALVE



ZONE ATLAS NO. D-18

<NOTICE TO CONTRACTORS>

1. All work shown on these plans to be performed under contract shall, except as otherwise stated or provided for hereon, be constructed in accordance with the City of Albuquerque Standard Specifications for Public Works Construction, 1986 Edition as amended through update No. 6.
2. Two (2) working days prior to any excavation the contractor must contact New Mexico One Call System (260-1990) for location of existing utilities.
3. Prior to construction, the Contractor shall excavate and verify the horizontal and vertical locations of all obstructions. Should a conflict exist, the Contractor shall notify the engineer or surveyor immediately so that the conflict can be resolved with a minimum amount of delay.
4. Three (3) working days prior to beginning construction, the contractor shall submit to the Construction Coordination Division a detailed construction schedule. Two (2) working days prior to construction, the Contractor shall obtain a barricading permit from the Construction Coordination Division. Contractor shall notify Barricade Engineer (765-2551) prior to occupying an intersection. Refer to Section 19 of the General Conditions of the Standard Specifications.
5. All street striping altered or destroyed shall be replaced in kind by Contractor to location and in kind as existing or as indicated by this plan set.
6. Contractor shall notify the engineer not less than seven (7) days prior to starting work in order that the engineer may take necessary measures to insure the preservation of survey monuments. Contractor the preservation of survey monuments. Contractor shall not disturb permanent survey monuments without the consent of the Engineer and out the consent of the engineer and shall notify the engineer and bear the expense of replacing any that may be disturbed without permission. Replacement shall be done by the City Survey Section. When a change is made in the finish elevations of the pavement of any roadway in which a permanent survey survey monument is located, Contractor shall, at his own expense, adjust the monument cover to the new grade otherwise specified. Refer to Section 4.4 of the General Conditions of the Standard Specifications.
7. Any existing infrastructure altered by the contractor shall be repaired per City of Albuquerque standards.
8. Any work affecting an arterial roadway requires twenty-four (24) hour construction.
9. Five (5) working days prior to construction, Contractor shall contact Water Systems (857-8200) for implementation of the Valve Shut-off Plan. Only City of Albuquerque employees designated by Water Systems are permitted to perform valve shut-off operations.

For Information Only

FRANK D. LOVLELADY, P.E.
300 ALAMOSA N.W.
ALBUQUERQUE, NM 87107
(505)345-2267

INSTALLATION OF TWO FIRE HYDRANTS & FIRE LINE FOR
QUALITY SUITES HOTEL
725 SAN ANTONIO BOULEVARD, N.E.
ALBUQUERQUE, NEW MEXICO

DATE	SHEETS	CITY ENGINEER	DATE	USER DEPARTMENT	DATE	USER DEPARTMENT	DATE
ENGINEERS STAMP AND SIGNATURE			APPROVALS		ENGINEER	DATE	*****
			D.R.C. Chairman		<i>Billy G. Kunkley</i>	7-16-96	APPROVED FOR CONSTRUCTION
			Transportation		<i>Billy G. Kunkley</i>	6-28-96	
			Water/Wastewater		<i>John A. Smith</i>	7-1-96	
			Hydrology		<i>John A. Smith</i>	7-1-96	
			Parks				
			Const.Mgmt.				 City Engineer 8/3/96
CITY PROJECT NO.			547481		SHEET 1 OF 1		