



IRRIGATION LEGEND

- ▲ RAINBIRD #1401 .25 GPM FULL CIRCLE TRICKLE PATTERN BUBBLER (SEE COA STANDARD DETAIL DRAWINGS: 2710, 2711, 2711-A & 2712)
- ⊕ WEATHERMATIC #11024FCR-10 1" PLASTIC ELECTRIC VALVE WITH FLOW CONTROL (SEE COA STANDARD DETAIL DRAWING: 2703)
- Ⓢ SCORPIO AC - 8 STATION CONTROLLER WITH INTERSPEC ENCLOSURE, KEYPAD AND DOMED ANTENNA. UNIT SHALL COMMUNICATE ON COA RADIO FREQUENCY (WIDE BAND). (SEE DETAIL DRAWING: B/4 & D/4)
- Ⓟ FEBCO #860U 3/4" REDUCED PRESSURE BACKFLOW PREVENTER INSTALLED IN HOTBOX #HR1 "HOT ROK" HEATED AND INSULATED BACKFLOW DEVICE ENCLOSURE. (SEE DETAIL DRAWING: C/4)
- Ⓜ 3/4" MASTER METER ASSEMBLY (FLOW METER WITH OUTPUT REGISTER)
- Ⓜ 3/4" WATER METER ASSEMBLY (SEE COA STANDARD DETAIL DRAWING: 2362 OR 2363)
- Ⓛ ELECTRICAL AC POWER SOURCE - PEDISTAL LOCATED BETWEEN 6401 AND 6405 PINE PARK PLACE
- SCH.40 PVC SOLVENT WELD CAP (PIPE SIZE)
- MAINLINE PIPING - 1 1/4" SCH.40 PVC SOLVENT WELD
- LATERAL PIPING - SCH.40 PVC SOLVENT WELD (SIZE INDICATED ON PLAN - UNSIZED PIPE IS 3/4")
- ===== SLEEVE PIPING - CLASS 200 PVC SOVENT WELD (TWO SIZES LARGER THAN PIPE TO BE SLEEVED)
- ELECTRICAL WIRE ROUTE

CONTROLLER STATION NUMBER
 FLOW IN GALLONS PER MINUTE

Mountain West GolfScapes, Inc.
 IRRIGATION DESIGNERS & CONSULTANTS
 2190 HWY 304 BELEN, NM 87002
 PHONE: (505) 861-1535
 FAX: (505) 864-3212
 E-MAIL: irrservices@aol.com
 WEB SITE: www.irrigationservicesinc.com

Irrigation Services
 IRRIGATION DESIGNERS & CONSULTANTS

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

CITY OF ALBUQUERQUE
 PARKS AND RECREATION DEPARTMENT
 DESIGN DEVELOPMENT DIVISION

TITLE: **PROTOTYPE MEDIAN LANDSCAPES**
 MCKINNEY MEDIANS: PINE PARK PLACE TO HARPER
 AS-BUILT IRRIGATION SYSTEM

Design Review Committee City Engineer Approval

MO./DAY/YR.
 05/05/05
 05/14/05

City Project No. 754604

Zone Map No. E-10

Sheet 1 of 1