











IRRIGATION LEGEND POE #1														
	EXISTING WATER METER TO REMAIN.													
	IRRIGATION MAIN LINE, 1", SCH 40 BELL END, SOLVENT WELD PVC. DEPTH OF BURY SHALL BE 28".													
	LATERAL PIPING, SCH. 40, BELL END, SOLVENT WELD PVC. DEPTH OF BURY, 18". SIZE PER PLAN.													
	ISOLATION VALVE													
	PRESSURE VACUUM BREAKER (PVB) BACKFLOW PREVENTER AND MASTER VALVE ASSEMBLY WITH BALL VALVES, INSTALLED IN INSULATED ENCLOSURE AND FLOW METER INSTALLED IN VALVE BOX PER DETAIL C/4. SIZE OF PVB, MASTER VALVE, AND FLOW METER SHALL BE SAME AS LINE SIZE. ENCLOSURE SHALL BE SIZED TO ACCOMMODATE SIZE OF PVB AND MASTER VALVE ASSEMBLY.													
	REMOTE CONTROL VALVE ASSEMBLY, RAINBIRD FEB PLASTIC BODY 24-VOLT AUTOMATIC VALVE, SIZE PER PLAN. INSTALL PER C.O.A. DRAWING NO. 2103.													
		<p>■ ● ▲</p> <p> IRRINET M DC 12 STATION CONTROLLER WITH SOLAR ENCLOSURE.</p>												
		<p>PRESSURE COMPENSATING BUBBLER ASSEMBLIES, RAIN BIRD 1400 SERIES, AS FOLLOWS: INSTALL PER C.O.A. DRAWING NUMBERS 2110, 2111, 2111-A AND 2112.</p> <table border="1"> <thead> <tr> <th>MODEL NO.</th> <th>GPM</th> <th>F81</th> </tr> </thead> <tbody> <tr> <td>1401</td> <td>25</td> <td>30</td> </tr> <tr> <td>1402</td> <td>50</td> <td>30</td> </tr> <tr> <td>1404</td> <td>10</td> <td>30</td> </tr> </tbody> </table>	MODEL NO.	GPM	F81	1401	25	30	1402	50	30	1404	10	30
MODEL NO.	GPM	F81												
1401	25	30												
1402	50	30												
1404	10	30												
IRRIGATION NOTES:														
<p>1. INSTALL 6'X6'X8" CONCRETE PAD FOR PVB/MASTER VALVE AND ENCLOSURE.</p> <p>2. PROVIDE INSULATED ENVELOPE FOR PVB/MASTER VALVE.</p>														



	5604 Wilshire Ave NE Albuquerque, NM 87113 (505)822-8722		NO. DATE		DESIGNED BY ML	DRAWN BY ML	CHECKED BY LS	
CITY OF ALBUQUERQUE CAPITAL IMPLEMENTATION PROGRAM DEPARTMENT OF MUNICIPAL DEVELOPMENT								
PROTOTYPE MEDIAN AND INTERSTATE LANDSCAPES FY-13A WYOMING: MONTGOMERY TO OSUNA: WORK ORDER #7 IRRIGATION PLAN								
Design Review Committee		City Engineer Approval		Last Design Update	Mo./Day/Yr.		Mo./Day/Yr.	
City Project No.		Zone Map No.		Sheet				
755309		F-19				1 OF 2		

[illegible]