

NOTICE TO CONTRACTORS

- An excavation/barricade permit will be required before beginning any work within City, County, or Village right-of-way. An approved copy of these plans must be submitted at the time of application for these permits.
- All work detailed on these plans to be done, except as otherwise stated or provided hereon, will be constructed in accordance with "City of Albuquerque Interim Standard Specification for Public Works Construction, 1986," latest revision. Two working days prior to any excavation, the contractor must contact Line Locating
- Service, 260-1990, for location of existing utilities. 4. Prior to construction, the contractor will excavate and verify the horizontal and vertical locations of all construction. Should a conflict exist, the contractor will notify the Construction Engineer so that the conflict can be resolved with a
- minimum amount of delay. The contractor will be responsible for coordinating the water shutoff with the Water Division seven working days prior to construction.
- 6. The contractor will be responsible for performing soil density tests as required

SCANNED BY PLANNING

| by the City of Albuquerque. | | | |
|---|------------------|---------|--|
| APPROVALS FOR | NAME | DATE | TITLE OF PROJECT: |
| DESIGN: UTILITY DEVELOPMENT | William J. Balch | 2/13/06 | MILLER VAN LINES 10001 BELL AVE. S.E. |
| CONSTRUCTION: CONSTRUCTION ENGINEER | James Alling | ./=9/0) | FIRE SPRINKLE TAP |
| ACCEPTANCE: CONSTRUCTION | | | PROJECT NO. 7783.81 ZONE ATLAS |

INSPECTOR

SHEET 3 OF 5







