

792081

CITY OF ALBUQUERQUE
PRIVATE FP WATER LINE INSTALLATION

PROJECT SITE

CONTACT PERSONS

PROPERTY OWNER FOR LOTS 2-B-2 AND 2-B-3 OF PLAT OF FAIRVIEW ADDITION ISLAMIC CENTER OF N.M. (256-1450)	CONTRACTOR TUT CONSTRUCTION INC. ROYCE SMITH (202-1184)	ENGINEER BJM CONSULTING BERNIE J. MONTOYA C.E. (250-7719)
--	---	---

LEGAL DESCRIPTION OF PROPERTY AND ADDRESS:
TRACTS 2-B-2 AND 2-B-3 FAIRVIEW ADDITION 1100 YALE BOULEVARD S.E.

NOTICE TO CONTRACTORS

- An excavation/barricade permit will be required before beginning any work within City, County, or Village right-of-way. An approved copy of these plans must be submitted at the time of application for these permits.
- All work detailed on these plans to be done, except as otherwise stated or provided hereon, will be constructed in accordance with "City of Albuquerque Interim Standard Specification for Public Works Construction, 1986," latest revision.
- Two working days prior to any excavation, the contractor must contact New Mexico Division seven (7) working days prior to construction.
- The contractor will be responsible for performing soil density tests as required by the City of Albuquerque.

APPROVALS FOR	NAME	DATE	TITLE OF PROJECT:
DESIGN UTILITY DEVELOPMENT	<i>William D. Balch</i>	9/14/06	PRIVATE FIRE PROTECTION WATER LINE
CONSTRUCTION ENGINEER	<i>RS-BULLIS</i>	12/19/2006	1100 YALE BOULEVARD S.E.
ACCEPTANCE CONSTRUCTION INSPECTOR	<i>Jim Cant</i>	12/15/06	PROJECT NO. 792081 SHEET 1 OF 4
			ZONE ATLAS L-15

CITY OF ALBUQUERQUE
PRIVATE FIRE WATER LINE INSTALLATION PROCEDURE

The following procedure has been established to expedite the installation of fire hydrants required as a result of a subdivision or a service request and to insure proper record keeping.

This procedure eliminates the need for a design by a licensed professional engineer, the processing of a SIA, and the need for a formal DRC and Work Order Process. It is intended for use only when no other construction of public infrastructure is required and the City Engineer/Utility Development determines that the normal design, review, and Work Order Process is not required. This procedure is for construction within or adjacent to local streets.

- Owner or contractor: submit plans using the attached City Standard format to the City Engineer/Utility Development at One Stop (Plaza del Sol, 600 2nd St. NW) for review and approval. Plans must include: Zone Atlas pg number, legal description, and location of fire hydrant(s) relative to nearest property corner or intersection. Must provide: one set of original mylars, 4 copies of the originals, and a fee of \$150 (checks only) FOR EACH hydrant or fire line. Provide name & phone no. of Contractor, Designer/Engineer, and name and phone no. of the Owner of the Project. Provide Shut-Off Plan if required.
- City Engineer/Utility Development will obtain new project number from the DRC Master Scheduler.
- City Engineer/Utility Development will forward the approved plan to Construction Division for review and to assign a city inspector to the project.
- Construction Division will forward a copy of the approved plan to the owner or owner's contractor. Prior to construction, the contractor must obtain the necessary permits from the City, County and/or Village. A copy of the approved design must accompany the request for a permit. The contractor must be properly licensed and bonded to do work on the City Water System. This must be verified through the City's Permits office.
- Any soil compaction, asphalt, concrete, or any material testing required by the standard specifications shall be done by the contractor at no expense to the City.
- Upon construction of the fire hydrant the contractor will obtain the city inspector's approval of the construction, the Inspector will sign the original which will then be forwarded to the Maps & Records Division for As-Built processing.
- The Construction Engineer will provide the City Engineer/Utility Development and DRC Master Scheduler written certification that the construction has been completed and accepted.
- If the construction does not pass inspection and a revised design is required, then steps "A-E" must be reinstated. No plat will be signed or meter released until the construction has been accepted by the Construction Division.

PROJECT NO. 792081	ZONE ATLAS L-15	TITLE: 1100 YALE BOULEVARD S.E.
SHEET 2 OF 4		

CITY OF ALBUQUERQUE
PRIVATE FIRE PROTECTION WATER LINE
WATER VALVE SHUT-OFF PLAN

WATER VALVE SHUT-OFF PLAN NOTES

- THE FOLLOWING VALVES MAY NEED TO BE CLOSED TO FACILITATE CONNECTION: VALVES # 252, #253, #202, AND # 151
- WATER SYSTEMS PERSONNEL SHALL PERFORM ALL SHUT-OFF, THE CONTRACTOR SHALL NOT OPERATE ANY VALVES THAT MAY AFFECT SYSTEM OPERATIONS.
- THE CONTRACTOR REQUEST A WATER SHUT-OFF IN WRITING, A MINIMUM OF SEVEN (7) DAYS ADVANCE PER STANDARD COA PROCEDURES

TITLE OF PROJECT:
PRIVATE FIRE PROTECTION
WATER LINE

1100 YALE BOULEVARD S.E.
PROJECT NO. 792081
SHEET 3 OF 4

ZONE ATLAS
L-15

2 3 4 5 6 7 8 9 10 11 12 13 14 15
316-792081-01-001

SCANNED BY
PLANNING

PRIVATE FIRE WATER LINE INSTALLATION

ISLAMIC CENTER OF NEW MEXICO

YALE BOULEVARD S.E.

RIGHT-OF-WAY LINE

52' F.F.

83' R.O.W.

6" C.I. WATER LINE

8" VCP

20' EASEMENT

1 2 3

PIPE LEGEND

PROPERTY LINE

WATER LINE

SAS LINE

1 FIELD LOCATE CITY MAIN
TIE TO EXISTING 6" C.I. MAIN

2 MAKE DRY CONNECTION. INSTALL
6"x6" TEE AND 6" GATE VALVE

3 THIS WORK ORDER IS ONLY FOR
CONSTRUCTION IN THE PUBLIC R.O.W.

PROJECT NO. 792081

SHEET 4 OF 4

ZONE ATLAS
L-15

TITLE: PRIVATE FIRE PROTECTION WATER LINE
1100 YALE BOULEVARD S.E.