



Excavate approximately 114'x7'x1.5' of unsuitable material and replace with base course to within 4" of finish grade.