

SAN PASQUALE AND CHACOMA  
INTERSECTION MODIFICATION

SHEET 1 OF 3  
PREPARED 12/27/17

GENERAL NOTES

1) CONTRACTOR WILL BE REQUIRED TO SUBMIT AS-BUILT DRAWINGS ONCE CONSTRUCTION IS COMPLETE.

- KEYED NOTES PROJECT MANAGER- JOSHUA ELLISON  
505-768-3657
- 1) REMOVE SHRUB.
  - 2) SAWCUT AND REMOVE CONCRETE SIDEWALK AND/OR CURB AND GUTTER TO NEAREST JOINT.
  - 3) SAWCUT AND DISPOSE EXISTING ASPHALT PAVEMENT, AND/OR MEDIAN CONCRETE CURB TO CONSTRUCT PEDESTRIAN REFUGE/WHEELCHAIR ACCESS RAMP.
  - 4) PROTECT EXISTING UTILITY MANHOLE/ VALVE.
  - 5) EXISTING VALLEY GUTTER TO REMAIN.
  - 6) EXISTING STORM DRAIN INLET TO REMAIN.
  - 7) REMOVE AND RELOCATE STOP SIGN





SAN PASQUALE AND CHACOMA  
INTERSECTION MODIFICATION

SHEET 2 OF 3  
PREPARED 12/27/2017

- GENERAL NOTES
- 1) ALL SLOPES SHOWN HEREON SHALL BE CONSIDERED MAXIMUMS.
  - 2) ALL CROSS SLOPES SHALL NOT BE GREATER THAN 1.5%.

- KEYED NOTES PROJECT MANAGER- JOSHUA ELLISON  
505-768-3657
- 1) INSTALL DETECTABLE WARNING SURFACE.
  - 2) INSTALL 24" WHITE THERMOPLASTIC STRIPES FOR PEDESTRIAN CROSSWALK. PROJECT MANAGER SHALL VERIFY LAYOUT BEFORE PERMANENT STRIPING IS INSTALLED.
  - 3) MATCH EXISTING SURFACE, CURB, SIDEWALK, OR FLOWLINE ELEVATION.
  - 4) ADJUST MANHOLE AND/OR VALVE COVER.
  - 5) PAINT CURB YELLOW.
  - 6) RELOCATE STOP SIGN.
  - 7) INSTALL 4" THICK CONCRETE SIDEWALK TO TIE EXISTING SIDEWALK INTO NEW WHEELCHAIR ACCESS RAMP.
  - 8) EXISTING STORM DRAIN INLET TO REMAIN.
  - 9) EXISTING VALLEY GUTTER TO REMAIN.
  - 10) UTILITY MANHOLE/ VALVE (TYP.) TO REMAIN.
  - 11) INSTALL 4" WHITE THERMOPLASTIC STRIPING.
  - 12) CONSTRUCT WHEELCHAIR ACCESS REFUGE- APPROXIMATELY 75 SQ. FT..
  - 13) INSTALL ASHLER PATTERNED MEDIAN CONCRETE. COLOR SHALL BE SAN DIEGO BUFF- APPROXIMATELY 45 SQ. FT..
  - 14) CONSTRUCT WHEELCHAIR ACCESS RAMP PER COA DRAWING 2441
  - 15) MATCH LIP OF NEW GUTTER TO EXISTING. ASPHALT PATCH/REPAIR SHALL BE CONSIDERED INCIDENTAL.
  - 16) INSTALL MEDIAN CURB & GUTTER PER COA DETAIL 2415B.
  - 17) INSTALL ASHLER PATTERNED MEDIAN CONCRETE. COLOR SHALL BE SAN DIEGO BUFF- APPROXIMATELY 45 SQ. FT..
  - 18) CONSTRUCT HEADER CURB.





