PROJECT 1000633

REFUSE NOTES

1. 8" SPLIT FACE CMU BLOCK WALL FINISH - COLOR TO MATCH BLDG.
2. FINISH GRADE
3. MASONRY CAP
4. 1- #5 BAR CONT. @ BOTTOM OF 2' TURNDOWNS, 2- #5 BARS @ BOTTOM OF 12" TURNDOWNS
5. 2- #5 BARS @ TOP KNOCK OUT CMU BOND BEAM AND 5- #5 BARS CONT. @ BOTTOM OF TURNDOWN UNDER WALLS, PROVIDE #3 BARS @ 52" O.C. VERTICAL @ OUT REINFORCED CELLS, DURAWALL @ 16" O.C. HORIZONTAL
6. 1/2" EXPANSION JOINT MATERIAL
7. 6" CONCRETE SLAB, 4000 PSI, 3/4" AGGREGATE WITH 6"x6" - 10/10 WWM (W 12" TURNDOWN EDGES UNDER CMU WALLS (W/ 2-#5 CONT.) AND @ TURNDOWN @ APRON (W/ 1-#5 CONT.)
8. 6" CONCRETE APRON, 4000 PSI, 3/4" AGGREGATE WITH 6"x6" - 10X10 (W4.0 W/ 6" TURNDOWN EDGES (W/1-#5 CONT.) ALL AROUND EXCEPT 12'-0 @ ENTRY (W/2-#5 CONT.)
9. 24" CONCRETE FILLED PIPE IN 18" DIA. X 2'-6" DEEP CONC. FOOTING, PAINT TO MATCH ENCLOSURE COLOR
10. ASPHALT PAVING - SEE PAVING SECTION
11. WOOD GATE PAINTED COLOR TO MATCH BUILDING PROVIDE DROP ANCHORS @ EACH LEAF AND ALL NECESSARY ITEMS FOR A COMPLETE ASSEMBLY



REFUSE ENCLOSURE
NOT TO SCALE



3 BICYCLE RACK
SCALE: 3/4"=1'-0"



2 TYPICAL LIGHT POLE
SCALE: 1"=10'-0"

ROOFTOP EQUIPMENT NOTE:
ALL HVAC EQUIPMENT SHALL BE LOWER THAN BUILDING PARAPET HEIGHTS OR OTHERWISE SCREENED

LIGHTING NOTE
LIGHTING TO BE BUILDING MOUNTED AND FROM POLES AS INDICATED IN KEYED NOTES. AREA LIGHTING INCLUDING PARKING AND WALKS SHALL BE ARRANGED SO THAT THE LOCATION OF THE LIGHTING FIXTURE TOGETHER WITH ITS CUTOFF ANGLE SHALL BE SUCH THAT IT DOES NOT DIRECTLY SHINE ON ANY PUBLIC R.O.W. IT SHALL NOT HAVE AN OFFSITE LUMINANCE GREATER THAN 1000 FOOTLAMBERTS AND IT SHALL NOT HAVE AN OFFSITE LUMINANCE GREATER THAN 200 FOOTLAMBERTS MEASURED FROM ANY PRIVATE PROPERTY IN A RESIDENTIAL ZONE.





5 SITE- LOT 7 & 8
1"=20'-0"

KEYED NOTES

1. HANDICAP SIGN - 2 REQUIRED, - SEE DETAIL
2. LIGHT POLE - SEE DETAIL
3. NEW CONCRETE PERMACURB TYPICAL
4. NEW SIDEWALK TYPICAL - RAISED 6" ABOVE ASPHALT PARKING SURFACE
5. NEW PARKING BUMPER - 2 REQUIRED
6. STANDARD DUTY ASPHALT PAVING TYPICAL, SEE PAVING SECTION
7. BIKE RACK - SEE DETAIL
8. SLOPE RAMP UP @ 1" PER FOOT SLOPE OR 8" IN 6'-0" IN DIRECTION SHOWN
9. NEW REFUSE ENCLOSURE, SEE DETAIL
10. NEW 6' WIDE SIDEWALK PER C.O.A. STANDARDS.
11. EXISTING TELEPHONE/CABLE PEDESTALS, VERIFY EXACT LOCATION PRIOR TO CONSTRUCTION
12. SHARED ACCESS EASEMENT
13. EXISTING SIDEWALK
14. EXTRUDED ASPHALT CURB
15. "FIRE LANE FOR FIRE DEPARTMENT ACCESS ONLY, TO BE PAINTED RED AND LABELED "FIRE LANE - NO PARKING" IN 4" HIGH BLOCK LETTERS EVERY 20'-0" ON FACE OF CURB.

GENERAL NOTES

A. VERIFY ALL CONDITIONS PRIOR TO CONSTRUCTION.

GENERAL NOTES - CITY REQUIRED

A. "THE RESPONSIBLE PARTY MUST RECTIFY ALL UNAPPROVED CONSTRUCTION RESULTING FROM ERRORS ON THE APPROVED SITE PLAN"
B. THIS SITE PLAN HAS BEEN APPROVED AND ACCEPTED BY ALL PARTIES. ANY FIELD CHANGES NOT EXCEPTED BY THE TRAFFIC ENGINEER AFTER APPROVAL WILL RESULT IN: (1) UNTIMELY DELAY OF INITIAL INSPECTION FOR TEMPORARY CERTIFICATE OF OCCUPANCY IN ORDER TO CORRECT UNAPPROVED WORK, AND (2) INCREASE IN CONSTRUCTION COST TO RESPONSIBLE PARTIES.
C. ALL ASPHALT AND CONCRETE CONSTRUCTION MUST BE 100% COMPLETE BEFORE INITIAL INSPECTION FOR TEMPORARY C.O. WILL BE SCHEDULED.
D. ALL SIDEWALK AND C&G IN DISREPAIR WILL BE REMOVED AND REPLACED.
E. CONSTRUCT DRIVEPAD PER CITY OF ALBUQUERQUE STANDARD DETAIL DWG. NO. 2425
F. CONTRACTOR MUST BE MADE AWARE THAT ANY AGREEMENT WITH THE OWNER STATING PORTIONS OF THIS BUILDING PERMIT WORK TO BE COMPLETED BY THE OWNER, OR A REPRESENTATIVE, WILL MEAN CERTIFICATE OF OCCUPANCY WILL NOT BE ISSUED UNTIL ALL WORK IS FINISHED.
G. CERTIFICATION BY THE DESIGNER OF RECORD, REQUIRED BY THE TRANSPORTATION SECTION, NEEDS TO STATE THAT THIS SITE WAS CONSTRUCTED IN ACCORDANCE WITH THE TRAFFIC CIRCULATION LAYOUT (TCL) BEFORE C.O. IS RELEASED.

BUILDING LEGEND

OFFICE BUILDING	6842 SQ.FT.
PARKING REQUIRED:	OFFICE = 1 PER 200 S.F. = 35 SPACES (2 HC. SPACES)
PARKING PROVIDED:	85 SPACES PROVIDED (2 HC. SPACES PROVIDED)
BICYCLE PARKING:	4 SPACES NEEDED, 5 SPACES PROVIDED
LANDSCAPING REQUIRED:	BLDG. SITE = 34,428 S.F. - 6842 S.F. (BLDG. AREA) = 27586 S.F. NET LOT AREA *15% = 4137 S.F.
LANDSCAPING PROVIDED:	12267 S.F.

THIS PLAN IS CONSISTENT WITH THE CONCEPTS OF THE ORIGINAL JOURNAL CENTER SITE PLAN APPROVED BY THE ENVIRONMENTAL PLANNING COMMISSION ON AUGUST 16, 1980 (AX-74-15, Z-74-80-2) AND THE IP ZONE.

IT CONFORMS WITH THE COMMENTS RENDERED BY THE DEVELOPMENT REVIEW BOARD ON 6/25/03 AS REFLECTED IN DRB 03-00987

Sheran Matson 6/25/03
PLANNING DIRECTOR | DATE

Project Number: 1000633
Application Number: 03-00987

DRB SITE DEVELOPMENT PLAN APPROVAL:

TRAFFIC ENGINEERING, TRANSPORTATION DIVISION	DATE 6-25-03
UTILITIES DEVELOPMENT	DATE 6-25-03
PARKS AND RECREATION DEPARTMENT	DATE 6/25/03
CITY ENGINEER	DATE 6/25/03
* ENVIRONMENTAL HEALTH DEPARTMENT - CONDITIONAL	DATE 6-23-03
SOLID WASTE MANAGEMENT	DATE 6/25/03
DRB CHAIRPERSON, PLANNING DEPARTMENT	DATE

AFD PLANS CHECKING OFFICE
924-3611
APPROVED/DISAPPROVED
HYDRANT(S) ONLY
SIGNATURE & DATE 7.1.03

RADIUS LEGEND

1 2' RADIUS	6 15' RADIUS
2 5' RADIUS	7 20' RADIUS
3 4' RADIUS	8 25' RADIUS
4 5' RADIUS	9 30' RADIUS
5 10' RADIUS	10 50' RADIUS

PARKING TYPES & ISLAND DETAILS



revisions

Job title
NM CREDIT UNION LEAGUE
4201 WOLCOTT AVENUE
ALBUQUERQUE, NEW MEXICO

PROJECT MANAGER	job no	date
JORGE DE LA TORRE, AIA	25002	5-19-03
sheet title		by
SITE DEVELOPMENT PLAN FOR BUILDING PERMIT		STN

STATE OF NEW MEXICO — JORGE DE LA TORRE NO. 9291 — 6/13/03 — REGISTERED

de la torre architects, pa. aia
2400 louisiana blvd ne
building 3 / suite 110
albuquerque nm 87110 / 505-883-7918

sheet - 2
C
of - 28



PLANT LEGEND

- BERRINDA ASH (H) 8
  Fraxinus velutina
  2" Cal.
- MUGO PINE 2 (M)
  Pinus mugo
  5 Gal.
- SILVERBERRY (M) 20
  Elaeagnus pungens
  5 Gal. 100sf
  2000 sf
- CURLLEAF MOUNTAIN MAHOGANY (L) 11
  Carcarpus ledifolius
  5 Gal. 64SF
  704 sf
- THREE-LEAF SUMAC (L) 9
  Rhus trilobata
  5 Gal. 36sf
  324 sf
- BEARGRASS 22 (M)
  Nolina microcarpa
  5 Gal. 36SF
  792 sf
- ENGLISH LAVENDER (M) 56
  Lavandula angustifolia
  5 Gal. 9SF
  803 sf
- GREYLEAF COTONEASTER 42 (M)
  Cotoneaster buxifolius
  5 Gal. 81SF
  Symbol indicates 3 plants
  3402 sf
- SANTA ANA TAN GRAVEL WITH FILTER FABRIC
- OKLAHOMA REDBUD (M) 3
  Cercis reniformis
  2" Cal.
- THORNLESS HAWTHORN (m) 1
  Crataegus crus-galli inermis
  2" Cal.
- SOTOL (L) 7
  Dasylirion wheeleri
- POWIS CASTLE SAGE (L) 12
  Artemisia x powis castle
  1 Gal. 25sf
  300 sf
- APACHE PLUME (L) 19
  Fallugia paradoxa
  5 Gal. 25sf
  475 sf
- ARP. ROSEMARY (M) 20
  Rosmarinus officianalis cultivars
  5 Gal. 36sf
  720 sf
- THREADGRASS (L) 25
  Stipa tennuisima
  1 Gal. 4sf
  100 sf
- WILDFLOWER 66 (L)
  1 Gal. 4sf
  264 sf
  Including but not limited to: Indian Blanketflower, Purple Coneflower, Torch Lily, Mexican Evening Primrose, Penstemon and Lamb's Ear
- BOULDERS 4

LANDSCAPE CALCULATIONS

NET LANDSCAPE AREA		
TOTAL LOT AREA	34499	square feet
TOTAL BUILDINGS AREA	6822	square feet
OFFSITE AREA	976	square feet
NET LOT AREA	26701	square feet
LANDSCAPE REQUIREMENT	15%	
TOTAL LANDSCAPE REQUIREMENT	4005	square feet
TOTAL LANDSCAPE PROVIDED	12887	square feet
GROUNDCOVER REQ.	75%	square feet
TOTAL GROUNDCOVER REQUIREMENT	9665	square feet
TOTAL GROUNDCOVER PROVIDED	9684	square feet
TOTAL BED PROVIDED	12887	square feet
TOTAL SOD PROVIDED	0	square feet
TOTAL NATIVE SEED PROVIDED	0	square feet

GRAPHIC SCALE
20 10 0 10 20
SCALE: 1"=20'

LANDSCAPE NOTES:
Landscape maintenance shall be the responsibility of the Property Owner.

It is the intent of this plan to comply with the City Of Albuquerque Water Conservation Landscaping and Water Waste Ordinance planting restriction approach.

Approval of this plan does not constitute or imply exemption from water waste provisions of the Water Conservation Landscaping and Water Waste Ordinance. Water management is the sole responsibility of the Property Owner.

All landscaping will be in conformance with the City of Albuquerque Zoning Code, Street Tree Ordinance, Pollen Ordinance, and Water Conservation Landscaping and Water Waste Ordinance. In general, water conservative, environmentally sound landscape principles will be followed in design and installation.

Plant beds shall achieve 75% live ground cover at maturity.

S.A. Tan Gravel over Filter Fabric shall be placed in all landscape areas which are not designated to receive native seed.

IRRIGATION NOTES:
Irrigation shall be a complete underground system with Trees to receive (5) 1.0 GPH Drip Emitters and Shrubs to receive (2) 1.0 GPH Drip Emitters. Drip and Bubbler systems to be tied to 1/2" polypipe with flush caps at each end.

Run time per each drip valve will be approximately 15 minutes per day, to be adjusted according to the season.

Point of connection for irrigation system is unknown at current time and will be coordinated in the field.

Irrigation will be operated by automatic controller. Location of controller to be field determined and power source for controller to be provided by others.

Irrigation maintenance shall be the responsibility of the Property Owner.

FINAL LANDSCAPING LAYOUT AND DESIGN TO BE DETERMINED UPON RECEIPT OF FINAL GRADING PLAN.

The Hilltop
LANDSCAPE ARCHITECTS & CONTRACTORS
Cont. Lic. #26458
7909 Edith N.E.
Albuquerque, NM 87184
Ph. (505) 898-9690
Fax (505) 898-7737
cmd@hilltoplandscaping.com

All creative ideas contained Herein remains the property of The Hilltop Landscape Architects and Contractors and are protected by copyright laws. This is an original design and must not be released or copied, unless applicable fees have been paid or job order placed.

revisions

job title
NM CREDIT UNION LEAGUE
4201 WOLLCOTT
ALBUQUERQUE, NEW MEXICO

PROJECT MANAGER	job no.	date
JORGE DE LA TORRE, AIA	23008	4-25-03
sheet title: LANDSCAPE PLAN		by: JES

6-12-03

de la torre architects, p.a.
2400 louisiana blvd ne
building 3 / suite 110
albuquerque n.m. 87110 / 505 · 883 · 7918

sheet 3
L-1
of 25

E:\Drawings\COMMERCIAL\NM Credit Union League\LS-12-03\NT-LS-01.dwg, 06/12/2003 10:53:41 AM



EAST ELEVATION
SCALE: 1/8"=1'-0"

NORTH ELEVATION
SCALE: 1/8"=1'-0"

SOUTH ELEVATION
SCALE: 1/8"=1'-0"

WEST ELEVATION
SCALE: 1/8"=1'-0"

KEYED NOTES

1. STUCCO SYSTEM TYPICAL ALL EXTERIOR SURFACES.
2. KAWNEER STOREFRONT SYSTEM. CLEAR ANODIZED FRAME, LIGHT BRONZE GLAZING.
3. PREMISE IDENTIFICATION SIGN SHALL CONTRAST W/ BACKGROUND AND BE VISABLE FROM THE STREET. 5 SQUARE FEET OF SIGNAGE
4. STUCCO CONTROL JOINT (TYP). CONTROL JOINTS REQUIRED AT ALL INSIDE CORNERS (TYP.)
5. METAL CAP FLASHING (TYPICAL)
6. GLASS BLOCK
7. STOREFRONT DOORS - TEMPERED GLASS
8. 2"X2" TUBE STEEL GATE - 1"X1" PICKETS - PAINT
9. BUILDING IDENTIFICATION SIGN SHALL CONTRAST W/ BACKGROUND AND BE VISABLE FROM THE STREET. 4.33 SQUARE FEET OF SIGNAGE.

LEGEND

STUCCO COLOR #1 - STO color - Pueblo #01005

STUCCO COLOR #2 - STO color - Desert Lace # 01004

ANSI NOTES

1. DOORS SHALL MEET THE FOLLOWING REQUIREMENTS (ALL OF UBC 1003.3.1) -
   UBC SECTION 1003.3.1.3: SWING AND OPENING FORCE - EXIT DOORS SERVING AN OCCUPANT LOAD OF 10 OR MORE SHALL BE OF THE PIVOTED, BALANCED OR SIDE-HINGED SWINGING TYPE. EXIT DOORS SHALL SWING IN THE DIRECTION OF THE PATH OF EXIT TRAVEL WHERE THE AREA SERVED HAS AN OCCUPANT LOAD OF 50 OR MORE. THE DOOR SHALL SWING TO THE FULLY OPEN POSITION WHEN AN OPENING FORCE NOT TO EXCEED 30 POUNDS (133.45 N) IS APPLIED TO THE LATCH SIDE.

   UBC SECTION 1003.3.1.8: TYPE OF LOCK OR LATCH - REGARDLESS OF THE OCCUPANT LOAD SERVED, EXIT DOORS SHALL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR EFFORT.

   ANSI 404.2.7, DOOR HARDWARE - HANDLES, PULLS, LATCHES, LOCKS AND OTHER OPERABLE PARTS ON ACCESSIBLE DOORS SHALL HAVE A SHAPE THAT IS EASY TO GRASP WITH ONE HAND AND DOES NOT REQUIRE TIGHT GRASPING, PINCHING, OR TWISTING OF THE WRIST TO OPERATE. SUCH HARDWARE SHALL BE 34 INCHES MINIMUM AND 48 INCHES MAXIMUM ABOVE THE FLOOR OR GROUND. WHERE SLIDING DOORS ARE IN THE FULLY OPEN POSITION, OPERATING HARDWARE SHALL BE EXPOSED AND USABLE FORM BOTH SIDES. EXCEPTION: LOCKS USED ONLY FOR SECURITY PURPOSES AND NOT USED FOR NORMAL OPERATION ARE PERMITTED IN ANY LOCATION.

   ANSI 404.2.8.1, DOOR CLOSERS - DOOR CLOSERS SHALL BE ADJUSTED SO THAT FROM AN OPEN POSITION OF 90 DEGREES, THE TIME REQUIRED TO MOVE THE DOOR TO AN OPEN POSITION OF 12 DEGREES WILL BE 5 SECONDS MINIMUM.

   ANSI 404.2.9, DOOR-OPENING FORCE - FIRE DOORS SHALL HAVE THE MINIMUM OPENING FORCE ALLOWABLE BY THE APPROPRIATE ADMINISTRATIVE AUTHORITY. THE MAXIMUM FORCE FOR PUSHING OPEN OR PULLING OPEN DOORS OTHER THAN FIRE DOORS SHALL BE AS FOLLOWS:
   - INTERIOR HINGED DOOR: 5.0 LB (22.2 N)
   - SLIDING/FOLDING DOOR: 5.0 LB (22.2 N)

   THESE FORCES DO NOT APPLY TO THE FORCE REQUIRED TO RETRACT LATCH BOLTS OR DISENGAGE OTHER DEVICES THAT HOLD THE DOOR IN A CLOSED POSITION.

   ANSI 404.2.10, DOOR SURFACE - DOOR SURFACES WITHIN 10 INCHES (255 mm) OF THE FLOOR OR GROUND MEASURED VERTICALLY SHALL BE A SMOOTH SURFACE ON THE PUSH SIDE EXTENDING THE FULL WIDTH OF THE DOOR. PARTS CREATING HORIZONTAL OR VERTICAL JOISTS IN SUCH SURFACE SHALL BE WITHIN 1/8 INCH (1.8 mm) OF THE SAME PLANE AS THE OTHER. CAVITIES CREATED BY ADDED KICK PLATES SHALL BE CAPPED. EXCEPTIONS: 1. SLIDING DOORS, 2. TEMPERED GLASS DOORS WITHOUT STILES AND HAVING A BOTTOM RAIL OR SHOE WITH THE TOP LEADING EDGE TAPERED AT NO LESS THAN 60 DEGREES FROM THE HORIZONTAL SHALL NOT BE REQUIRED TO MEET THE 10 INCH (255 mm) BOTTOM RAIL HEIGHT REQUIREMENT, 3. DOORS WHICH DO NOT EXTEND TO WITHIN 10 INCHES (255 mm) OF THE FLOOR OR GROUND.

2. SIGNS SHALL MEET THE SECTION OF THE 1998 NMBC SECTION 1103.2.4.

revisions

job title
NM CREDIT UNION LEAGUE
4201 WOLCOTT AVENUE
ALBUQUERQUE, NEW MEXICO

PROJECT MANAGER	job no	date
JORGE DE LA TORRE, NA	23008	5-19-03
sheet title: ELEVATIONS		by: STM

STATE OF NEW MEXICO
JORGE DE LA TORRE
NO. 859
6/23/03
REGISTERED ARCHITECT

de la torre architects, p.a.
2400 louisiana blvd ne
building 3 / suite 110
albuquerque n.m. 87110 • 505 • 883 • 7918

sheet - 4
DRB 3 of - 23



KEYED CONSTRUCTION NOTES

1. 12" SIDEWALK CULVERT PER C.O.A. DWG. No. 2236



D-19 1"=750'±

VICINITY MAP

LEGAL DESCRIPTION: LOT 7A, JOURNAL CENTER 2

AREA: 0.7895 ACRES

FLOOD ZONE DESIGNATION: AS SHOWN ON FIRM PANEL 136 (9-20-96), THIS SITE IS WITHIN ZONE X, AN AREA DETERMINED TO BE OUTSIDE THE 500-YR FLOODPLAIN.

EXISTING CONDITIONS: THE UNDEVELOPED SITE SLOPES FROM EAST TO WEST AT 1-2%. FLOW DISCHARGES TO WOLCOTT NE AND HANCOCK CT NE. IT IS CONVEYED WEST TO THE NORTH PINO INLET AND TO THE NORTH DIVERSION CHANNEL.

EXISTING HYDROLOGY:
Precipitation Zone: 2
Land Treatment: 100% A
$Q_{100-6} = (1.56)(0.7895) = 1.2$ CFS

PROPOSED CONDITIONS: PROPOSED CONSTRUCTION INCLUDES A 12,000 SF BUILDING, PAVED PARKING & LANDSCAPED AREAS. RUNOFF WILL DISCHARGE THROUGH TWO DRIVEPADS ONTO WOLCOTT NE AND HANCOCK COURT NE.

PROPOSED HYDROLOGY:
Land Treatment: 10% B, 10% C, 80% D
$Q_{100-6} = (.08)(2.28)+(.08)(3.14)+(0.83)(4.70) = 3.4$ CFS

CURVE	LENGTH	DELTA	RADIUS	TANGENT	DIRECTION	CHORD
C1	131.38' (131.39')	18°05'42" (18°05'46")	416.00'	66.24' (66.25')	S74°48'28"E (S74°48'01"E)	130.83' (130.84')
C2	122.30' (122.29')	140°08'48" (140°08'22")	50.00'	137.92'	N20°14'28"E	94.01'
C3	28.18' (28.17')	53°48'44" (53°48'35")	30.00'	15.22'	N22°55'34"W (N22°55'30"W)	27.15'
C4	107.30'	17°33'55" (17°33'57")	350.00'	54.07' (54.02')	N12°45'45"E	106.88'
C5	48.55' (48.54')	92°42'58" (92°42'08")	30.00'	31.46' (31.45')	N67°53'48"E	43.42'

LEGEND

- 5120 CONTOUR (MAJOR)
- 5121 CONTOUR (MINOR)
- TC= / FL= TOP CURB / FLOWLINE
- x 00.00 SPOT ELEVATION
- CONCRETE CURB
- CONCRETE/SIDEWALK
- SIGN
- FENCE
- SANITARY SEWER MANHOLE
- CLEANOUT
- WATER VALVE
- FIRE HYDRANT
- WATER METER
- SPRINKLER CONTROL
- STREET LIGHT/ LOT LIGHT
- TELEPHONE PEDESTAL
- CATV PEDESTAL

ISAACSON & ARFMAN, P.A.
Consulting Engineering Associates
128 Monroe Street N.E.
Albuquerque New Mexico
1278-2EX-1.DWG/ts 05/29/03

revisions

job title: NM CREDIT UNION LEAGUE
ALBUQUERQUE, NEW MEXICO

PROJECT MANAGER	job no	date
JORGE DE LA TORRE, AIA	23008	2-19-03
sheet title: DRB GRADING/UTILITY PLAN		by

FRED C. ARFMAN NEW MEXICO 7322 LICENSED PROFESSIONAL ENGINEER

de la torre architects, p.a.
2400 louisiana blvd ne
building 3 / suite 110
albuquerque nm 87110 / 505 . 883 . 7915

sheet 1 S
C2
DRB
of 28