EXHIBIT A (REVISED 5/10/99)

SUBDIVISION IMPROVEMENT AGREEMENT DEVELOPMENT REVIEW BOARD REQUIRED INFRASTRUCTURE LISTING Lots 1 - 17, La Cueva Village, Unit 2

DRB Project No.: 100 1160 **DRC Project No.:** Prelim. Plat Approved: Prelim. Plat Expires: Site Plan Approved: **Date Submitted:**

Following is a summary of PUBLIC/PRIVATE Infrastructure required to be constructed or financially guaranteed for the above development. This listing is not necessarily a complete listing. During the SIA process and/or in the review of the construction drawings, if the DRC Chair determines that appurtenant items and/or unforeseen items have not been included in the infrastructure listing, the DRC Chair may include those items in the listing and related financial guarantee. Likewise, if the DRC Chair determines that appurtenant or non essential items can be deleted from the listing, those items may be deleted as well as the related portions of the financial guarantees. All such revisions require approval by the DRC Chair, the User Department and agent/owner. If such approvals are obtained, these revisions to the listing will be incorporated administratively. In addition, any unforeseen items which arise during construction which are necessary to complete the project and which normally are the Subdivider's responsibility will be required as a condition of project acceptance and close out by the City.

SIZE	TYPE IMPROVEMENT	LOCATION	FROM	TO
30'	Arterial Pavement with PEFM Curb and Gutter (West Side Only)	Barstow St NE	Carmel Ave NE	NE Corner of Unit 2
6'	Sidewalk (West Side Only)			
28' F-F 4'	Residential Pavement with Std Curb and Gutter (Both Sides) Deferred Sidewalk (Both Sides)	La Caverna Ave NE	Existing Dead End @ West end of Unit 2	Oso Loco PI NE
8" 6".	Sanitary Sewer Water line		5	21. m. 1. m
چار کا	SIDEWALK	CARMEL AVE NE	SW CORNER	BANSIOND ST NE
28' F-F	Residential Pavement with Mount. Curb and Gutter (Both Sides)	Oso Loco Place NE	La Caverna Ave NE	Carmel Ave NE
4' 6"	Deferred Sidewalk (Both Sides) Water line			
8"	Sanitary Sewer	Oso Loco Place NE	La Caverna Ave NE	Lot 1
24' Wide 42'' 54" 96"	Concrete Channel* PCP 5D ** RCP Storm Drain* RCP Storm Drain*	AMAFCA ROW AMAFCA ROW/ COA ROW AMAFCA ROW/ COA ROW	NW Corner of Unit 2 EXIT MH 150' West of Barstow C 150' West of Barstow C	150' West of Barstow CL 250 TO CONC. CHANNEL APS Detention Pond L 1320' East of Barstow CL
Per	Concrete Inlet Structure, Grading, and	Lots 7,8 Block 9,Tr 3, Unit 3, NAA		

LETTER OF MAP REVISION FROM FEMA REQUIRED FOR FINANCIAL GUARANTY RELEASE

CLOMR Rip-Rap Armored Training Dike*

* DENOTES ITEM TO BE DESIGNED AND CONSTRUCTED BY AMAFCA BY SEPARATE PROJECT AND GUARANTEED BY SEPARATE AGREEMENT BETWEEN CITY, DEVELOPER, AMAFCA, AND APS. I reeme Means

ENGINEER'S CERTIFICATION PER D.P.M. REQUIRED FOR FINANCIAL GUARANTY RELEASE. STREET LIGHTS PER D.P.M. REQUIREMENTS SUBJECT TO DRC REVIEW AND APPROVAL.

DEVELOPMENT REVIEW BOARD MEMBE	ER APPROVALS
constr. completion deadline 4.25-03	
^ /1) ~	
Plan 4.2501 Slaver Meeting 4/25/01	Adiesa E. Carlelain 4-25-01
Transportation Dev. Date Utility Dev. Date	Parks & Recreation Date
a our i	
Comen Me 4/25/61	fant of 4/25/0
City Engineer Date AMAFCA Date	DRB Chair Date
DDC DEVISIONS	

DIG ILLIIOTIO V							
REVISIONS	DATE	DRC CHAIR	USER DEPARTMENT	AGENT/OWNER			
1							
2							