Current DRC	
Project No.	

ORIGINAL

Figure 12

INFRASTRUCTURE LIST EXHIBIT "A"

TO SUBDIVISION IMPROVEMENTS AGREEMENT

Date Preliminary Plat Approved

Date Submitted:

Date Site Plan Approved:

November 26, 2001

Date Preliminary Plat Expiers:

DEVELOPMENT REVIEW BOARD (D.R.B.) REQUIRED INFRASTRUCTURE LIST CANTABELLA SUBDIVISION UNITS II & III (TRACTS D-1-A & E-2, VENTANA RANCH)

Following is a summary of PUBLIC/PRIVATE Infrastructure required to be constructed or financially guaranteed for the above development. This Listing is not necessarily a complete listing. During the SIA process and/or in of the construction drawings, if the DRC Chair determines that appurtenant items and/or unforeseen items have not been included in the infrastructure listing, the DRC Chair may include those items in the listing and related financial guarantee. Likewise, if the DRC Chair determines that appurtenant or non-essential items can be deleted from the listing, those items may be deleted as well as the related portions of the financial guarantees. All such revisions require approval by the DRC Chair, the User Department and agent/owner. If such approvals are obtained, these revisions to the listing will be incorporated administratively. In addition, any unforeseen items which arise during construction which which are necessary to complete the project and which normally are the Subdivider's responsibility will be required as a condition of project acceptance and close out by the City.

SIA Sequence #	COA DRC Project #	Size	Type of Improvement	Location	From	То	Private Inspector	City Inspector	City Crist Engineer
CANTABELLA SUBDIVISION UNIT II PUBLIC ROADWAY IMPROVEMENTS - UNIT II - ON SITE (D.R. HORTON)									
		28' F-F	RESIDENTIAL PAVING W/ PCC CURB & GUTTER & PCC 4' WIDE SIDEWALK ON BOTH SIDES*	CALLE HERMOSA PLACE	CALLE BELLA	CALLE DE VIDA			- L
		28' F-F	RESIDENTIAL PAVING W/ PCC CURB & GUTTER & PCC 4' WIDE SIDEWALK ON BOTH SIDES*	CALLE TESORO (LOOP ROAD)	CALLE DE VIDA	CALLE DE VIDA			
		32' F-F	RESIDENTIAL PAVING W/ PCC CURB & GUTTER & PCC 4' WIDE SIDEWALK ON BOTH SIDES*	CALLE CHULITA	CALLE CHULITA BNDRY BTWN UNIT I & UNIT II	CALLE CANTA			
		28 F-F	RESIDENTIAL PAVING W/ PCC CURB & GUTTER & PCC 4' WIDE SIDEWALK ON BOTH SIDES*	CALLE CANTA	CALLE CHULITA	NORTH CUL-DE-SAC TERMINUS			
		28' F-F	RESIDENTIAL PAVING W/ PCC CURB & GUTTER & PCC 4" WIDE SIDEWALK ON BOTH SIDES*	CALLE ALLEGRO	CALLE CHULITA	NORTH CUL-DE-SAC TERMINUS			
		28' F-F	RESIDENTIAL PAVING W/ PCC CURB & GUTTER & PCC 4' WIDE SIDEWALK ON BOTH SIDES*	CALLE DOLCE	CALLE ALLEGRO	EAST CUL-DE-SAC TERMINUS	<u> </u>		- 1
		* SIDEWALKS TO BE DEFERRED. WAIVER OF SIDEWALKS AROUND ALL CUL-DE-SAC'S						1	
			STREET LIGHTS AS PER COA DPM						

	SIA Sequence #	COA DRC Project #	Size	Type of Improvement	Location	From	То	Private Inspector	City Inspector	City Cnst Engineer
PUBLIC SANITARY SEWER IMPROVEMENTS - UNIT III - ON SITE NMUI										
			8" DIA	SANITARY SEWER W/ NEC. MH'S & SERVICES	CALLE HERMOSA PLACE	WEST CUL-DE-SAC TERMINUS	CALLE BELLA			
			8" DIA	SANITARY SEWER W/ NEC- MH'S & SERVICES	CALLE PLACIDO	CALLE HERMOSA PLACE	LOT 170			<u> </u>
			8" DIA	SANITARY SEWER W/ NEC. MH'S & SERVICES	CALLE BELLA	CALLE HERMOSA PLACE	LOT 136			
7			8" DIA	SANITARY SEWER W/ NEC- MH'S & SERVICES	CALLE CHULITA	NORTH CUL-DE-SAC TERMINUS	CALLE CANTA			
M			PUBLIC ROADW	AY IMPROVEMENTS - UNIT III - OFF ŞI	TE (LAS VENTANAS LTD	. PARTNERSHIP)				
NICINA			25' F-F (EAST HALF) w/ right turn*	ARTERIAL PAVING W/ PCC CURB & GUTTER & 10' WIDE ASPHALT TRAIL ON EAST SIDE	UNIVERSE BLVD.	VENTANA ROAD (EXISTING)	VENTANA HILLS ROAD (EXISTING)			
5	ASPHALT TRAIL ON EAST SIDE NEDWAY CURB STREET LIGHTS AS PER COA DPM A ~ 150 FT LONG 12 FT WIDE RIGHT TURN LANE IS REQUIRED ON UNIVERSE BLVD AT THE VENTANA ROAD INTERSECTION									
			PUBLIC STORM	DRAIN IMPROVEMENTS - UNIT III - OF	F SITE (LAS VENTANAS	LTD. PARTNERSHIP)				
	TYPE "A" A TYPE A INLET IS REQUIRED ON THE EAST SIDE OF UNIVERSE BLVD, NORTH OF THE INTERSECTION OF / / / _ /									1
	KEVIN PATTON	W	11/26/01	Jan &		11/28/01	Colierne E	Condu	lava	11/28/0
	PREPARED BY: PI		DATE	TRANSPORTATION DE	ough.	//-28-01 DATE	N/	AMAFCA	- Latte	DATE
	SIGNATURE	tu	11.26.01 DATE	D 10	00-	11-28-01 DATE	Bradh S.1	Sus ham.		11/28/01 DATE
	MAXIMUM TIME AL	LOW TO CONST	RUCT	NEW MEXICO UTILI		//-27-51				DATE
					DESIGN REVIEW COMM	TTEE REVISIONS				
	DENAG	NON	DATE	DRC CHAIR			DEPARTMENT		AGENT/OWNE	R
	REVIS	DIOIN	1-22-02	In the		Brady 1. B	iha	ww	- twiter	