

Current DRC Project No. _____

ORIGINAL

Figure 12
INFRASTRUCTURE LIST
 EXHIBIT 'A'
 TO SUBDIVISION IMPROVEMENTS AGREEMENT
 DEVELOPMENT REVIEW BOARD (D.R.B.) REQUIRED INFRASTRUCTURE LIST
UNM GIBSON COMMERCIAL DISTRICT

Date Submitted: 11/8/11
 Date Site Plan for Bldg Permi Approv: _____
 Date Site Plan for Sub. Approved: _____
 Date Preliminary Plat Approved: 11-9-11
 Date Preliminary Plat Expires: 11-9-12
 DRB Project No. 1001725

Following is a summary of PUBLIC/PRIVATE Infrastructure required to be constructed or financially guaranteed for the above development. This Listing is not necessarily a complete listing. During the SIA process and/or in the review of the construction drawings, if the DRC Chair determines that appurtenant items and/or unforeseen items have not been included in the infrastructure listing, the DRC Chair may include those items in the listing and related financial guarantee. Likewise, if the DRC Chair determines that appurtenant or non-essential items can be deleted from the listing, those items may be deleted as well as the related portions of the financial guarantees. All such revisions require approval by the DRC Chair, the User Department and agent/owner. If such approvals are obtained, these revisions to the listing will be incorporated administratively. In addition, any unforeseen items which arise during construction which which are necessary to complete the project and which normally are the Subdivider's responsibility will be required as a condition of project acceptance and close out by the City.

SIA Sequence #	COA DRC Project #	Size	Type of Improvement	Location	From	To	Private Inspector	City Inspector	City Cnst Engineer		
		PAVING									
		29' F-F EACH DIRECTION	1-12' LANE, 1-11' LANE, 1-6' BIKE LANE, IN EACH DIRECTION, MEDIAN C&G, STANDARD C&G, ARTERIAL PAVEMENT, 6' SIDEWALK (BOTH SIDES)	ALUMNI DRIVE	GIBSON BLVD	300' NORTH OF GIBSON PLUS TRANSITION	/	/	/		
			SINGLE LANE ROUNDABOUT	INTERSECTION OF ALUMNI DRIVE AND VARSITY AVENUE			/	/	/		
		18' F-F EACH DIRECTION	1-12' LANE, 1-6' BIKE LANE, IN EACH DIRECTION, MOUNTABLE MEDIAN C&G, STANDARD C&G, ARTERIAL PAVEMENT, 6' SIDEWALK (BOTH SIDES)	ALUMNI DRIVE	300' SOUTH OF ROUNDABOUT	TRACT 8 ENTRANCE	/	/	/		
		36' F-F	2-12' LANES, 2-6' BIKE LANES, STANDARD C&G, ARTERIAL PAVEMENT, 6' SIDEWALK (BOTH SIDES)	ALUMNI DRIVE	TRACT 8 ENTRANCE	EXISTING TERMINUS OF WEST ROAD	/	/	/		
		36' F-F	2-12' LANES, 2-6' BIKE LANES, STANDARD C&G, ARTERIAL PAVEMENT, 6' SIDEWALK (BOTH SIDES)	VARSIY AVENUE	ROUNDABOUT (ALUMNI DRIVE)	UNIVERSITY BLVD	/	/	/		
		12' FACE TO EDGE	75' NB LEFT TURN LANE WITH TRANSITION, MEDIAN C&G	ALUMNI DRIVE	NORTH PL OF TRACT 2	APPROX. 75' SOUTH OF NORTH PL OF TRACT 2	/	/	/		
		12' FACE TO EDGE	100' NB LEFT TURN LANE WITH TRANSITION, MEDIAN C&G	UNIVERSITY BLVD	VARSIY AVENUE	APPROX. 100' SOUTH OF VARSITY AVENUE	/	/	/		
		12' FACE TO EDGE	150' SB RIGHT TURN LANE WITH TRANSITION, STANDARD C&G	UNIVERSITY BLVD	VARSIY AVENUE	APPROX. 150' NORTH OF VARSITY AVENUE	/	/	/		
		12' FACE TO EDGE	115' (OR MAX POSSIBLE) WB RIGHT TURN LANE WITH TRANSITION, STANDARD C&G	GIBSON BLVD	ALUMNI DRIVE	APPROX. 115' EAST OF ALUMNI DRIVE	/	/	/		
		12' FACE TO EDGE	200' EB LEFT TURN LANE WITH TRANSITION, MEDIAN C&G	GIBSON BLVD	ALUMNI DRIVE	APPROX. 200' WEST OF ALUMNI DRIVE	/	/	/		
		12' FACE TO EDGE	150' WB RIGHT TURN LANE WITH TRANSITION, STANDARD C&G	GIBSON BLVD	MULBERRY STREET	APPROX. 150' EAST OF MULBERRY STREET	/	/	/		
		12' FACE TO EDGE	50' WB LEFT TURN LANE WITH TRANSITION, MEDIAN C&G	GIBSON BLVD	MULBERRY STREET	APPROX. 50' EAST OF MULBERRY STREET	/	/	/		
		12' EDGE TO EDGE	RESTRIPE TO PROVIDE 2ND SB LEFT TURN LANE	UNIVERSITY BLVD	GIBSON BLVD	APPROX. 130' NORTH OF GIBSON BLVD	/	/	/		
			6' SIDEWALK	UNIVERSITY BLVD	NORTH PL	SOUTH PL	/	/	/		
			6' SIDEWALK	GIBSON BLVD	WEST PL	EAST PL	/	/	/		
		53,000 CY	CUT VOLUME APPROX 12,000 CY, FILL VOLUME APPROX 42,000 CY EARTHWORK ALONG ALUMNI DRIVE AND VARSITY AVENUE				/	/	/		

		PUBLIC WATER							
		12"	WATERLINE W/ NEC. VALVES FH'S, MJ'S & RJ'S	ALUMNI DRIVE	EXISTING WATER LINE IN GIBSON BLVD.	EXISTING WATER LINE IN LOBO VILLAGE (CPN #566582)	/	/	/
		8"-10"	WATERLINE W/ NEC. VALVES FH'S, MJ'S & RJ'S	VARSITY AVENUE	EXISTING WATER LINE IN UNIVERSITY BLVD.	100' EAST OF ALUMNI DRIVE	/	/	/
		SANITARY SEWER							
		8"-10"	SANITARY SEWER LINE W/ NEC. MH'S & SERVICES	ALUMNI DRIVE	EXISTING SANITARY SEWER LINE IN GIBSON BLVD.	100' SOUTH OF ROUNDABOUT	/	/	/
		8"	SANITARY SEWER LINE W/ NEC. MH'S & SERVICES	VARSITY AVENUE	100' WEST OF UNIVERSITY BLVD	ROUNDABOUT	/	/	/
		8"-10"	SANITARY SEWER LINE W/ NEC. MH'S & SERVICES	ALUMNI DRIVE	ROUNDABOUT	800' NORTH TO EXISTING SANITARY SEWER MH	/	/	/
		STORM DRAIN							
		78"	RCP STORM DRAIN LINE W/ LATERALS, MH & INLETS	VARSITY AVENUE	UNIVERSITY BLVD	POINT OF CONNECTION TO EXISTING AT THE WEST SIDE OF ALUMNI DRIVE	/	/	/
		30"	RCP STORM DRAIN LINE W/ MH & INLETS	ALUMNI DRIVE	ROUNDABOUT	APPROX. 190' NORTH OF ROUNDABOUT	/	/	/
		36"	RCP STORM DRAIN LINE W/ MH & INLETS	ALUMNI DRIVE	ROUNDABOUT	APPROX. 225' SOUTH OF ROUNDABOUT	/	/	/
		42"	RCP STORM DRAIN LINE W/ MH & INLETS	ALUMNI DRIVE	20' NORTH OF THE NORTHWEST CORNER OF TRACT 8	APPROX. 120' SOUTH OF THE NORTHWEST CORNER OF TRACT 8	/	/	/
		36"	RCP STORM DRAIN LINE W/ LATERALS, MH & INLETS	ALUMNI DRIVE	APPROX. 120' SOUTH OF THE NORTHWEST CORNER OF TRACT 8	APPROX. 330' SOUTH OF THE NORTHWEST CORNER OF TRACT 8	/	/	/
		48"	RCP STORM DRAIN LINE W/ MH & INLETS	APPROX. 250' SOUTH OF SUNSHINE TERRACE AVENUE	ALUMNI DRIVE	SOUTH DIVERSION CHANNEL	/	/	/
			STORM DRAIN JUNCTION BOX OR MANIFOLD	WEST OF UNIVERSITY BLVD	APPROX. 80' SOUTH OF VARSITY AVENUE		/	/	/
			DEMO OF EXISTING CONCRETE CHANNEL	GENIEVA'S ARROYO	UNIVERSITY BLVD	TERMINUS OF CONCRETE CHANNEL APPROX. 740' WEST OF UNIVERSITY BLVD	/	/	/
			DEMO OF EXISTING 48" STORM DRAIN	NORTH SIDE OF GENIEVA'S ARROYO	UNIVERSITY BLVD	EXISTING AMAFCA CONCRETE BAFFLE RUNDOWN	/	/	/
			DEMO OF EXISTING 54" STORM DRAIN	EXIST. EASEMENT ON TRACT 1	EXISTING AMAFCA CONCRETE BAFFLE RUNDOWN	GIBSON BLVD	/	/	/
			WATER QUALITY MANHOLE	NEAR DOWNSTREAM TERMINUS OF 78" STORM DRAIN			/	/	/
			WATER QUALITY MANHOLE	NEAR DOWNSTREAM TERMINUS OF 48" STORM DRAIN			/	/	/
			ENERGY DISSIPATION DEVICE	AT DOWNSTREAM TERMINUS OF 78" STORM DRAIN			/	/	/
							/	/	/
		MISC							
			TRAFFIC SIGNAL	GIBSON BLVD AND ALUMNI DRIVE			/	/	/
			LOMR FOR GENEVAS ARROYO FLOODPLAIN (FINANCIAL GUARANTEE AMOUNT = \$40,000) THE FINANCIAL GUARANTEE WILL NOT BE RELEASED UNTIL THE LOMR IS APPROVED BY FEMA				/	/	/

AGENT/OWNER

BRIAN C. PATTERSON
 PREPARED BY: 11/8/2011
 DATE

BOHANNAN HUSTON INC
 FIRM
 SIGNATURE *BCH*

MAXIMUM TIME ALLOWED TO CONSTRUCT
 IMPROVEMENTS WITHOUT A DRB EXTENSION

DEVELOPMENT REVIEW BOARD MEMBER APPROVALS

Paul Clark 11-9-11
 DRB CHAIR DATE
Alan Deter 11-09-11
 TRANSPORTATION DEVELOPMENT DATE
 ABCWUA DATE

Carl S. Dumont 11-9-11
 PARKS & GENERAL SERVICES Recreation DATE
Ante G. Chene 11-9-11
 AMAFCA CITY ENGINEER DATE

ENGINEER'S CERTIFICATION OF THE GRADING PLAN IS REQUIRED FOR RELEASE OF THE SIA AND FINANCIAL GUARANTEE

DESIGN REVIEW COMMITTEE REVISIONS

REVISION	DATE	DRC CHAIR	USER DEPARTMENT	AGENT/OWNER