




ID	DELTA	TANGENT	ARC	RADIUS	CHORD	CHORD BRG
C1	05°17'48"	88.90'	177.88'	1922.00'	177.62'	N88°45'30"W
C2	08°32'05"	42.33'	84.50'	567.24'	84.42'	S01°17'15"W
C3	15°07'38"	22.57'	44.88'	170.00'	44.75'	S11°11'34"W
C4	36°33'40"	26.43'	51.05'	80.00'	50.19'	S37°07'26"W
C5	32°59'26"	14.81'	28.79'	50.00'	28.39'	S71°48'41"W



VICINITY MAP:



LOCATION MAP:



PARKING CALCULATIONS: (CONT'D)

COMPACT PARKING CALCULATION:  
59 REQ'D SPACES x 33% = 19 SPACES ALLOWED  
TOTAL COMPACT SPACES = 6 SPACES PROVIDED

DISABLED PARKING REQUIREMENTS:  
TOTAL DISABLED SPACES REQUIRED = 4 SPACES  
TOTAL DISABLED SPACES PROVIDED = 4 SPACES

MOTORCYCLE REQUIREMENTS:  
TOTAL MOTORCYCLE SPACES REQUIRED = 2 SPACE  
TOTAL MOTORCYCLE SPACES PROVIDED = 2 SPACE

COMMERCIAL BICYCLE REQUIREMENTS:  
1 BICYCLE SPACE FOR EACH 20 PARKING SPACES = 3 SPACES  
59 PARKING SPACES/20 = 3 TOTAL SPACE REQUIRED  
TOTAL BICYCLE SPACES REQUIRED = 3 SPACES  
TOTAL BICYCLE SPACES PROVIDED = 3 SPACES

KEYED NOTES:

- PROPOSED REFUSE ENCLOSURE WITH STUCCO FINISH TO MATCH BUILDING COLOR.
- PROPOSED LANDSCAPING AREA. REFER TO LANDSCAPING PLAN.
- PROPOSED HANDICAP PAVEMENT SIGN.
- PROPOSED STAMPED CONCRETE HANDICAP AISLE WITH 12" HIGH PAINTED LETTERING "NO PARKING" PER 66-1-4.1.8 NMSA 1978.
- PHASE II AND LIMITS OF CONSTRUCTION LINE FROM BACK OF CURB/SIDEWALK.
- PROPOSED ASPHALT PAVING.
- PROPOSED SITE LIGHTING. HEIGHT NOT TO EXCEED 20' TALL.
- PROPOSED BIKE RACK WITH 3 SPACES.
- PROPOSED CONCRETE SIDEWALK.
- PROPOSED STAMPED CONCRETE PEDESTRIAN CONNECTION.
- PROPOSED PAINTED PARKING STRIPING.
- PROPOSED FIRE HYDRANT LOCATION. REFER TO UTILITY PLAN.
- PROPOSED CONCRETE CURB. SEE GRADING & DRAINAGE PLAN AND COA STD. DWG. 2415A.
- PROPOSED HANDICAP RAMP. REFER TO DETAIL NOTED. SIGN TO BE NOTED PER 66-7-352.4C NMSA 1978. VIOLATORS ARE SUBJECT TO A FINE AND/OR TOWING.
- PROPOSED 4'-0" WIDE x 8'-0" LONG MOTORCYCLE SPACES WITH SIGNAGE AT EACH SPACE.
- CURRENT CURB LINE.
- COMPACT PARKING SPACES 9'-0"x15'-0" WITH PAINTED "COMPACT CAR" PAVEMENT DESIGNATION.
- PROPOSED PAINTED DIRECTION ARROW ON PAVEMENT.
- PROPOSED SIDEWALK CULVERT WITH METAL GRATE TOP TO BE FLUSH WITH TOP OF CONCRETE SIDEWALK. REFER TO CIVIL AND COA STD. DWG. 2236.
- PROPOSED ELECTRICAL TRANSFORMER LOCATION.
- PROPOSED CONCRETE SIDEWALK CONNECTION TO EXISTING SIDEWALK. MAX SLOPE 1:12.
- PROPOSED CONCRETE RAMP WITH STEEL PIPE HANDRAILS, PAINTED.
- PROPOSED CONCRETE RETAINING WALL. REFER TO GRADING AND DRAINAGE.
- PROPOSED CONCRETE STAIR WITH STEEL PIPE HANDRAILS, PAINTED.
- PROPOSED RAMP DOWN INTO PARKING GARAGE BELOW BUILDING.
- PROPOSED 10'-0" WIDE ASPHALT TRAIL.
- PROPOSED CONCRETE DRAINAGE CHANNEL ALONG PROPERTY LINE OUT TO EAGLE RANCH ROAD. REFER TO GRADING AND DRAINAGE PLAN.
- PROPOSED PLAZA (680 SF.) WITH BENCH SEATING.
- PROPOSED CONCRETE DRIVEWAY (STD. DWG. 2426) AND RAMPS (STD. DWG. 2426) TO BE CONSTRUCTED TO COA STANDARDS.
- TEMPORARY ASPHALT PAVING TO NEW DRIVEWAY LOCATION ON NUNZIO AVENUE (SHOWN HATCHED).
- TEMPORARY ASPHALT CURB ALONGSIDE TEMPORARY DRIVEWAY.
- TIE NEW DRIVEWAY CURB INTO EXISTING CURB AND GUTTER SYSTEM. REFER TO GRADING AND DRAINAGE PLAN.
- PROPOSED OPENING IN EXISTING CURB AND GUTTER SYSTEM FOR DRAINAGE. REFER TO GRADING AND DRAINAGE PLAN.
- PROPOSED CONCRETE SIDEWALK (STD. DWG. 2430).
- PROPOSED CONCRETE VENT OPENING FROM UNDERGROUND PARKING TO GRADE ABOVE.
- PROPOSED CONCRETE ISLAND.
- PROPOSED STAIRWELL TO FIRST FLOOR.
- PROPOSED BUILDING COLUMNS.
- PROPOSED UNDERGROUND PARKING GATE.
- SUMP PUMP PIT WITH GRATE COVER REFER TO GRADING AND DRAINAGE.
- PARKING ISLAND TO SERVE AS FIRST FLUSH DRAINAGE AREA. PROVIDE CURB OPENINGS ON UPSTREAM SIDE.
- FUTURE OFFSITE IMPROVEMENTS.

SITE DEVELOPMENT DATA:

LEGAL DESCRIPTION:  
TRACT H OF FOUNTAIN HILLS PLAZA SUBDIVISION.  
CITY OF ALBUQUERQUE,  
BERNALILLO COUNTY, NEW MEXICO

LAND AREA:  
0.9755 ACRES (42,493 SQ. FT.)

CURRENT ZONING:  
SU-1 FOR PDA TO INCLUDE C-3 USES  
(PERMISSIVE AND CONDITIONAL)

ZONE ATLAS PAGE:  
C-12-Z

BUILDING AREAS: (GROSS BUILDING AREAS)  
2-STORY DENTAL OFFICE: 10,674 GSF.  
7,678 GSF.-1ST FLOOR  
2,996 GSF.-2ND FLOOR  
FUTURE BUILDING (PHASE II): 3,000 SF.  
TOTAL GROSS BUILDING AREA 13,674 SF.

SITE DEVELOPMENT PHASING:

PHASE I:  
PHASE I WILL INCLUDE THE CONSTRUCTION OF PROPOSED 2-STORY DENTAL CLINIC, UNDERGROUND PARKING BELOW BUILDING FOOTPRINT, TEMPORARY PAVING OF ACCESS DRIVE THRU ADJACENT LOT 10-A-1 TO THE NORTH ONTO NUNZIO AVENUE NW. AND RELATED AT GRADE PARKING FOR PROPOSED USES.

PHASE II:  
PHASE II WILL INCLUDE THE CONSTRUCTION OF THE FUTURE BUILDING ONLY. PHASE II SHALL BE REVIEWED AND APPROVED BY THE DEVELOPMENT REVIEW BOARD (DRB) AND ADHERE TO THE DESIGN STANDARDS INCLUDED IN THE PREVIOUSLY APPROVED SITE DEVELOPMENT PLAN FOR SUBDIVISION.

SITE DEVELOPMENT GENERAL NOTES:

- THE DESIGN STANDARDS INCLUDED IN THE APPROVED SITE DEVELOPMENT PLAN FOR SUBDIVISION-FOUNTAIN HILLS PLAZA (EPC APPROVAL: MAY 2007 & DRB APPROVAL: JUNE 2007) SHALL GOVERN ALL NEW BUILDINGS FOR TRACT H OF THIS DEVELOPMENT.
- THE PARKING LOT DIMENSIONS ARE FROM FACE OF CURB TO FACE OF CURB.
- LANDSCAPING AND SIGNING WILL NOT INTERFERE WITH CLEAR SIGHT REQUIREMENTS. THEREFORE, SIGNS, WALLS, TREES, AND SHRUBBERY BETWEEN 3 AND 8 FEET TALL (AS MEASURED FROM THE GUTTER PAN) WILL NOT BE ACCEPTABLE IN THIS AREA.
- ANY ENCROACHMENT OR OVERHANG INTO THE ROW FROM SIGNS, FENCES, CANOPY, ROOF LINES, ETC. WILL REQUIRE AN ANNUAL REVOCABLE ENCROACHMENT PERMIT.
- ALL CURBS SURROUNDING LANDSCAPING, SHALL PROVIDE WATER RUNOFF OPENINGS TO ALLOW SURFACE DRAINAGE INTO THE LANDSCAPED AREAS (WATER HARVESTING).
- ALL SIGNAGE AND FENCES WILL BE DONE UNDER SEPARATE PERMIT.
- TRACTS C, F, & G ARE SUBJECT TO A TWENTY-FIVE FOOT WIDE FLOATING ACCESS, WATER, DRAINAGE AND SANITARY SEWER EASEMENT FOR THE BENEFIT OF AND TO BE MAINTAINED BY TRACTS E, F, & G GRANTED WITH THIS PLAT. THIS EASEMENT SHALL BE CONFIRMED AND DEFINED WITH FUTURE PLATTING. PLAT OF FOUNTAIN HILLS PLAZA SUBDIVISION RECORDED ON: 09/19/07

SITE DEVELOPMENT SITE LIGHTING NOTES:

- THE LOCATION OF THE LIGHTING FIXTURES TOGETHER WITH ITS CUT-OFF ANGLE SHALL BE SUCH THAT IT DOES NOT DIRECTLY SHINE ON ANY PUBLIC RIGHT-OF-WAY OR ADJACENT RESIDENTIAL PROPERTY.
- THE MAXIMUM HEIGHT OF A LIGHT POLE MEASURED FROM THE FINISH GRADE TO THE TOP OF THE POLE SHALL BE 20'-0" MAXIMUM.
- LIGHTING TO BE PROVIDED ON COMMERCIAL BUILDING FACADES SHALL BE MOUNTED AT 12 FEET MAXIMUM.
- SITE LIGHTING SHALL BE FULLY SHIELDED, AND HIGH-PRESSURE SODIUM LIGHTING AND UN-SHIELDED UPLIGHTING SHALL BE PROHIBITED AT 12 FEET MAXIMUM.

PARKING CALCULATIONS: (NET LEASABLE AREAS)

PROPOSED 2-STORY DENTAL CLINIC:  
7,178 NSF.-1ST FLOOR/200 = 36 SPACES  
2,840 NSF.-2ND FLOOR/300 = 9 SPACES

REQUIRED SPACES 45 SPACES

FUTURE BUILDING: (PHASE II)  
2,700 NSF./200 = 14 SPACES

TOTAL REQUIRED SPACES 59 SPACES

TRANSIT REDUCTIONS:  
59 SPACES REQ'D x 10% REDUCTION = (PROXIMITY TO BUS ROUTE 94)  
59 x 10% = 5.9 TOTAL SPACES REQUIRED

TOTAL PARKING SPACES REQUIRED = 53 SPACES  
TOTAL PARKING SPACES PROVIDED = 53 SPACES

43 REGULAR SPACES  
6 COMPACT SPACE  
4 HANDICAP VAN PARKING SPACE

PROJECT NUMBER: 1003445 APPLICATION NUMBER: 05EPC-00022

THIS PLAN IS CONSISTENT WITH THE SPECIFIC SITE DEVELOPMENT PLAN APPROVED BY THE ENVIRONMENTAL PLANNING COMMISSION (EPC) DATED AUGUST 18, 2005 AND THE FINDINGS AND CONDITIONS IN THE OFFICIAL NOTIFICATION OF DECISION ARE SATISFIED.

IS AN INFRASTRUCTURE LIST REQUIRED? ( ) YES ( ) NO IF YES, THEN A SET OF APPROVED DRG PLANS WITH A WORK ORDER IS REQUIRED FOR ANY CONSTRUCTION WITHIN PUBLIC RIGHT-OF-WAY OR FOR CONSTRUCTION OF PUBLIC IMPROVEMENTS.

DRB SITE DEVELOPMENT PLAN SIGNOFF APPROVAL:

TRAFFIC ENGINEER, TRANSPORTATION DIVISION	Date
UTILITIES DEVELOPMENT	Date
PARKS AND RECREATION DEPARTMENT	Date
CITY ENGINEER	Date
*ENVIRONMENTAL HEALTH DEPARTMENT (CONDITIONAL)	Date
SOLID WASTE MANAGEMENT APPROVAL IS ATTACHED AS SEPARATE SHEET	Date
SOLID WASTE MANAGEMENT	Date
DRB CHAIRPERSON, PLANNING DEPARTMENT	Date

PROJECT: 1003445  
DATE: 2-25-15  
APP: 15-70020  
(SBS)


Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque, NM 87102  
505 268 4144 [p]  
505 268 4244 [f]

job number 14-22  
drawn by cv, mws  
project manager Douglas Heller, AIA  
date 3/5/15

Smiles for Kids Dental Office  
9201 Eagle Ranch Road, NW,  
Albuquerque, New Mexico 87114

Site Development Plan For Building Permit

SDPBP  
SHEET 1 of 7




SITE CONCEPTUAL GRADING PLAN



VICINITY MAP: C-12

GRADING KEYED NOTES


1. INSTALL SIDEWALK CULVERT
2. INSTALL RIBBON CHANNEL
3. INSTALL RETAINING WALL
4. INSTALL SUMP PUMP
5. POND FOR FIRST FLUSH
6. BUILDING STEM WALL
7. SWALE TO KEEP RUNOFF AWAY FROM BUILDING AND RETAINING WALLS
8. CHECK DAM



ACCESS ROAD CONCEPTUAL GRADING PLAN

**LEGEND**

	PROPERTY LINE
	EXISTING CONTOURS
	PROPOSED SPOT ELEVATION
	TC=TOP OF CURB, FL=FLOW LINE
	TW=TOP OF WALL, BW=BOTTOM OF WALL
	EX=EXISTING, TG=TOP OF GRADE
	PROPOSED DIRECTION OF FLOW
	WATER BLOCK
	PROPOSED RETAINING WALL
	PROPOSED INDEX CONTOURS
	PROPOSED INTER CONTOURS
	PROPOSED CURB & GUTTER
	EASEMENT
	PROPOSED STORM DRAIN LINE



revision	
by	
date	
rev	◀◀◀◀


**MH**  
Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]

job number	20150304
drawn by	MHS
project manager	CSB
date	12.12.2014

project title  
**Smiles for Kids Dental Office**  
9201 Eagle Ranch Road, NW,  
Albuquerque, New Mexico 87114  
sheet title  
**Conceptual Grading Plan**





SITE CONCEPTUAL DRAINAGE MANAGEMENT PLAN



ACCESS ROAD CONCEPTUAL GRADING PLAN

- LEGEND**
- PROPERTY LINE
  - - - 5.301 EXISTING CONTOURS
  - 65.23 PROPOSED SPOT ELEVATION
  - TC=TOP OF CURB, FL=FLOW LINE  
TW=TOP OF WALL, BW=BOTTOM OF WALL  
EX=EXISTING, TG=TOP OF GRADE
  - S=2.0% PROPOSED DIRECTION OF FLOW
  - ~~~~~ WATER BLOCK
  - PROPOSED RETAINING WALL
  - - - 5.305 PROPOSED INDEX CONTOURS
  - - - PROPOSED INTER CONTOURS
  - PROPOSED CURB & GUTTER
  - - - EASEMENT
  - SD PROPOSED STORM DRAIN LINE



FEMA FIRM MAP # 35001C0116G

**Smiles for Kids Dental Office**  
**Proposed Ultimate Development Conditions Basin Data Table**

This table is based on the DPM Section 22.2, Zone: 1

Basin ID	Area (SQ. FT)	Area (AC.)	Land Treatment Percentages				Q(100yr) (cfs/ac.)	Q(100yr-5hr) (CFS)	WTE (Inches)	V(100yr-5hr) (CF)	V(100yr-10day) CF
			A	B	C	D					
Proposed 1	42493	0.98	0.0%	0.0%	26.0%	74.0%	3.98	3.88	1.72	6074	9926
<b>TOTAL</b>	<b>42493</b>	<b>**0.98</b>						<b>3.88</b>			<b>***9926</b>

PROPOSED BASIN DATA TABLE

**INTRODUCTION:**

THE PROJECT IS LOCATED ON THE NORTHWEST INTERSECTION OF PASEO DEL NORTE BLVD AND EAGLE RANCH RD. THIS SITE IS NOT WITHIN A DEFINED FLOOD ZONE AS SHOWN ON FIRM MAP NUMBER 35001C0116G (THIS SHEET). THE PURPOSE OF THIS SUBMITTAL IS TO PROVIDE A DRAINAGE MANAGEMENT PLAN FOR THE DEVELOPMENT OF SMILES FOR KIDS DENTAL OFFICE AND REQUEST SITE DEVELOPMENT PLAN FOR BUILDING PERMIT APPROVAL.

**EXISTING CONDITIONS:**

THE 0.98 ACRE SITE IS CURRENTLY UNDEVELOPED. THE SITE SLOPES TO THE NORTH / NORTHEAST WHERE THE RUNOFF OPENLY DISCHARGES INTO EAGLE RANCH RD.

BASED ON THE DRAINAGE STUDY FOR FOUNTAIN HILLS (CITY OF ALBUQUERQUE DRAINAGE FILE #C12/039), THE ALLOWABLE PEAK DISCHARGE FROM THE SITE IS APPROXIMATELY 4.08 CFS.

**METHODOLOGY:**

THE HYDROLOGIC ANALYSIS PROVIDED WITH THIS DRAINAGE MANAGEMENT PLAN HAS BEEN PREPARED IN ACCORDANCE WITH SECTION 22.2 OF THE DPM. THE SITE IS LOCATED WEST OF THE RIO GRANDE WITHIN PRECIPITATION ZONE 1. LAND TREATMENT PERCENTAGES WERE CALCULATED BASED ON THE ACTUAL CONDITIONS IN EACH ONSITE BASIN AND ARE SUMMARIZED IN THE "PROPOSED BASIN DATA TABLE" (THIS SHEET).

**PROPOSED CONDITIONS:**

THIS DRAINAGE MANAGEMENT PLAN WAS DEVELOPED IN ACCORDANCE WITH A FULLY DEVELOPED SITE. IT WAS DETERMINED THAT THE MAXIMUM ALLOWABLE PEAK DISCHARGE FROM THE SITE IS APPROXIMATELY 4.08 CFS (AS MENTIONED ABOVE). THIS IS A SMALL SITE AND ACTS AS ONE DRAINAGE BASIN (BASIN 1).

THE ULTIMATE OUTFALL LOCATION IS EAGLE RANCH ROAD THROUGH MEANS OF RIBBON CHANNEL AND A SMALL POND (POND 1) IN THE PARKING LOT USED TO MITIGATE THE FIRST FLUSH. A PORTION OF THE SITE DRAINS INTO THE PARKING GARAGE, THAT FLOW IS THEN DIRECTED INTO A SUMP WHERE IT DISCHARGES INTO SANITARY SEWER.

OFFSITE PRIVATE ACCESS ROAD IS NOT INCLUDED IN THE CALCULATION. RUNOFF FROM TRACT 10-A-1 WILL BE ADDRESSED WITH THE DEVELOPMENT OF THAT TRACT.

**FIRST FLUSH CALCULATIONS:**

IMPERVIOUS AREA: 28,868 SF  
VOLUME REQUIRED: 1,036 CF  
VOLUME PROVIDED: 315 CF

THERE WERE MANY CONTRIBUTING FACTORS THAT LIMITED THE VOLUME THAT COULD BE INCORPORATED INTO THE SITE DESIGN. THE SITE HAS AN EXISTING SLOPE OF APPROXIMATELY 10.00% STEEP SLOPE SITES MAKE IT CHALLENGING TO INCORPORATE SHALLOW RETENTION AREAS IN THE LANDSCAPE DESIGN AND REDUCE THE ACTUAL VOLUME INTERCEPTED. IN ADDITION, BUILDING AND SITE PARKING SET BACKS LIMITED THE AREA AVAILABLE TO PROVIDE RETENTION PONDS WHERE THEY WOULD BE MOST EFFECTIVE AT TREATING THE FIRST FLUSH. ANOTHER SITE CONSTRAINT IS AN EXISTING UTILITY EASEMENT (ALONG EAGLE RANCH AND PASEO DEL NORTE) CONTAINING COMMUNICATION AND GAS LINES. GIVEN THE SITE CONSTRAINTS, THIS DESIGN MAXIMIZED THE FIRST FLUSH RETAINED WITHIN THE PARKING LOT PONDING AREA.

**CONCLUSION:**

THE PEAK DISCHARGE FROM THE SITE IS 3.88 CFS WHICH IS LESS THAN THE ALLOWABLE PEAK DISCHARGE RATE, THEREFORE WE ARE IN CONFORMANCE WITH CITY OF ALBUQUERQUE HYDROLOGY REQUIREMENTS AND REQUEST SITE DEVELOPMENT PLAN FOR BUILDING PERMIT APPROVAL.


revision  
by  
date  
rev

**MH**  
Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]

job number 20150304  
drawn by MHS  
project manager GSB  
date 12.12.2014

project title Smiles for Kids Dental Office  
9201 Eagle Ranch Road, NW,  
Albuquerque, New Mexico 87114  
sheet title Conceptual Drainage Management Plan

sheet-  
C101  
SHEET 3 of 7




SITE CONCEPTUAL UTILITY PLAN

UTILITY KEYED NOTES

1. CONNECT TO EXISTING 12" WATERLINE
2. INSTALL 1-1/2" WATER METER
3. INSTALL NEW DOMESTIC SERVICE LINE
4. INSTALL NEW FIRE PROTECTION LINE
5. INSTALL NEW PRIVATE FIRE HYDRANT
6. INSTALL HEATED ENCLOSURE FOR DOMESTIC AND FIRE PROTECTION REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTER
7. INSTALL POST INDICATOR VALVE
8. STUB TO WITHIN 5' OF BUILDING
9. CONNECT TO EXISTING 8" SAS LINE
10. INSTALL NEW SAS SERVICE LINE

LEGEND

	PROPERTY LINE
	EXISTING EASEMENT
	EXISTING SANITARY SEWER
	EXISTING WATER LINE
	PROPOSED EASEMENT
	PROPOSED SANITARY SEWER LINE
	PROPOSED SANITARY SEWER MANHOLE
	PROPOSED CLEANOUT
	PROPOSED WATER LINE
	PROPOSED VALVE
	PROPOSED FIRE LINE
	PROPOSED HYDRANT
	PROPOSED CAP
	PROPOSED WATER METER
	PROPOSED POST INDICATOR VALVE




rev	date	by	revision

**MH**  
**Mullen Heller**  
 Architecture P.C.  
 924 Park Avenue SW  
 Suite B  
 Albuquerque 87102  
 505 268 4144 [p]  
 505 268 4244 [f]

job number	20150304
drawn by	MHS
project manager	GSB
date	12.12.2014

project title  
**Smiles for Kids Dental Office**  
 9201 Eagle Ranch Road, NW,  
 Albuquerque, New Mexico 87114  
 sheet title  
**Conceptual Utility Plan**



Eagle Ranch Street Trees  
5 Required  
5 Provided

EAGLE RANCH RD.

Parking Lot  
Trees, 1 per 10 Spaces  
33 Spaces  
3 Trees Required

Proposed 2-story  
Dental Office With  
Underground Parking  
7605 sf Footprint


FUTURE

Paseo del Norte Street Trees  
4 Required  
4 Provided

PASEO DEL NORTE




SCALE: 1" = 20'-0"



**TREE PLANTING DETAIL**

- NTS
- GENERAL NOTES:**
1. ROOTBALL SHALL BE PLACED ON UNDISTURBED SOIL TO PREVENT TREE FROM SETTLING.
  2. TOP OF ROOTCOLLAR INDICATED LEVEL AT WHICH TREE WAS GROWN AND DUG; THIS REPRESENTS THE LEVEL AT WHICH THE TREE SHOULD BE INSTALLED; THAT LEVEL MAY BE EXCEEDED BY ONLY A ONE INCH LAYER OF SOIL.
  3. PRIOR TO BACKFILLING TREE, ALL WIRE, ROPE AND SYNTHETIC MATERIALS SHALL BE REMOVED FROM THE TREE AND THE PLANTING PIT.
  4. PRIOR TO BACKFILLING ALL BURLAP SHALL BE CUT AWAY EXCEPT FROM BOTTOM OF THE ROOTBALL.
- CONSTRUCTION NOTES:**
- A. TREE
  - B. BACKFILL WITH EXISTING SOIL.
  - C. 3" DEPTH OF GRAVEL MULCH.
  - D. UNDISTURBED SOIL.





**SHRUB PLANTING DETAIL**

- NTS
- GENERAL NOTES:**
1. THE OUTSIDE DIAMETER OF THE WATER RETENTION BASIN SHALL BE TWICE THE DIAMETER OF THE SHRUB PLANTING PIT.
- CONSTRUCTION NOTES:**
- A. SHRUB.
  - B. BACKFILL WITH EXISTING SOIL.
  - C. EARTH BERM AROUND WATER RETENTION BASIN.
  - D. 3" DEPTH OF GRAVEL MULCH.
  - E. FINISH GRADE.
  - F. UNDISTURBED SOIL.

**LANDSCAPE LEGEND**

QTY	SIZE	COMMON/BOTANICAL	H2O USE
<b>Trees</b>			
3	2" Cal.	Ash <i>Fraxinus sp.</i>	40x35 1225 3675 M
2	2" cal	Honey Locust <i>Gleditsia triacanthos</i>	50x45 2025 3150 M
1	6 - 8'	Austrian Pine <i>Pinus nigra</i>	35x25 625 3750 M
2	4 - 6'	Palm Yucca <i>Yucca faxoniana</i>	15x6 36 3750 M
10	15 Gal.	Oklahoma Redbud <i>Cercis reniformis</i>	15x12 144 3750 M
<b>Shrubs &amp; Groundcovers</b>			
6	15 Gal.	Desert Willow <i>Chilopsis linearis</i>	20x25 625 3750 M
9	5 Gal	India Hawthorne <i>Raphiolepis indica</i>	3x5 25 225 M
22	5 Gal	Feather Reed Grass <i>Calamagrostis arundinacea</i>	25x2 4 88 M
16	5 Gal	Wintergreen Barberry <i>Berberis julianae</i>	5x5 25 400 M
3	5 Gal	Butterfly Bush <i>Buddleia davidii</i>	5x5 25 75 M
9	5 Gal	Winter Jasmine <i>Jasminum nudiflorum</i>	4x12 144 1236 M
12	5 Gal	Buffalo Juniper <i>Juniperus sabina 'Buffalo'</i>	6x12 144 1728 M
3	5 Gal	Cherry Sage <i>Salvia greggii</i>	2x3 9 27 M
2	5 Gal	Blue Mist <i>Caryopteris x clandonensis</i>	3x3 9 18 M
3	5 Gal	Fern Bush <i>Chamaebatiaria millefolium</i>	5x6 36 108 L
9	5 Gal	Apache Plume <i>Fallugia paradoxa</i>	6x1 49 294 L
15	5 Gal	Chamaea <i>Chrysothamnus nauseosus</i>	5x5 25 375 L
8	2-3cf	Boulders To be placed at contractor discretion	Total Live Plant Cover 21059



**LANDSCAPE NOTES:**  
Landscape maintenance shall be the responsibility of the Property Owner. The Property Owner shall maintain street trees in a living, healthy, and attractive condition.

It is the intent of this plan to comply with the City Of Albuquerque Water Conservation Landscaping and Water Waste Ordinance planting restriction approach. Approval of this plan does not constitute or imply exemption from water waste provisions of the Water Conservation Landscaping and Water Waste Ordinance.

Water management is the sole responsibility of the Property Owner. All landscaping will be in conformance with the City of Albuquerque Zoning Code, Street Tree Ordinance, Foliage Ordinance, and Water Conservation Landscaping and Water Waste Ordinance. In general, water conservative, environmentally sound landscape principles will be followed in design and installation.

Plant beds shall achieve 75% live ground cover at maturity.  
Brown Gravel over Filter Fabric to a minimum depth of 3" shall be placed in all landscape areas which are not designated to receive native seed.

No changes or substitutions shall be made to this plan without the express written consent of the Landscape Architect of record.

This plan is the exclusive property of the Hilltop and is provided to the client per a design build agreement. If the Hilltop is not the landscape installation contractor, a design fee equal to 5% of the contract shall be paid to The Hilltop by the owner, prior to release of plans.

The Landscape Architect of record reserves the right to inspect the installation and reject any and all irrigation, plant materials and gravel, and have replaced at the contractors expense, any item not in compliance with the intent of this plan.

**IRRIGATION NOTES:**  
Irrigation shall be a complete underground system with Trees to receive 1 Netafim spiral (50' length) with 3 loops at a final radius of 4.5' from tree trunk, primed in place. Netafim shall have emitters 12" oc. with a flow of 6 gph. Shrubs to receive (2) 1/2 GPH Drip Emitters. Drip and Bubbler systems to be tied to 1/2" poly pipe with flush caps at each end. Trees and shrubs shall be on separate valves.  
Run time per each shrub drip valve will be approximately 15 minutes per day. Tree drip valve shall run 15 hours, 3 times per week. Run time will be adjusted according to the season.


Point of connection for irrigation system is unknown at current time and will be coordinated in the field. Irrigation will be operated by automatic controller.

Location of controller to be field determined and power source for controller to be provided by others.  
Irrigation maintenance shall be the responsibility of the Property Owner.


Water and Power source shall be the responsibility of the Developer/Builder.

**LANDSCAPE CALCULATIONS**


TOTAL LOT AREA (sf)	42493
MINUS TOTAL BUILDING AREA (sf)	-7605
MINUS PHASE TWO	-5521
TOTAL LOT AREA OF PHASE ONE (sf)	29358
LANDSCAPE REQUIREMENT	x 20
TOTAL LANDSCAPE REQUIRED ( 20% )	5872
TOTAL LANDSCAPE PROVIDED	12711
TOTAL LIVE PLANT COVER REQUIRED ( 75% )	9578
TOTAL LIVE PLANT COVER PROVIDED	21059




FEBCO MODEL 765  
Pressure Vacuum Breaker  
Outside Installation



FEBCO MODEL 765  
Pressure Vacuum Breaker  
Feature




Netafim Spiral Detail



The Hilltop  
1909 Edith NE  
Albuquerque, NM 87114  
Cont. Lic. #64958  
Ph: (505) 898-3630  
Fax: (505) 898-1151  
darryl@hilltoplandscaping.com

Landscape Architect



Mullen Heller  
Architecture P.C.

924 Park Avenue SW

Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]

Fountain Hills Dental  
9201 Eagle Ranch Rd  
Albuquerque, NM 87114

LANDSCAPE PLAN


The design contained herein remains the property of The Hilltop Architects & Contractors. Contractors who are provided by copyright. This is an original design and shall not be released or copied unless applicable fees have been paid for a job order placed.




DRAWN BY  
on  
REVISIONS  
01/16/2016

DATE  
01/16/16


SHEET #  
LS-101




1 West Elevation  
Scale: 1/8" = 1'-0"



2 South Elevation  
Scale: 1/8" = 1'-0"



3 North Elevation  
Scale: 1/8" = 1'-0"



4 East Elevation  
Scale: 1/8" = 1'-0"

GENERAL NOTES:

- [A] ALL DIMENSIONS ARE FROM FACE OF STUD TO FACE OF STUD, UNLESS OTHERWISE NOTED.
- [B] THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD. IF DIMENSIONAL ERROR, VARIANCES, AND/OR CONFLICTS EXIST, AS DESCRIBED WITHIN THE CONSTRUCTION DOCUMENTS, OR CONDITIONS ARE ENCOUNTERED THAT ARE NOT COVERED IN THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT BEFORE COMMENCING THAT PORTION OF THE WORK.
- [C] CONTRACTOR TO VERIFY SIZES OF ALL OWNER PROVIDED EQUIPMENT PRIOR TO INSTALLATION.
- [D] ALL CONSTRUCTION SHALL BE IN COMPLIANCE WITH ALL APPLICABLE BUILDING CODES, MODEL CODES, LOCAL CODES, LAWS AND ORDINANCES.

KEYED NOTES:

- [1] ALUMINUM STOREFRONT SYSTEM, CLEAR ANNOZIZED FRAME WITH SPANDREL GLAZING.
- [2] ALUMINUM STOREFRONT SYSTEM, CLEAR ANNOZIZED FRAME WITH TINTED GLAZING.
- [3] FIELD-1: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: LIGHT TAN
- [4] FIELD-2: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: TAN
- [5] FIELD-3: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: LIGHT BROWN
- [6] ACCENT 1: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: ORANGE (EARTH TONE)
- [7] ACCENT 2: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: GREEN (EARTH TONE)
- [8] NATURAL STONE VENER FINISH.
- [9] METAL PARAPET CAP TO MATCH ADJACENT FINISH COLOR.
- [10] METAL WALL PANEL SYSTEM (NON CORRUGATED). LIGHT TAN OR GRAY.
- [11] METAL RAILING; PAINTED DARK EARTH TONE.
- [12] ALUMINUM STOREFRONT DOOR, CLEAR ANNOZIZED FRAME WITH SPANDREL LIGHT.
- [13] HOLLOW METAL DOOR PAINTED TO MATCH STUCCO.
- [14] METAL CANOPY TO MATCH STOREFRONT FINISH.
- [15] 12" HIGH ADDRESS CHANNEL LETTERS.
- [16] STUCCO CONTROL JOINT.

EXISTING BUILDING C  
SIGNAGE CALCULATIONS:

- BUILDING MOUNTED:
- WEST ELEVATION- 2900 SF X 9%  
234 SF ALLOWED  
85 SF ILLUMINATED PROVIDED
  - SOUTH ELEVATION- 1194 SF X 9%  
126 SF ALLOWED  
120 SF ILLUMINATED PROVIDED
  - EAST ELEVATION- 2900 SF X 9%  
107 SF ALLOWED  
96 SF ILLUMINATED PROVIDED
  - NORTH ELEVATION- 1189 SF X 9%  
107 SF ALLOWED  
99 SF ILLUMINATED PROVIDED


revision	
by	
date	
rev	△ △ △ △ △




Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque 87102  
505 268 4144[p]  
505 268 4244 [f]

job number	14-22
drawn by	av
project manager	Douglas Heller, AIA
date	12.12.2014


project title  
**Smiles for Kids Dental Office**  
9201 Eagle Ranch Road, NW  
Albuquerque, New Mexico 87114  
sheet title  
**Exterior Elevations**




**1 Dumpster Enclosure Plan**  
Scale: 1/8"=1'-0"




**2 Dumpster Enclosure Front Elevation**  
Scale: 3/8"=1'-0"




**3 Dumpster Enclosure Side Elevation**  
Scale: 3/8"=1'-0"




**4 Refuse Enclosure Wall Section**  
Scale: 1"=1'-0"




**5 H.C. Ramp Detail**  
Scale: Not To Scale (Isometric)




**6 HC Parking Striping Detail**  
Scale: 1/4"=1'-0"




**7 HC Pavement Sign Detail**  
Scale: 3/4"=1'-0"




**8 Bicycle Rack Detail**  
Scale: 3/4"=1'-0"



**9 Light Pole Elevation Detail**  
Scale: 1"=1'-0"



**10 HC Parking Sign Detail**  
Scale: 3/4"=1'-0"



**11 MC Parking Sign Detail**  
Scale: 3/4"=1'-0"


revision	
by	
date	
rev	5 4 3 2 1

**MH**  
Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]

job number	14-22
drawn by	ov
project manager	Douglas Heller, AIA
date	12.12.2014

project file  
**Smiles for Kids Dental Office**  
9201 Eagle Ranch Road, NW  
Albuquerque, New Mexico 87114  
sheet file  
**Site Details**

ID	DELTA	TANGENT	ARC	RADIUS	CHORD	CHORD BRG
C1	05°17'48"	88.90'	177.68'	1922.00'	177.62'	N88°45'30"W
C2	08°32'05"	42.33'	84.50'	567.24'	84.42'	S01°17'15"W
C3	15°07'38"	22.57'	44.88'	170.00'	44.75'	S11°17'34"W
C4	36°33'40"	26.43'	51.05'	80.00'	50.19'	S37°07'26"W
C5	32°59'26"	14.81'	28.79'	50.00'	28.39'	S71°48'41"W



TRACT F  
FOUNTAIN HILLS PLAZA SUBDIVISION  
NOT A PART  
ZONING: SU-1 FOR PDA  
TO INCLUDE C-3 USES

TRACT G  
FOUNTAIN HILLS PLAZA SUBDIVISION  
NOT A PART  
ZONING: SU-1 FOR PDA  
TO INCLUDE C-3 USES

LOT 10-A-1  
ALBUQUERQUE WEST - UNIT 1  
NOT A PART  
ZONING: SU-1 FOR PDA  
TO INCLUDE C-3 USES

NUNZIO AVENUE N.W.  
(60' RIGHT-OF-WAY)

EAGLE RANCH ROAD N.W.  
(RIGHT-OF-WAY: VARIES)

PASEO DEL NORTE N.W.  
(156' RIGHT-OF-WAY)

PARKING CALCULATIONS: (CONT'D)

**COMPACT PARKING CALCULATION:**  
59 REQ'D SPACES x 33% = 19 SPACES ALLOWED  
TOTAL COMPACT SPACES = 6 SPACES PROVIDED

**DISABLED PARKING REQUIREMENTS:**  
TOTAL DISABLED SPACES REQUIRED = 4 SPACES  
TOTAL DISABLED SPACES PROVIDED = 4 SPACES

**MOTORCYCLE REQUIREMENTS:**  
TOTAL MOTORCYCLE SPACES REQUIRED = 2 SPACE  
TOTAL MOTORCYCLE SPACES PROVIDED = 2 SPACE

**COMMERCIAL BICYCLE REQUIREMENTS:**  
1 BICYCLE SPACE FOR EACH 20 PARKING SPACES = 59 PARKING SPACES/20 = 3 TOTAL SPACE REQUIRED  
TOTAL BICYCLE SPACES REQUIRED = 3 SPACES  
TOTAL BICYCLE SPACES PROVIDED = 3 SPACES

KEYED NOTES:

- PROPOSED REFUSE ENCLOSURE WITH STUCCO FINISH TO MATCH BUILDING COLOR.
- PROPOSED LANDSCAPING AREA. REFER TO LANDSCAPING PLAN.
- PROPOSED HANDICAP PAVEMENT SIGN.
- PROPOSED STAMPED CONCRETE HANDICAP AISLE WITH 12" HIGH PAINTED LETTERING "NO PARKING" PER 66-1-4.1.B NMSA 1978.
- PHASE II AND LIMITS OF CONSTRUCTION LINE FROM BACK OF CURB/SIDEWALK.
- PROPOSED ASPHALT PAVING.
- PROPOSED SITE LIGHTING. HEIGHT NOT TO EXCEED 20' TALL.
- PROPOSED BIKE RACK WITH 3 SPACES.
- PROPOSED CONCRETE SIDEWALK.
- PROPOSED STAMPED CONCRETE PEDESTRIAN CONNECTION.
- PROPOSED PAINTED PARKING STRIPING.
- PROPOSED FIRE HYDRANT LOCATION. REFER TO UTILITY PLAN.
- PROPOSED CONCRETE CURB. SEE GRADING & DRAINAGE PLAN AND COA STD. DWG. 2415A.
- PROPOSED HANDICAP RAMP. REFER TO DETAIL.
- PROPOSED HANDICAP PARKING SIGN. "VAN" WHERE NOTED. SIGN TO BE NOTED PER 66-7-352.4C NMSA 1978. VIOLATORS ARE SUBJECT TO A FINE AND/OR TOWING.
- PROPOSED 4'-0" WIDE x 8'-0" LONG MOTORCYCLE SPACES WITH SIGNAGE AT EACH SPACE.
- EXISTING CITY CURB AND GUTTER TO REMAIN.
- COMPACT PARKING SPACES 9'-0"x16'-0" WITH PAINTED "COMPACT CAR" PAVEMENT DESIGNATION.
- PROPOSED PAINTED DIRECTION ARROW ON PAVEMENT.
- PROPOSED SIDEWALK CULVERT WITH METAL GRATE TOP TO BE FLUSH WITH TOP OF CONCRETE SIDEWALK. REFER TO CIVIL AND COA STD. DWG. 2236.
- PROPOSED ELECTRICAL TRANSFORMER LOCATION.
- PROPOSED CONCRETE SIDEWALK CONNECTION TO EXISTING SIDEWALK. MAX SLOPE 1:12.
- PROPOSED CONCRETE RAMP WITH STEEL PIPE HANDRAILS, PAINTED.
- PROPOSED INTEGRALLY COLORED CONCRETE RETAINING WALL. REFER TO GRADING AND DRAINAGE.
- PROPOSED CONCRETE STAIR WITH STEEL PIPE HANDRAILS, PAINTED.
- PROPOSED RAMP DOWN INTO PARKING GARAGE BELOW BUILDING.
- EXISTING 10'-0" PUBLIC UTILITY & BICYCLE FACILITY EASEMENT.
- PROPOSED CONCRETE DRAINAGE CHANNEL ALONG PROPERTY LINE OUT TO EAGLE RANCH ROAD. REFER TO GRADING AND DRAINAGE PLAN.
- PROPOSED PLAZA (680 SF.) WITH BENCH SEATING.
- PROPOSED CONCRETE DRIVEWAY (STD. DWG. 2426) AND RAMPS (STD. DWG. 2426) TO BE CONSTRUCTED TO COA STANDARDS.
- TEMPORARY ASPHALT PAVING TO NEW DRIVEWAY LOCATION ON NUNZIO AVENUE (SHOWN HATCHED).
- TEMPORARY ASPHALT CURB ALONGSIDE TEMPORARY DRIVEWAY.
- THE NEW DRIVEWAY CURB INTO EXISTING CURB AND GUTTER SYSTEM. REFER TO GRADING AND DRAINAGE PLAN.
- PROPOSED OPENING IN EXISTING CURB AND GUTTER SYSTEM FOR DRAINAGE. REFER TO GRADING AND DRAINAGE PLAN.
- PROPOSED 6'-0" WIDE ADA ACCESSIBLE CONCRETE SIDEWALK (STD. DWG. 2430).
- PROPOSED CONCRETE VENT OPENING FROM UNDERGROUND PARKING TO GRADE ABOVE.
- PROPOSED CONCRETE ISLAND.
- PROPOSED STARWELL TO FIRST FLOOR.
- PROPOSED BUILDING COLUMNS.
- PROPOSED UNDERGROUND PARKING GATE.
- SUMP PUMP PIT WITH GRATE COVER. REFER TO GRADING AND DRAINAGE.

SITE DEVELOPMENT DATA:

**LEGAL DESCRIPTION:**  
TRACT H OF FOUNTAIN HILLS PLAZA SUBDIVISION, CITY OF ALBUQUERQUE, BERNALILLO COUNTY, NEW MEXICO

**LAND AREA:**  
0.9755 ACRES (42,493 SQ. FT.)

**CURRENT ZONING:**  
SU-1 FOR PDA TO INCLUDE C-3 USES (PERMISSIVE AND CONDITIONAL)

**ZONE ATLAS PAGE:**  
C-12-Z

**BUILDING AREAS: (GROSS BUILDING AREAS)**  
2-STORY DENTAL OFFICE: 10,674 GSF.  
7,678 GSF--1ST FLOOR  
2,996 GSF--2ND FLOOR  
FUTURE BUILDING (PHASE II): 3,000 SF.  
TOTAL GROSS BUILDING AREA 13,674 SF.

SITE DEVELOPMENT PHASING:

**PHASE I:**  
PHASE I WILL INCLUDE THE CONSTRUCTION OF PROPOSED 2-STORY DENTAL CLINIC, UNDERGROUND PARKING BELOW BUILDING FOOTPRINT, TEMPORARY PAVING OF ACCESS DRIVE THRU ADJACENT LOT 10-A-1 TO THE NORTH ONTO NUNZIO AVENUE NW, AND RELATED AT GRADE PARKING FOR PROPOSED USES.

**PHASE II:**  
PHASE II WILL INCLUDE THE CONSTRUCTION OF THE FUTURE BUILDING ONLY. PHASE II SHALL BE REVIEWED AND APPROVED BY THE DEVELOPMENT REVIEW BOARD (DRB) AND ADHERE TO THE DESIGN STANDARDS INCLUDED IN THE PREVIOUSLY APPROVED SITE DEVELOPMENT PLAN FOR SUBDIVISION.

SITE DEVELOPMENT GENERAL NOTES:

- THE DESIGN STANDARDS INCLUDED IN THE APPROVED SITE DEVELOPMENT PLAN FOR SUBDIVISION-FOUNTAIN HILLS PLAZA (EPC APPROVAL: MAY 2007 & DRB APPROVAL: JUNE 2007) SHALL GOVERN ALL NEW BUILDINGS FOR TRACT H OF THIS DEVELOPMENT.
- THE PARKING LOT DIMENSIONS ARE FROM FACE OF CURB TO FACE OF CURB.
- LANDSCAPING AND SIGNING WILL NOT INTERFERE WITH CLEAR SIGHT REQUIREMENTS. THEREFORE, SIGNS, WALLS, TREES, AND SHRUBBERY BETWEEN 3 AND 8 FEET TALL (AS MEASURED FROM THE GUTTER PAN) WILL NOT BE ACCEPTABLE IN THIS AREA.
- ANY ENCROACHMENT OR OVERHANG INTO THE ROW FROM SIGNS, FENCES, CANOPY, ROOF LINES, ETC. WILL REQUIRE AN ANNUAL REVOCABLE ENCROACHMENT PERMIT.
- ALL CURBS SURROUNDING LANDSCAPING SHALL PROVIDE WATER RUNOFF OPENINGS TO ALLOW SURFACE DRAINAGE INTO THE LANDSCAPED AREAS (WATER HARVESTING).
- ALL SIGNAGE AND FENCES WILL BE DONE UNDER SEPARATE PERMIT.

SITE DEVELOPMENT SITE LIGHTING NOTES:

- THE LOCATION OF THE LIGHTING FIXTURES TOGETHER WITH ITS OUT-OF-ANGLE SHALL BE SUCH THAT IT DOES NOT DIRECTLY SHINE ON ANY PUBLIC RIGHT-OF-WAY OR ADJACENT RESIDENTIAL PROPERTY.
- THE MAXIMUM HEIGHT OF A LIGHT POLE MEASURED FROM THE FINISH GRADE TO THE TOP OF THE POLE SHALL BE 20'-0" MAXIMUM.
- LIGHTING TO BE PROVIDED ON COMMERCIAL BUILDING FACADES SHALL BE MOUNTED AT 12 FEET MAXIMUM.
- SITE LIGHTING SHALL BE FULLY SHIELDED, AND HIGH-PRESSURE SODIUM LIGHTING AND UN-SHIELDED UPLIGHTING SHALL BE PROHIBITED AT 12 FEET MAXIMUM.

PARKING CALCULATIONS: (NET LEASABLE AREAS)

**PROPOSED 2-STORY DENTAL CLINIC:**  
7,178 NSF--1ST FLOOR/200 = 36 SPACES  
2,840 NSF--2ND FLOOR/300 = 9 SPACES

**REQUIRED SPACES** 45 SPACES

**FUTURE BUILDING: (PHASE II)**  
2,700 NSF./200 = 14 SPACES



**TOTAL REQUIRED SPACES** 59 SPACES  
**TOTAL REQUIRED**

**TRANSIT REDUCTIONS:**  
59 SPACES REQ'D x 10% REDUCTION = 53 SPACES (PROXIMITY TO BUS ROUTE 94)  
59 x 10% = 5.9 TOTAL SPACES REQUIRED

**TOTAL PARKING SPACES REQUIRED: = 53 SPACES**  
**TOTAL PARKING SPACES PROVIDED: = 53 SPACES**

43 REGULAR SPACES  
6 COMPACT SPACE  
4 HANDICAP VAN PARKING SPACE

PROJECT NUMBER:	APPLICATION NUMBER:
THIS PLAN IS CONSISTANT WITH THE SPECIFIC SITE DEVELOPMENT PLAN APPROVED BY THE ENVIRONMENTAL PLANNING COMMISSION (EPC) DATED: AND THE FINDINGS AND CONDITIONS IN THE OFFICIAL NOTIFICATION OF DECISION ARE SATISFIED.	
<b>IS AN INFRASTRUCTURE LIST REQUIRED? ( ) YES ( ) NO</b> IF YES, THEN A SET OF APPROVED DRC PLANS WITH A WORK ORDER IS REQUIRED FOR ANY CONSTRUCTION WITHIN PUBLIC RIGHT-OF-WAY OR FOR CONSTRUCTION OF PUBLIC IMPROVEMENTS.	
<b>DRB SITE DEVELOPMENT PLAN SIGNOFF APPROVAL:</b>	
TRAFFIC ENGINEER, TRANSPORTATION DIVISION	Date
UTILITIES DEVELOPMENT	Date
PARKS AND RECREATION DEPARTMENT	Date
CITY ENGINEER	Date
*ENVIRONMENTAL HEALTH DEPARTMENT (CONDITIONAL)	Date
SOLID WASTE MANAGEMENT APPROVAL IS ATTACHED AS SEPARATE SHEET	Date
SOLID WASTE MANAGEMENT	Date
DRB CHAIRPERSON, PLANNING DEPARTMENT	Date




project file: Smiles for Kids Dental Office  
9201 Eagle Ranch Road, NW  
Albuquerque, New Mexico 87114


sheet title: Site Development Plan For Building Permit

job number: 14-22  
drawn by: Douglas Heller, AIA  
project manager: Douglas Heller, AIA  
date: 12.12.2014






SITE CONCEPTUAL DRAINAGE MANAGEMENT PLAN



ACCESS ROAD CONCEPTUAL GRADING PLAN

- LEGEND**
- PROPERTY LINE
  - 5301- EXISTING CONTOURS
  - 65.23 PROPOSED SPOT ELEVATION
  - TC=TOP OF CURB, FL=FLOW LINE, TW=TOP OF WALL, BW=BOTTOM OF WALL, EX=EXISTING, TG=TOP OF GRADE
  - S=2.0% PROPOSED DIRECTION OF FLOW
  - ~~~~~ WATER BLOCK
  - ===== PROPOSED RETAINING WALL
  - 5305- PROPOSED INDEX CONTOURS
  - ===== PROPOSED INTER CONTOURS
  - ===== PROPOSED CURB & GUTTER
  - EASEMENT
  - SD PROPOSED STORM DRAIN LINE



FEMA FIRM MAP # 35001C0116G

**Smiles for Kids Dental Office**  
**Proposed Ultimate Development Conditions Basin Data Table**

This table is based on the DPM Section 22.2, Zone: 1

Basin ID	Area (SQ. FT)	Area (AC.)	Land Treatment Percentages				Q(100yr)	Q(100yr-6hr)	WT E	V(100yr-6hr)	V(100yr-10day)
			A	B	C	D	(cfs/ac.)	(CFS)	(inches)	(CF)	CF
Proposed											
1	42493	0.98	0.0%	0.0%	26.0%	74.0%	3.98	3.88	1.72	6074	9926
<b>TOTAL</b>	<b>42493</b>	<b>**0.98</b>						<b>3.88</b>			<b>***9926</b>

PROPOSED BASIN DATA TABLE

**INTRODUCTION:**

THE PROJECT IS LOCATED ON THE NORTHWEST INTERSECTION OF PASEO DEL NORTE BLVD AND EAGLE RANCH RD. THIS SITE IS NOT WITHIN A DEFINED FLOOD ZONE AS SHOWN ON FIRM MAP NUMBER 35001C0116G (THIS SHEET). THE PURPOSE OF THIS SUBMITTAL IS TO PROVIDE A DRAINAGE MANAGEMENT PLAN FOR THE DEVELOPMENT OF SMILES FOR KIDS DENTIST OFFICE AND REQUEST SITE DEVELOPMENT PLAN FOR BUILDING PERMIT APPROVAL.

**EXISTING CONDITIONS:**

THE 0.98 ACRE SITE IS CURRENTLY UNDEVELOPED. THE SITE SLOPES TO THE NORTH / NORTHEAST WHERE THE RUNOFF OPENLY DISCHARGES INTO EAGLE RANCH RD.

BASED ON THE DRAINAGE STUDY FOR FOUNTAIN HILLS (CITY OF ALBUQUERQUE DRAINAGE FILE #C12/D3B), THE ALLOWABLE PEAK DISCHARGE FROM THE SITE IS APPROXIMATELY 4.08 CFS.

**METHODOLOGY:**

THE HYDROLOGIC ANALYSIS PROVIDED WITH THIS DRAINAGE MANAGEMENT PLAN HAS BEEN PREPARED IN ACCORDANCE WITH SECTION 22.2 OF THE DPM. THE SITE IS LOCATED WEST OF THE RIO GRANDE WITHIN PRECIPITATION ZONE 1. LAND TREATMENT PERCENTAGES WERE CALCULATED BASED ON THE ACTUAL CONDITIONS IN EACH ONSITE BASIN AND ARE SUMMARIZED IN THE "PROPOSED BASIN DATA TABLE" (THIS SHEET).

**PROPOSED CONDITIONS:**


THIS DRAINAGE MANAGEMENT PLAN WAS DEVELOPED IN ACCORDANCE WITH A FULLY DEVELOPED SITE. IT WAS DETERMINED THAT THE MAXIMUM ALLOWABLE PEAK DISCHARGE FROM THE SITE IS APPROXIMATELY 4.08 CFS (AS MENTIONED ABOVE). THIS IS A SMALL SITE AND ACTS AS ONE DRAINAGE BASIN (BASIN 1).


THE ENTIRE SITE ACTS AS BASIN 1. THE ULTIMATE OUTFALL LOCATION IS EAGLE RANCH ROAD THROUGH MEANS OF RIBBON CHANNEL AND SEVERAL SMALL PONDS USED TO MITIGATE THE FIRST FLUSH. A PORTION OF THE SITE DRAINS INTO THE PARKING GARAGE. THAT FLOW IS THEN DIRECTED INTO A SUMP PUMP WHERE IT DISCHARGES INTO THE ADJACENT RIBBON CHANNEL AND ULTIMATELY OUTFALLS INTO EAGLE RANCH RD.

OFFSITE PRIVATE ACCESS ROAD IS NOT INCLUDED IN THE CALCULATION. RUNOFF FROM TRACT 10-A-1 WILL BE ADDRESSED WITH THE DEVELOPMENT OF THAT TRACT.


**CONCLUSION:**

THE PEAK DISCHARGE FROM THE SITE IS 3.88 CFS WHICH IS LESS THAN THE ALLOWABLE PEAK DISCHARGE RATE, THEREFORE WE ARE IN CONFORMANCE WITH CITY OF ALBUQUERQUE HYDROLOGY REQUIREMENTS AND REQUEST SITE DEVELOPMENT PLAN FOR BUILDING PERMIT APPROVAL.





**SITE CONCEPTUAL GRADING PLAN**



**ACCESS ROAD CONCEPTUAL GRADING PLAN**




**VICINITY MAP: C-12**

**GRADING KEYED NOTES**

1. INSTALL SIDEWALK CULVERT
2. INSTALL RIBBON CHANNEL
3. INSTALL RETAINING WALL
4. INSTALL SUMP PUMP
5. POND FOR FIRST FLUSH

**LEGEND**

- PROPERTY LINE
- 5.301- EXISTING CONTOURS
- 65.23 PROPOSED SPOT ELEVATION
- TC=TOP OF CURB, FL=FLOW LINE
- TW=TOP OF WALL, BW=BOTTOM OF WALL
- EX=EXISTING, TG=TOP OF GRADE
- S=2.0% PROPOSED DIRECTION OF FLOW
- ~~~~~ WATER BLOCK
- ===== PROPOSED RETAINING WALL
- 5.305 PROPOSED INDEX CONTOURS
- ===== PROPOSED INTER CONTOURS
- ===== PROPOSED CURB & GUTTER
- - - - - EASEMENT
- SD PROPOSED STORM DRAIN LINE




revision	
by	
date	
rev	◀◀◀◀

**MH**  
Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]

job number	20150304
drawn by	MHS
project manager	GSR
date	12.12.2014

project title  
**Smiles for Kids Dental Office**  
9201 Eagle Ranch Road, NW,  
Albuquerque, New Mexico 87114  
sheet title  
**Conceptual Grading Plan**




**SITE CONCEPTUAL UTILITY PLAN**

**UTILITY KEYED NOTES**

1. CONNECT TO EXISTING 12" WATERLINE
2. INSTALL 1-1/2" WATER METER
3. INSTALL NEW DOMESTIC SERVICE LINE
4. INSTALL NEW FIRE PROTECTION LINE
5. INSTALL NEW PRIVATE FIRE HYDRANT
6. INSTALL HEATED ENCLOSURE FOR DOMESTIC AND FIRE PROTECTION REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTER
7. INSTALL POST INDICATOR VALVE
8. STUB TO WITHIN 5' OF BUILDING
9. CONNECT TO EXISTING 8" SAS LINE
10. INSTALL NEW SAS SERVICE LINE


**LEGEND**

---	PROPERTY LINE
- - - -	EXISTING EASEMENT
---	EXISTING SANITARY SEWER
---	EXISTING WATER LINE
- - - -	PROPOSED EASEMENT
SAS	PROPOSED SANITARY SEWER LINE
●	PROPOSED SANITARY SEWER MANHOLE
● <sub>CO</sub>	PROPOSED CLEANOUT
WL	PROPOSED WATER LINE
X	PROPOSED VALVE
FL	PROPOSED FIRE LINE
●	PROPOSED HYDRANT
□	PROPOSED CAP
■	PROPOSED WATER METER
● <sub>PIV</sub>	PROPOSED POST INDICATOR VALVE




revision	
by	
date	
rev	◀◀◀◀◀

**MH**  
**Mullen Heller**  
 Architecture P.C.  
 924 Park Avenue SW  
 Suite B  
 Albuquerque 87102  
 505 268 4144 [p]  
 505 268 4244 [f]




job number	20150304
drawn by	MHS
project manager	GSS
date	12.12.2014

project title  
**Smiles for Kids Dental Office**  
 9201 Eagle Ranch Road, NW,  
 Albuquerque, New Mexico 87114  
 sheet title  
**Conceptual Utility Plan**



The Hilltop  
1909 Edith NE  
Albuquerque, NM 87184  
Cont. Lic. #16468  
PH: (505) 890-9690  
Fax: (505) 890-1131  
danny@hilltoplandscaping.com

Landscape Architect



Mullen Heller  
Architecture P.C.

924 Park Avenue SW

Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]

Fountain Hills Dental  
920 Eagle Ranch Rd  
Albuquerque, NM 87114

LANDSCAPE PLAN


The design contained herein remains the property of The Hilltop Landscape Architects and Contractors. It is not to be reproduced, copied, or used in any other project without the written consent of The Hilltop Landscape Architects and Contractors. This is an original design and any copies released or reproduced without the written consent of The Hilltop Landscape Architects and Contractors have been filed or a job order placed.



DRAWN BY  
on  
REVISIONS  
01/15/2015

DATE  
01/14/15

SHEET  
LS-101



**LANDSCAPE LEGEND**

QTY	SIZE	COMMON/BOTANICAL	H2O USE
<b>Trees</b>			
3	2" Cal.	Ash <i>Fraxinus sp.</i>	M+
2	2" cal	Honey Locust <i>Gleditsia triacanthos</i>	M
1	6 - 8'	Austrian Pine <i>Pinus nigra</i>	M
2	4 - 6'	Palm Yucca <i>Yucca faxoniana</i>	M
11	15 Gal.	Oklahoma Redbud 15x12 <i>Cercis reniformis</i>	M
<b>Shrubs &amp; Groundcovers</b>			
6	15 Gal.	Desert Willow <i>Chilopsis linearis</i>	625 3750 M
9	5 Gal.	India Hawthorn <i>Raphiolepis indica</i>	25 225 M
14	5 Gal.	Feather Reed Grass <i>Calamagrostis arundinacea</i>	4 56 M
16	5 Gal.	Wintergreen Barberry <i>Berberis julianae</i>	25 400 M
3	5 Gal.	Butterfly Bush <i>Buddleia davidii</i>	25 75 M
9	5 Gal.	Winter Jasmine <i>Jasminum nudiflorum</i>	144 1296 M
12	5 Gal.	Buffalo Juniper <i>Juniperus sabino 'Buffalo'</i>	144 1728 M
3	5 Gal.	Cherry Sage <i>Salvia greggii</i>	9 27 M
2	5 Gal.	Blue Mist <i>Caryopteris x clandonensis</i>	9 18 M
3	5 Gal.	Fern Bush <i>Chamaebotaria millefolium</i>	36 108 L
6	5 Gal.	Apache Plume <i>Fallugia paradoxa</i>	49 294 L
7	5 Gal.	Chemisa <i>Chrysothamnus nauseosus</i>	25 175 L
8	2-3cf	Boulders To be placed at contractor discretion	8152
		Landscape Gravel / Filter Fabric 3/4" Crushed Grey / Filter Fabric	2689
		Landscape Gravel / Filter Fabric 7/8" Santa Fe Brown / Filter Fabric	6878
		Oversize Landscape Gravel / Filter Fabric 2-4" Adobe Rose	100

**LANDSCAPE NOTES:**  
Landscape maintenance shall be the responsibility of the Property Owner. The Property Owner shall maintain street trees in a living, healthy, and attractive condition.

It is the intent of this plan to comply with the City of Albuquerque Water Conservation Landscaping and Water Waste Ordinance planting restriction approach. Approval of this plan does not constitute or imply exemption from water waste provisions of the Water Conservation Landscaping and Water Waste Ordinance.

Water management is the sole responsibility of the Property Owner. All landscaping will be in conformance with the City of Albuquerque Zoning Code, Street Tree Ordinance, Pollen Ordinance, and Water Conservation Landscaping and Water Waste Ordinance. In general, water conservative, environmentally sound landscape principles will be followed in design and installation.

Plant beds shall achieve 75% live ground cover at maturity.  
Brown Gravel over Filter Fabric to a minimum depth of 3" shall be placed in all landscape areas which are not designated to receive native seed.

No changes or substitutions shall be made to this plan without the express written consent of the Landscape Architect of record.

This plan is the exclusive property of the Hilltop and is provided to the client per a design build agreement. If the Hilltop is not the landscape installation contractor, a design fee equal to 5% of the contract shall be paid to the Hilltop by the owner, prior to release of plans.

The Landscape Architect of record reserves the right to inspect the installation and reject any and all irrigation, plant materials and gravel, and have replaced at the contractor's expense, any item not in compliance with the intent of this plan.

**IRRIGATION NOTES:**  
Irrigation shall be a complete underground system with Trees to receive 1 Netafim spiral (50' length) with 3 loops at a final radius of 4.5' from tree trunk, placed in place. Netafim shall have emitters 12" o.c. with a flow of 1/2 gph. Shrubs to receive (2) 1/2 GPH Drip Emitters. Drip and Bubbler systems to be tied to 1/2" poly pipe with flush caps at each end. Trees and shrubs shall be on separate valves.

Run time per each shrub drip valve will be approximately 15 minutes per day. Tree drip valves shall run 15 hours, 3 times per week. Run time will be adjusted according to the season.

Point of connection for irrigation system is unknown at current time and will be coordinated in the field. Irrigation will be operated by automatic controller.

Location of controller to be field determined and power source for controller to be provided by others.



Irrigation maintenance shall be the responsibility of the Property Owner.

Water and Power source shall be the responsibility of the Developer/Builder.

**LANDSCAPE CALCULATIONS**

TOTAL LOT AREA (sf)	42493
MINUS TOTAL BUILDING AREA (sf)	-7608
MINUS PHASE TWO	-5527
TOTAL LOT AREA OF PHASE ONE (sf)	29358
LANDSCAPE REQUIREMENT	x 20
TOTAL LANDSCAPE REQUIRED (20%)	5872

LANDSCAPE PROVIDED (32.58%)	9567
TOTAL LIVE GROUND COVER REQUIRED (75%)	7175
TOTAL LIVE GROUND COVER PROVIDED (85%)	8152



**TREE PLANTING DETAIL**


NTS

**GENERAL NOTES:**

1. ROOTBALL SHALL BE PLACED ON UNDISTURBED SOIL TO PREVENT TREE FROM SETTLING.
2. TOP OF ROOTCOLLAR INDICATED LEVEL AT WHICH TREE WAS GROWN AND DUG; THIS REPRESENTS THE LEVEL AT WHICH THE TREE SHOULD BE INSTALLED; THAT LEVEL MAY BE EXCEEDED BY ONLY A ONE INCH LAYER OF SOIL.
3. PRIOR TO BACKFILLING TREE, ALL WIRE, ROPE AND SYNTHETIC MATERIALS SHALL BE REMOVED FROM THE TREE AND THE PLANTING PIT.
4. PRIOR TO BACKFILLING ALL BURLAP SHALL BE CUT AWAY EXCEPT FROM BOTTOM OF THE ROOTBALL.

**CONSTRUCTION NOTES:**

- A. TREE
- B. BACKFILL WITH EXISTING SOIL.
- C. 3" DEPTH OF GRAVEL MULCH.
- D. UNDISTURBED SOIL.



**SHRUB PLANTING DETAIL**




NTS


**GENERAL NOTES:**

1. THE OUTSIDE DIAMETER OF THE WATER RETENTION BASIN SHALL BE TWICE THE DIAMETER OF THE SHRUB PLANTING PIT.


**CONSTRUCTION NOTES:**

- A. SHRUB
- B. BACKFILL WITH EXISTING SOIL.
- C. EARTH BERM AROUND WATER RETENTION BASIN.
- D. 3" DEPTH OF GRAVEL MULCH.
- E. FINISH GRADE.
- F. UNDISTURBED SOIL.







1 West Elevation  
Scale: 1/8" = 1'-0"



2 South Elevation  
Scale: 1/8" = 1'-0"



3 North Elevation  
Scale: 1/8" = 1'-0"



4 East Elevation  
Scale: 1/8" = 1'-0"

- GENERAL NOTES:
- [A] ALL DIMENSIONS ARE FROM FACE OF STUD TO FACE OF STUD, UNLESS OTHERWISE NOTED.
  - [B] THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD. IF DIMENSIONAL ERROR, VARIANCES, AND/OR CONFLICTS EXIST, AS DESCRIBED WITHIN THE CONSTRUCTION DOCUMENTS, OR CONDITIONS ARE ENCOUNTERED THAT ARE NOT COVERED IN THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT BEFORE COMMENCING THAT PORTION OF THE WORK.
  - [C] CONTRACTOR TO VERIFY SIZES OF ALL OWNER PROVIDED EQUIPMENT PRIOR TO INSTALLATION.
  - [D] ALL CONSTRUCTION SHALL BE IN COMPLIANCE WITH ALL APPLICABLE BUILDING CODES, MODEL CODES, LOCAL CODES, LAWS AND ORDINANCES.

- KEYED NOTES:
- [1] ALUMINUM STOREFRONT SYSTEM, CLEAR ANNOZIZED FRAME WITH SPANDREL GLAZING.
  - [2] ALUMINUM STOREFRONT SYSTEM, CLEAR ANNOZIZED FRAME WITH TINTED GLAZING.
  - [3] FIELD-1: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: LIGHT TAN
  - [4] FIELD-2: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: TAN
  - [5] FIELD-3: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: LIGHT BROWN
  - [6] ACCENT 1: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: ORANGE (EARTH TONE)
  - [7] ACCENT 2: 2-COAT SYNTHETIC STUCCO SYSTEM WITH ELASTOMERIC FINISH COAT. COLOR: GREEN (EARTH TONE)
  - [8] NATURAL STONE VENEER FINISH.
  - [9] METAL PARAPET CAP TO MATCH ADJACENT FINISH COLOR.
  - [10] METAL WALL PANEL SYSTEM (NON CORRUGATED). LIGHT TAN OR GRAY.
  - [11] METAL RAILING; PAINTED DARK EARTH TONE.
  - [12] ALUMINUM STOREFRONT DOOR, CLEAR ANNOZIZED FRAME WITH SPANDREL LIGHT.
  - [13] HOLLOW METAL DOOR PAINTED TO MATCH STUCCO.
  - [14] METAL CANOPY TO MATCH STOREFRONT FINISH.
  - [15] 12" HIGH ADDRESS CHANNEL LETTERS.
  - [16] STUCCO CONTROL JOINT.

EXISTING BUILDING C  
SIGNAGE CALCULATIONS:  
BUILDING MOUNTED:


WEST ELEVATION- 2900 SF X 9%	234 SF ALLOWED
	85 SF ILLUMINATED PROVIDED
SOUTH ELEVATION- 1194 SF X 9%	126 SF ALLOWED
	120 SF ILLUMINATED PROVIDED
EAST ELEVATION- 2900 SF X 9%	107 SF ALLOWED
	96 SF ILLUMINATED PROVIDED
NORTH ELEVATION- 1189 SF X 9%	107 SF ALLOWED
	99 SF ILLUMINATED PROVIDED

revision	
by	
date	
rev	1 2 3 4


**MH**  
Mullen Heller  
Architecture P.C.  
924 Park Avenue SW  
Suite B  
Albuquerque, NM 87102  
505 268 4144 [p]  
505 268 4244 [f]

job number	14-22
drawn by	ov
project manager	Douglas Heller, AIA
date	12.12.2014


project title  
**Smiles for Kids Dental Office**  
9201 Eagle Ranch Road, NW,  
Albuquerque, New Mexico 87114  
sheet title  
**Exterior Elevations**




1 Dumpster Enclosure Plan  
Scale: 1/8" = 1'-0"




2 Dumpster Enclosure Front Elevation  
Scale: 3/8" = 1'-0"




3 Dumpster Enclosure Side Elevation  
Scale: 3/8" = 1'-0"




4 Refuse Enclosure Wall Section  
Scale: 1" = 1'-0"




5 H.C. Ramp Detail  
Scale: Not To Scale (Isometric)




6 HC Parking Striping Detail  
Scale: 1/4" = 1'-0"




7 HC Pavement Sign Detail  
Scale: 3/4" = 1'-0"




8 Bicycle Rack Detail  
Scale: 3/4" = 1'-0"



9 Light Pole Elevation Detail  
Scale: 1" = 1'-0"



10 HC Parking Sign Detail  
Scale: 3/4" = 1'-0"




11 MC Parking Sign Detail  
Scale: 3/4" = 1'-0"

revision	
by	
date	
rev	1 2 3 4



Mullen Heller  
Architecture P.C.

924 Park Avenue SW  
Suite B  
Albuquerque 87102  
505 268 4144 [p]  
505 268 4244 [f]



job number	14-22
drawn by	av
project manager	Douglas Heller, AIA
date	12.12.2014

project title  
**Smiles for Kids Dental Office**  
9201 Eagle Ranch Road, NW,  
Albuquerque, New Mexico 87114  
sheet title  
**Site Details**

sheet  
**A002**

**SHEET 7 OF 7**