

NOTES:
 1) SIGNS DEPICTED ARE ILLUSTRATIVE.
 2) PROPOSED SIGNAGE FOR CONSTRUCTION WILL BE PROVIDED BY BUILDING PERMIT.

Taco Bell - 12" Channel Letter

FRONT VIEW
 12" height, 5'-11 3/8" width for 'TACO', 5'-7 13/16" width for 'BELL'.

ILLUMINATION LAYOUT
 Shows LED quantities and spacing based on system used.

TYPICAL SECTION
 Labels include: 1/2" DIA. PIPE SPACER, BUILDING FINISH, 3/8" DIA. FASTENER WITH NUT, FLAT & LOCK WASHER, TO PRIMARY POWER SUPPLY, WALL STUD ON 16" CTRS., PLYWOOD SHEATHING, WOOD BLOCKING, .063 ALUM BACK, .150 SG POLYCARBONATE, 1" JEWELITE, .040 RETURNS, 1/4" DIA. WEEP HOLE.

SPECIFICATIONS
DESIGN PARAMETERS
 • Structural adequacy shall be the manufacturer's responsibility using the following criteria:
 • 110 MPH 3 second gust wind speed, Exposure C, Category II, Components & Cladding, Zone 5.
 • Attachment may vary based on wall conditions.
 • Compliant with national building codes and standards (IBC 2009, AISC 13th Edition, ASCE 7-05, ACI & Aluminum Design Manual).
 • Refer to written documentation for material specifications.
Materials
 • Cabinet: .040 aluminum returns w/ white finish and .063 aluminum back
 • 1" white Jewelite trim
 • Face: .150 SG polycarbonate
 • Removable face
Area
 • Squared: 12.17 sf
 • Actual: 8.18 sf
ELECTRICAL PERFORMANCE SPECIFICATIONS
 • NEC approval required.
 • 12V, Class II UL approved system.
 • 50,000 hour system where no greater than 30% lumen depreciation is experienced at 50K hours.
 • Thermally managed surface mount devices (SMD).
 LED(s): (77) HighLight LS-CORE-50K-G2 White (5000K) LEDs (25 ft) or equivalent - pre-approval required
 Power Supply: (1) General LED PS 12-60W-100-277V @ 0.8 amps or equivalent - Remotely Located
 Total Load: 0.8 amps
 Circuit(s): (1) 20 amp-120V
GRAPHIC & COLOR SPECIFICATIONS:
 • TB Bronze Tiger Drylac 48-66230 C33
 • PMS 285U
 • Amber Wave SW-887 PMS 138U
 • PMS 131U
 • PMS 135U
 • Yellow PMS 108U
 • Pantone Process Magenta U
 • Pantone Violet U
 • Pantone Black
 • Benjamin Moore Bavarian Cream White #2148-70
 • Violet 3M Vinyl 3830-9126
 • White Matte - Cabinet Interior

YUM! BRANDS - 1900 COLONEL SANDERS LANE - LOUISVILLE, KY 40213 - 502.874.3800

Taco Bell - Swinging Bell - Formed Face

FRONT VIEW
 58 1/2" width, 54.34" height.

ILLUMINATION LAYOUT
 Shows LED quantities and spacing based on system used.

TYPICAL SECTION
 Labels include: 1/2" DIA. PIPE SPACER, BUILDING FINISH, 3/8" DIA. FASTENER WITH NUT, FLAT & LOCK WASHER, TO PRIMARY POWER SUPPLY, WALL STUD ON 16" CTRS., PLYWOOD SHEATHING, WOOD BLOCKING, .080 ALUM BACK, .150 SG POLYCARBONATE VACUUM-FORMED, .050 RETURNS, 1/4" DIA. WEEP HOLE.

SPECIFICATIONS
DESIGN PARAMETERS
 • Structural adequacy shall be the manufacturer's responsibility using the following criteria:
 • 110 MPH 3 second gust wind speed, Exposure C, Category II, Components & Cladding, Zone 5.
 • Attachment may vary based on wall conditions.
 • Compliant with national building codes and standards (IBC 2009, AISC 13th Edition, ASCE 7-05, ACI & Aluminum Design Manual).
 • Refer to written documentation for material specifications.
Materials
 • Cabinet: .050 aluminum returns w/ violet finish and .080 aluminum back
 • Face: .150 SG polycarbonate vacuum formed
 • Second surface depression
 • Removable face for service
Area
 • Squared: 22.24 sf
 • Actual: 14.19 sf
 • Weight (Est.): 100 lbs
ELECTRICAL PERFORMANCE SPECIFICATIONS
 • NEC approval required.
 • 12V, Class II UL approved system.
 • 50,000 hour system where no greater than 30% lumen depreciation is experienced at 50K hours.
 • Thermally managed surface mount devices (SMD).
 LED(s): (30) HighLight LS-APEX-50K-G2 White (5000K) LEDs (18 ft) or equivalent - pre-approval required
 Power Supply: (1) General LED PS 12-60W-100-277V @ 0.8 amps or equivalent
 Total Load: 0.8 amps
 Circuit(s): (1) 20 amp-120V
GRAPHIC & COLOR SPECIFICATIONS:
 • TB Bronze Tiger Drylac 48-66230 C33
 • PMS 285U
 • Amber Wave SW-887 PMS 138U
 • PMS 131U
 • PMS 135U
 • Yellow PMS 108U
 • Pantone Process Magenta U
 • Pantone Violet U
 • Pantone Black
 • Benjamin Moore Bavarian Cream White #2148-70
 • Violet 3M Vinyl 3830-9126
 • White Matte - Cabinet Interior

YUM! BRANDS - 1900 COLONEL SANDERS LANE - LOUISVILLE, KY 40213 - 502.874.3800

12134.230
 DRB 1ST SUB 09.08.16
 CONTRACT DATE: --
 BUILDING TYPE: EXP. LITE MED4
 PLAN VERSION: SEPTEMBER 2015
 SITE NUMBER: --
 STORE NUMBER: --

TACO BELL
 UNSER BLVD NW & McMAHON BLVD. NW
 ALBUQUERQUE, NM 87114

EXPLORER LITE
 MEDIUM 40

SIGNAGE CUT SHEETS

A4.2