



- NOTES:
- REFER TO GEOTECH REPORT FOR MIX REQUIREMENTS AND FINAL PAVEMENT DESIGN.
 - SUBGRADE SHALL BE PREPARED PER GEOTECH REPORT.
 - PAVEMENT SECTIONS:
#1 = TRUCK LOADING AREA & OUTDOOR LOT
#2 = SIDEWALKS
 - PROVIDE 6X6
 - CONCRETE SHALL BE 4500 PSI MIN OR GREATER IF REQUIRED BY GEOTECH.
 - FENCED OUTDOOR YARD AREA CONCRETE SECTION SHALL HAVE A BROOM FINISH AND INCLUDE TUFSTRAND SF FIBER @ 3LBS / CY
- CONCRETE PAVEMENT SECTIONS**
N.T.S.


- NOTES:
- REFER TO GEOTECH REPORT FOR MIX REQUIREMENTS AND FINAL PAVEMENT DESIGN.
 - SUBGRADE SHALL BE PREPARED PER GEOTECH REPORT.
 - PAVEMENT SECTIONS:
#1 = STANDARD DUTY
#2 = HEAVY DUTY
- ASPHALT PAVEMENT SECTIONS**
N.T.S.




- NOTES:
- 5000 PSI CONCRETE WITH FIBERMESH REINFORCEMENT, OR 4X4 WWM WITH 2" MIN COVER.
 - BRUSHED FINISH ON ALL EXPOSED CONCRETE.
 - TOOL CONTRACTION JOINT IN EVERY 10FT O.C.
 - COMPACT SUBGRADE PER GEOTECHNICAL RECOMMENDATIONS, COMPACT TO 95% STANDARD PROCTOR MINIMUM.
 - CONCRETE THICKNESS PER GEOTECHNICAL RECOMMENDATIONS - 4" MIN.
 - PROVIDE SUBGRADE BASE COURSE PER GEOTECHNICAL RECOMMENDATIONS.
 - TACTILE WARNING TO BE 2X4" PAD WITH RAISED DOMES. PROVIDE ADHESIVE YELLOW TYPE AS THE MINIMUM. REFER TO GOVERNING JURISDICTION OR ARCHITECT FOR ADDITIONAL REQUIREMENTS.
 - PROVIDE 1/2" RADIUS ON ALL EDGES.
 - SIDEWALK SLOPE AT THE TOP OF THE RAMP SHALL BE NO MORE THAN 5.0%.
 - ADJUST RAMP LENGTH AS NEEDED TO MAINTAIN A MAX SLOPE OF 8.33%.
 - ANY RAMP LONGER THAN 10FT WILL REQUIRE A HANDRAIL, BUILT TO ADA STANDARDS
 - ADJUST RAMP WIDTH TO MATCH SIDEWALK.
- TWO WAY ADA RAMP W/ LANDING**
N.T.S.



- NOTES:
- CONCRETE SHALL BE 4000 PSI MIN.
 - SUBGRADE SHALL BE PREPARED PER GEOTECH REPORT.
 - REFER TO SITE PLAN FOR BOLLARD LOCATION AND SIZE.
 - BOLLARD SHALL BE SCH 40 GALVANIZED STEEL PIPE PAINTED OSHA YELLOW AND FILLED WITH CONCRETE.
 - BOLLARDS SHALL BE FACTORY COLORED "TAN." EQUAL ALTERNATE ALLOWED
- BOLLARD DETAILS**
N.T.S.



- NOTES:
- 5000 PSI CONCRETE WITH FIBERMESH REINFORCEMENT.
 - BRUSHED FINISH ON ALL EXPOSED CONCRETE.
- PRIVATE CURB & GUTTER**
N.T.S.



PRIVATE ADA RAMP
N.T.S.

12134.230

- △EPC 1ST SUB 03.30.16
- △EPC 2ND SUB 05.02.16
- △DRB 1ST SUB 10.03.16

CONTRACT DATE: APRIL 24, 2016
BUILDING TYPE: EXPLORER MEDS4
PLAN VERSION: APRIL 2015 (N)
SITE NUMBER:
STORE NUMBER:

TACO BELL
UNSER BLVD
ALBUQUERQUE, NM 87114



DETAIL SHEET 3

D3.0