

Subdivision Data

GROSS ACREAGE.	
ZONE ATLAS PAGE NO	•••••
NUMBER OF EXISTING LOTS	
NUMBER OF LOTS CREATED.	
MILES OF FULL WIDTH STREETS	0.00
MILES OF HALF WIDTH STREETS	0.00
RIGHT-OF-WAY DEDICATION TO THE CI	TY OF ALBUQUERQUE 0 0031 ACRES
DATE OF SURVEY	••••••••••••••••••••••••••••••••••••••

Purpose of Plat

- 1. ELIMINATE ALL INTERIOR LOT LINES BETWEEN THE EXISTING THREE MRGCD TRACTS SUBDIVIDED AS SHOWN HEREON.
- 2. DEDICATE ADDITIONAL RIGHT-OF-WAY AS SHOWN HEREON.

Free Consent & Dedication

THE SUBDIVISION HEREON DESCRIBED IS WITH THE FREE CONSENT AND AND IN ACCORDANCE WITH THE DESIRES OF THE UNDERSIGNED OWNER(S) AND/OR PROPRIETOR(S) THEREOF AND HEREBY DEDICATE, TO THE CITY OF ALBUQUERQUE, ADDITIONAL RIGHT-OF-WAY IN FEE SIMPLE WITH WARRANTY COVENANTS AS SHOWN HEREON. SAID OWNER(S) AND/OR PROPRIETOR(S) DO HEREBY CONSENT TO ALL OF THE FOREGOING AND DO HEREBY CERTIFY THAT THIS SUBDIVISION IS THEIR FREE ACT AND DEED. SAID OWNER(S) WARRANT THAT THEY HOLD AMONG THEM COMPLETE AND INDEFEASIBLE TITLE IN FEE SIMPLE TO THE LAND SUBDIVIDED.

CARL DAVIDSON	DATE
SANDRA DAVIDSON	DATE

Acknowledgment

STATE OF NEW MEXICO

SS

COUNTY OF BERNALILLO

THIS INSTRUMENT WAS ACKNOWLEDGED BEFORE ME ON

BY: CARL & SANDRA DAVIDSON, HUSBAND AND WIFE

NOTARY PUBLIC

MY COMMISSION EXPIRES

Indexing Information

Section 8, Township 10 North, Range 3 East, NMPM as Projected into the Town of Albuquerque Grant Subdivision: MRGCD Map No. 36
Owner: Carl & Sandra Davidson
UPC #101405917203830806 — Tract 52A1B
#101405917203830806 — Tract 52A1A2 & Tract 71

Notes

1. FIELD SURVEY PERFORMED IN NOVEMBER 2006 & SUPPLEMENTAL DATA COLLECTED AUGUST 2012.

2. ALL DISTANCES ARE GROUND DISTANCES: U.S. SURVEY FOOT.

3. THE SUBJECT PROPERTY IS LOCATED IN SECTION 8, TOWNSHIP 10, RANGE 3 EAST, AS PROJECTED INTO THE TOWN OF ALBUQUERQUE GRANT.

4. THE BASIS OF BEARINGS REFERENCES THE NEW MEXICO STATE PLANE COORDINATES (NAD 83-GRID).

5. LOT LINES TO BE ELIMINATED ARE SHOWN AS THUS

Documents

- 1. TITLE COMMITMENT PROVIDED BY LANDAMERICA ALBUQUERQUE TITLE FILED NUMBER 6218001858 WITH AN EFFECTIVE DATE OF OCTOBER 23, 2006.
- 2. MIDDLE RIO GRANDE CONSERVANCY DISTRICT MAP NUMBER 36.

Legal

A CERTAIN TRACT OF LAND COMPRISING OF TRACT 71, TRACT 52A1A2 AND TRACT 52A1B AS SHOWN ON M.R.G.C.D. MAP NO. 36, IN THE CITY OF ALBUQUERQUE, BERNALILLO COUNTY, NEW MEXICO, AND BEING MORE PARTICULARLY DESCRIBED BY METES AND BOUNDS AS FOLLOWS:

BEGINNING AT THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED TRACT ALSO BEING THE NORTHWEST CORNER OF THE INTERSECTION OF SIXTH STREET, N.W. AND THE A.T. & S.F. RAILROAD SPUR RIGHT-OF-WAY, WHENCE A TIE TO ACS MONUMENT "A_438" BEARS N 42'02'58" E, A DISTANCE OF 3826.15:

THENCE FROM THE POINT OF BEGINNING, COINCIDING WITH NORTHERLY RIGHT-OF-WAY LINE OF THE A.T. & S.F. RAILROAD SPUR, N 87°00'35" W. A DISTANCE OF 242.29 FEET TO AN ANGLE POINT MARKED BY A 1/2" REBAR;

THENCE, COINCIDING SAID NORTHERLY RIGHT-OF-WAY THE FOLLOWING THREE COURSES:

N 86°07'55" W A DISTANCE OF 81.90 FEET TO AN ANGLE POINT MARKED BY A BATHEY MARKER LS#14271;

N 82'23'55" W A DISTANCE OF 80.53 FEET TO AN ANGLE POINT MARKED BY A BATHEY MARKER LS#14271;

N 80°45'55" W A DISTANCE OF 2.65 FEET TO THE SOUTHWEST CORNER OF THE HEREIN DESCRIBED TRACT MARKED BY A BATHEY MARKER LS#14271;

THENCE, LEAVING SAID RIGHT-OF-WAY, N 10°33'15" E, A DISTANCE OF 101.37 FEET TO AN ANGLE POINT MARKED BY A BATHEY MARKER LS#14271;

THENCE, N 08°36'40" E, A DISTANCE OF 105.33 FEET TO THE NORTHWEST CORNER OF THE HEREIN DESCRIBED TRACT, MARKED BY A BATHEY MARKER LS#14271, LYING ON THE SOUTHERLY RIGHT-OF-WAY OF HAINES AVENUE, N.W.;

THENCE, COINCIDING WITH SAID HAINES AVENUE, N.W., RIGHT-OF-WAY, S 80°45'35" E, A DISTANCE OF 404.37' TO THE NORTHEAST CORNER OF THE HEREIN DESCRIBED TRACT, ALSO BEING LOCATED ON THE WESTERLY RIGHT-OF-WAY LINE OF 6TH STREET, N.W.

THENCE, COINCIDING WITH SAID 6TH STREET, N.W., RIGHT-OF-WAY, S 09'14'25" W, A DISTANCE OF 170.32' TO THE POINT OF BEGINNING CONTAINING 1.7754 ACRES (77,338 SQ. FT.) MORE OR LESS.

Middle Rio Grande Conservancy District

APPROVED ON THE CONDITION THAT ALL RIGHTS OF THE MIDDLE RIO GRANDE CONSERVANCY DISTRICT IN EASEMENTS, RIGHTS OF WAY, ASSESSMENTS AND LIENS, ARE FULLY RESERVED TO SAID DISTRICT, AND THAT IF PROVISION FOR IRRIGATION SOURCE AND EASEMENTS ARE NOT PROVIDED FOR BY THE SUBDIVIDER FOR THE SUBDIVISION, ADDITION, OR PLAT, SAID DISTRICT IS ABSOLVED OF ALL OBLIGATIONS TO FURNISH IRRIGATION WATERS AND SERVICES TO ANY PORTIONS THEREOF, OTHER THAN FROM EXISTING TURNOUTS.

APPROVED BY

DATE

Plat of Lot 1, Lands of Sandra & Carl Davidson

Comprising of
Tracts 71, 52A1A2, and 52A1B
MRGCD Map Number 36
City of Albuquerque
Bernalillo County, New Mexico
August 2012

Approved and Accepted by:

APPROVAL AND CONDITIONAL ACCEPTANCE AS SPECIFIED BY THE ALBUQUERQUE SUBDIVISION ORDINANCE, CHAPTER 14 ARTICLE 14 OF THE REVISED ORDINANCES OF ALBUQUERQUE, NEW MEXICO, 1994.

fara fara and a same of the fara and a same	
approvals:	
PNM Electric Services	
	Dat
New Mexico Gas Company	Dat
Qwest Corp. d/b/a CenturyLink QC	Date
Comcast	Date
approvals:	Date
City Surveyor	Dat∈
Traffic Engineer	
Stric Engineer	Date
	Date
Real Property Division	Date
Real Property Division ABCWUA	Date Date
Real Property Division	Date
Real Property Division ABCWUA Parks and Recreation Department	Date Date
Real Property Division ABCWUA	Date Date
Real Property Division ABCWUA Parks and Recreation Department	Date Date
Real Property Division ABCWUA Parks and Recreation Department	Date Date Date
Real Property Division ABCWUA Parks and Recreation Department AMAFCA	Date Date

Surveyor's Certificate

"I, WILL PLOTNER JR., A DULY QUALIFIED REGISTERED PROFESSIONAL LAND SURVEYOR UNDER THE LAWS OF THE STATE OF NEW MEXICO, DO HEREBY CERTIFY THAT THIS PLAT AND DESCRIPTION WERE PREPARED BY ME OR UNDER MY SUPERVISION, SHOWS ALL EASEMENTS AS SHOWN ON THE PLAT OF RECORD OR MADE KNOWN TO ME BY THE OWNERS AND/OR PROPRIETORS OF THE SUBDIVISION SHOWN HEREON, THE UTILITY COMPANIES OR OTHER INTERESTED PARTIES AND MEETS THE MINIMUM REQUIREMENTS FOR MONUMENTATION AND SURVEYS OF THE ALBUQUERQUE SUBDIVISION ORDINANCE, AND FURTHER MEETS THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF."


WILL PLOTNER JR.
N.M.R.P.S. No. 14271

82812 DATE




P.O. BOX 44414 RIO RANCHO, N.M. 87174

Phone (505) 896-3050 Fax (505) 891-0244 Sheet 1 of 2



Plat of Lot 1, Lands of Sandra & Carl Davidson


Comprising of
Tracts 71, 52A1A2, and 52A1B
MRGCD Map Number 36
City of Albuquerque
Bernalillo County, New Mexico
August 2012



Solar Collection Note

PER SECTION 14-14-4-7 OF THE SUBDIVISION ORDINANCE:

NO PROPERTY WITHIN THE AREA OF THIS PLAT SHALL AT ANY TIME BE SUBJECT TO A DEED RESTRICTION, COVENANT, OR BUILDING AGREEMENT PROHIBITING SOLAR COLLECTORS FROM BEING INSTALLED ON BUILDINGS OR ERECTED ON THE LOTS OR PARCELS WITHIN THE AREA OF PROPOSED PLAT, THE FOREGOING REQUIREMENT SHALL BE A CONDITION TO APPROVAL OF THIS PLAT.



CARTESIAN SURVEYS INC.

P.O. BOX 44414 RIO RANCHO, N.M. 87174 Phone (505) 896-3050 Fax (505) 891-0244

Sheet 2 of 2