

BUILDING INFORMATION

BUILDING 1

ADDRESS : 2440 LOUISIANA BLVD.
LEGAL DESCRIPTION :
ZONE ATLAS : H-19
AREA : 14,067 SF
CONSTRUCTION TYPE : V-B
SPRINKLERED : YES
FIRE FLOW : GPM _____
BUILDING HEIGHT : '30'-0"
HYDRANTS REQUIRED : 1

BUILDING 2

ADDRESS : 2440 LOUISIANA BLVD.
LEGAL DESCRIPTION :
ZONE ATLAS : H-19
AREA : 74,000 SF
CONSTRUCTION TYPE : III-A
SPRINKLERED : YES
FIRE FLOW : GPM _____
BUILDING HEIGHT : '70'-0"
HYDRANTS REQUIRED : 2

BUILDING 3



ADDRESS : 2440 LOUISIANA BLVD.
LEGAL DESCRIPTION :
ZONE ATLAS : H-19
AREA : 5051 SF
CONSTRUCTION TYPE : V-B
SPRINKLERED : NO
FIRE FLOW : GPM _____
BUILDING HEIGHT : '22'-0"
HYDRANTS REQUIRED : 2

NOTES

1. ALL RADII ALONG FIRE LANE SHALL BE 28'.
2. MONUMENT SIGN IDENTIFY BUILDINGS WILL BE PROVIDED AT ADJACENT ROADWAYS.
3. ALL BUILDINGS SHALL HAVE A KNOX BOX FOR FIRE DEPARTMENT ACCESS.
4. FIRE HYDRANT CONNECTION SHALL BE WITHIN 100 FT OF A FIRE HYDRANT.
5. ALL AREAS PAVED INCLUDING FIRE ACCESS.
6. SLOPES WILL NOT EXCEED 10% IN GRADE FOR THE FIRE ACCESS ROAD

LEGEND

- PROPERTY LINE
- - - MARKED FIRE ACCESS



REVISIONS



DRAWN BY	
REVIEWED BY	
DATE	5.18.16
PROJECT NO	20160384

DRAWING NAME
FIRE ONE PLAN

SHEET NO

C-001

