

Notes

1. FIELD SURVEY PERFORMED IN NOVEMBER 2012.

2. ALL DISTANCES ARE GROUND DISTANCES: U.S. SURVEY FOOT.

 THE BASIS OF BEARINGS REFERENCES NEW MEXICO STATE PLANE COORDINATES (NAD 83-GRID).

Subdivision Data

GROSS ACREAGE
ZONE ATLAS PAGE NO
NUMBER OF EXISTING LOTS
NUMBER OF LOTS CREATED
MILES OF FULL WIDTH STREETS
MILES OF HALF WIDTH STREETS
RIGHT-OF-WAY DEDICATION TO THE CITY OF ALBUQUERQUE D.0384 ACRES
DATE OF SURVEY

Free Consent & Dedication

THE SUBDIVISION HEREON DESCRIBED IS WITH THE FREE CONSENT AND IN ACCORDANCE WITH THE DESIRES OF THE UNDERSIGNED OWNER(S) AND/OR PROPRIETOR(S) THEREOF DO HEREBY GRANT THE RIGHT TO CONSTRUCT, OPERATE, INSPECT, MAINTAIN FACILITIES THEREIN; AND ALL PUBLIC UTILITIES EASEMENTS SHOWN HEREON FOR THE COMMON AND JOINT USE OF GAS, ELECTRICAL POWER AND COMMUNICATION SERVICE FOR BURIED DISTRIBUTION LINES, CONDUITS AND PIPES FOR UNDERGROUND UTILITIES WHERE SHOWN OR INDICATED, AND INCLUDING THEIR RIGHT OF INGRESS AND EGRESS FOR CONSTRUCTION AND MAINTENANCE, AND THE RIGHT TO TRIM INTERFERING TREES AND SHRUBS. SAID OWNER(S) AND/OR PROPRIETOR(S) DO HEREBY CONSENT TO ALL OF THE FOREGOING AND DOES HEREBY CERTIFY THAT THIS SUBDIVISION IS THEIR FREE ACT AND DEED. SAID OWNER(S) AND/OR PROPRIETOR(S) WARRANT THAT THEY HOLD AMONG THEM COMPLETE AND INDEFEASIBLE TITLE IN FEE SIMPLE TO THE LAND SUBDIVIDED. SAID OWNER(S) AND/OR PROPRIETOR(S) DO HEREBY DEDICATE ADDITIONAL PUBLIC RIGHT OF WAY SHOWN HEREON TO THE CITY OF ALBUQUERQUE IN FEE SIMPLE WITH WARRANTY COVENANTS.

MARK TEKIN

DATE

Acknowledgment


STATE OF COUNTY OF

SS

THIS INSTRUMENT WAS ACKNOWLEDGED BEFORE ME ON ______

BY: MARK TEKIN

NOTARY PUBLIC



Indexing Information

Sections 20 & 29, Township 10 North, Range 4 East, N.M.P.M. Subdivision: Buena Ventura UPC #102005648654211801

Purpose of Plat

1. SUBDIVIDE AS SHOWN HEREON.

2. DEDICATE ADDITIONAL PUBLIC RIGHT OF WAY AS SHOWN HEREON.

3. GRANT EASEMENTS AS SHOWN HEREON.

Legal

LOTS LETTERED "E" AND "F" IN BLOCK NUMBERED SEVEN (7), BUENA VENTURA, AN ADDITION TO THE CITY OF ALBUQUERQUE, NEW MEXICO, AS THE SAME IS SHOWN AND DESIGNATED ON THE PLAT THEREOF, FILED IN THE OFFICE OF THE COUNTY CLERK OF BERNALILLO COUNTY, NEW MEXICO, ON SEPTEMBER 11, 1941, IN PLAT BOOK C1, PAGE 8, LESS AND EXCEPTING THEREFROM THE NORTH TWENTY FEET (N. 20') OF SAID LOT LETTERED "F" CONVEYED TO THE CITY OF ALBUQUERQUE, A MUNICIPAL CORPORATION, BY QUITCLAIM DEED RECORDED NOVEMBER 3, 1954, IN BOOK D 295, PAGE 435, AS DOC. NO. 38395, RECORDS OF BERNALILLO COUNTY, NEW MEXICO.

BEING MORE BEING DESCRIBED BY METES AND BOUNDS AS FOLLOWS:


BEGINNING AT THE NORTHWEST CORNER OF THE HEREIN DESCRIBED PARCEL, MARKED WITH A 1/2" REBAR; WHENCE A TIE TO ACS MONUMENT "14-K20", BEARS N 61'09'29" W, A DISTANCE OF 5358.35 FEET;

THENCE, FROM THE POINT OF BEGINNING, N 89'44'22" E, A DISTANCE OF 269.99 FEET TO THE NORTHEAST CORNER OF THE HEREIN DESCRIBED PARCEL, BEING A POINT ON THE WESTERLY RIGHT-OF-WAY OF GLORIETA STREET NE, MARKED WITH A BATHEY MARKER WITH CAP "LS 14271";

THENCE, COINCIDING WITH THE SAID WESTERLY RIGHT-OF-WAY, S 00°15'38" E, A DISTANCE OF 408.86 FEET TO THE SOUTHEAST CORNER OF THE HEREIN DESCRIBED PARCEL, BEING A POINT ON THE NORTHERLY RIGHT-OF-WAY OF CENTRAL AVENUE NE, MARKED WITH CHISELED X;

THENCE, COINCIDING WITH THE SAID NORTHERLY RIGHT-OF-WAY, N 82"15'08" W, A DISTANCE OF 272.65 FEET TO THE SOUTHWEST CORNER OF THE HEREIN DESCRIBED PARCEL, BEING A POINT ON THE EASTERLY RIGHT-OF-WAY OF ESPEJO STREET NE, MARKED WITH A CHISELED X;

THENCE, COINCIDING WITH THE SAID EASTERLY RIGHT-OF-WAY, N 0015'38" W, A DISTANCE OF 370.87 FEET TO THE POINT OF BEGINNING, CONTAINING 2.4164 ACRES (105,260 SQ. FT.), MORE OR LESS.



Plat for East Central Gateway Plaza

Being Comprised of

Lot E and a Portion of Lot F, Block 7,
Buena Ventura
City of Albuquerque
Bernalillo County, New Mexico
May 2014

Approved and Accepted by:

APPROVAL AND CONDITIONAL ACCEPTANCE AS SPECIFIED BY THE ALBUQUERQUE SUBDIVISION ORDINANCE, CHAPTER 14 ARTICLE 14 OF THE REVISED ORDINANCES OF ALBUQUERQUE, NEW MEXICO, 1994.

Project Number /0/0043
Application Number |4DRB-70099

Plat approvals:	
Formers Vigil	5-22-14
PNM Electric Services	, Date,
CII ET	5/23/14
New Nexico Gas Company	Date ,
- China	5/22/14
Qwest Corporation d/b/a CenturyLink QC	Date
which that	5/23/14
Copricast	Date
City approvals: P. Lovola	4-7-14
City Surveyor	Date
/12>23-3	05-23-14
Traffic Enginee	Date
allonlater	04/16/14
ABCWUA	Date
and S. lumont	4-16-14
Part Recreation Department	Date
aut a chur	4-14-14
AMAFGA Centra Chene	Date 4-16-14
City Engineer	Date
Lock Clory	5-5-14
DRB/Chairperson, Planning Department	Date

Surveyor's Certificate

"I, WILL PLOTNER JR., A DULY QUALIFIED REGISTERED PROFESSIONAL LAND SURVEYOR UNDER THE LAWS OF THE STATE OF NEW MEXICO, DO HEREBY CERTIFY THAT THIS PLAT AND DESCRIPTION WERE PREPARED BY ME OR UNDER MY SUPERVISION, SHOWS ALL EASEMENTS AS SHOWN ON THE PLAT OF RECORD OR MADE KNOWN TO ME BY THE OWNERS AND/OR PROPRIETORS OF THE SUBDIVISION SHOWN HEREON, THE UTILITY COMPANIES OR OTHER INTERESTED PARTIES AND MEETS THE MINIMUM REQUIREMENTS FOR MONUMENTATION AND SURVEYS OF THE ALBUQUERQUE SUBDIVISION ORDINANCE, AND FURTHER MEETS THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO AND IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF."

WILL PLOTNER JR.
N.M.R.P.S. No. 14271


DATE

CARTESIAN SURVEYS INC.

P.O. BOX 44414 RIO RANCHO, N.M. 87174 Phone (505) 896-3050 Fax (505) 891-0244



Sheet 1 of 2



Plat for East Central Gateway Plaza

Being Comprised of

Lot E and a Portion of Lot F, Block 7, Buena Ventura City of Albuquerque Bernalillo County, New Mexico May 2014

LINE TABLE					
LINE	LENGTH	BEARING			
L1	25.90'	N 07°44'52" E			
L2	15.71'	S 82°15'08" E			
L3	26.88'	N 0015'38" W			
L4	33.92'	S 00°15'38" E			

		CUR	VE TABLE		
CURVE	LENGTH	RADIUS	DELTA	CHORD	CHORD BEARING
C1	35.78'	25.00'	81.59,30,	32.80'	S 41'15'23" E
C2	42.76	25.00'	98'00'30"	37 74'	N 48'44'37" F

Easement Notes

- CROSS LOT DRAINAGE EASEMENT OUTSIDE OF BUILDING AREAS, TO BE MAINTAINED BY THE OWNERS OF EACH INDIVIDUAL TRACT.
- 2 5' CENTURYLINK EASEMENT GRANTED WITH THE FILING OF THIS PLAT

Solar Collection Note

PER SECTION 14-14-4-7 OF THE SUBDIVISION ORDINANCE:

NO PROPERTY WITHIN THE AREA OF REQUESTED FINAL ACTION SHALL AT ANY TIME BE SUBJECT TO A DEED RESTRICTION, COVENANT, OR BUILDING AGREEMENT PROHIBITING SOLAR COLLECTORS FROM BEING INSTALLED ON BUILDINGS OR ERECTED ON THE LOTS OR PARCELS WITHIN THE AREA OF PROPOSED PLAT, THE FOREGOING REQUIREMENT SHALL BE A CONDITION TO APPROVAL OF THIS PLAT.

Public Utility Easements:

Public utility easements shown on this plat are granted for the common and joint use

- A. Public Service Company of New Mexico ("PNM"), a New Mexico corporation, (PNM electric) for installation, maintenance and service of overhead and underground electrical lines, transformers, and other equipment and related facilities reasonably necessary to provide electrical services.
- B. New Mexico Gas Company for installation, maintenance, and service of natural gas lines, valves and other equipment and facilities reasonably necessary to provide natural gas services.
- C. Qwest Corp. d/b/a CenturyLink QC for the installation, maintenance, and service of such lines, cable, and other related equipment and facilities reasonably necessary to provide communication services.
- D. Cable TV for the installation, maintenance, and service of such lines, cable, and other related equipment and facilities reasonably necessary to provide cable services.

Included, is the right to build, rebuild, construct, reconstruct, locate, relocate, change, remove, replace, modify, renew, operate and maintain facilities for purposes described above, together with free access to, from, and over said easements, with the right and privilege of going upon, over and across adjoining lands of Grantor for the purposes set forth herein and with the right to utilize the right of way and easement to extend services to customers of Grantee, including sufficient working area space for electric transformers, with the right and privilege to trim and remove trees, shrubs or bushes which interfere with the purposes set forth herein. No building, sign, pool (choveground or subsurface), hot tub, concrete or wood pool decking, or other structure shall be erected or constructed on said easements, nor shall any well be drilled or operated thereon. Property owners shall be solely responsible for correcting any violations of National Electrical Safety Code by construction of pools, decking, or any structures adjacent to or near easements shown on this plat.

Easements for electric transformer/switchgears, as installed, shall extend ten (10) feet in front of transformer/switchgear doors and five (5) feet on each side.

1 inch = 40 ft.

In approving this plat, Public Service Company of New Mexico (PNM), New Mexico Gas Company (NMGC) and Qwest D/B/A Centurylink QC did not conduct a Title Search of the properties shown hereon. Consequently, PNM, NMGC and Qwest D/B/A Centurylink QC do not waive or release any easement or easement rights which may have been granted by prior plat, replat or other document and which are not shown on this plat.

DOC# 2014044860

06/05/2014 12:34 PM Page: 2 of 2 tyPLAT R:\$25 00 8: 2014C P: 0053 M Toplous Olivere, Benealitic Cour

Sheet 2 of 2