


- KEYED NOTES
- 8" CMU WALL WITH 2 COAT 5/8" STUCCO SYSTEM. COLOR TO MATCH BLDG. BASE
  - FINISH GRADE.
  - SLOPE STUCCO CAP.
  - 4-#4 BARS CONT. @ BOTTOM OF FOOTING 4" @ 16" O.C. ACROSS BOTTOM OF FOOTING.
  - 2-#5 BARS @ TOP KNOCK-OUT BLOCK BOND BEAM. CONTINUOUS. #5 BARS @ 32" O.C. VERTICAL. GROUT REINFORCED CELLS. DURAWALL @ 16" O.C. HORIZONTAL.
  - 1/2" EXPANSION JOINT MATERIAL
  - 4" CONCRETE SLAB 4000 PSI 3/4" AGGREGATE WITH 6x6 @ 10x10 W/M.
  - 6" CONCRETE APRON 4000 PSI 3/4" AGGREGATE WITH 6x6 @ 10x10 W/M W/ TURNDOWN EDGE.
  - 6" CONCRETE FILLED PIPE IN 18" DIA. X 2'-6" DEEP CONC. FOOTING. PAINT TO MATCH STUCCO FINISH.
  - ASPHALT PAVING
  - GROUT ALL CELLS SOLID BELOW GRADE, TYPICAL.
  - 2" VENT TO 16" ABOVE TOP OF ENCLOSURE WALL. PROVIDE BREATHABLE VENT CAP.
  - CLEAN OUT RE: DET 17(A)3 FOR INFO
  - CATCH BASIN ZURN Z-891 6" X 20" SANI-FLO CATCH BASIN FABRICATED 1/2" GAGE TYPE 304 STAINLESS STEEL BASIN WITH BOLTED FLANGED CONNECTION COMPLETE WITH FLANGE GASKET. PROVIDE SPECIAL DUTY, CLASS "E" Z-882-PGE DUCTILE IRON SLOTTED GRATE, AND SEDIMENT BASKET.



REV	DATE	BY	REVISION
1			
2			
3			
4			
5			

**MODULUS ARCHITECTS**  
 100 SUN AVE. N.W. SUITE 305  
 ALBUQUERQUE, NEW MEXICO 87109  
 PHONE (505) 338-1499 FAX (505) 338-1498



PROJECT TITLE KIDDIE ACADEMY SEC. OF LOUISIANA AND ALAMEDA NE ALBUQUERQUE	JOB NO. XXXXX	DRAWN BY S
PROJECT MANAGER STEPHEN DUNBAR, AIA	SHEET TITLE SITE DETAILS	

DATE 8/31/2016	sheet A1.3
SCALE NT.S	et.