
ADMINISTRA	TIVE AMENDMENT			
FILE #PROJECT #				
	,			
	·			
APPROVED I	BY DATE			



GENERAL NOTES:

- 1. ZONING, SU-1 FOR R-T MAXIMUM 35 DWELLING UNITS PROPOSED DEVELOPMENT.
- 2. APPROXIMATE ACREAGE 2.89 NUMBER OF LOTS - 1 D.U. PROPOSED DENSITY - 12.1 D.U. /ACRE
- 3. MINIMUM UNIT DIMENSIONS 28'x82.5' TYPICAL AREA - 2310 SQ. FT.
- 4. ALL STREETS AND UTILITES IMPROVEMENTS ARE TO BE PRIVATE.
- 5. NO INDIVIDUAL LOTS SHALL BE ALLOWED DIRECT ACCESS TO SAN CLEMENTE.
- 6. OFF-STREET PARKING SHALL BE PROVIDED ON EACH LOT, AS REQUIRED BY THE ZONING CODE.
- 7. NO IMPROVEMENT WILL BE CONSTRUCTED IN THE IRRIGATION EASEMENT. ONLY GRAVEL AND LANDSCAPING WILL BE PLACED IN THE EASEMENT. NO CHANGES WILL BE MADE TO THE CONFIGURATION OF THE DITCH, ITS BANKS OR ITS CHECKGATE. THERE SHALL BE A 10' SEPARATION BETWEEN THE RESIDENCES AND THE IRRIGATION
- 8. SIDEWALKS SHALL BE BUILT PER APPROVED SITE PLAN DATED APRIL 4, 2004.

9. STREET LIGHTS WILL BE INSTALLED ACCORDING TO THE DESIGN PROVCESS MANUAL

REQUIREMENTS FOR STREET LIGHT LOCATIONS, WITH ONE STREETLIGHT AT EACH INTERSECTION

10. SOLID WASTE NOTE: GARBAGE AND RECYCLING BINS WILL BE PLACED ON SAN CLEMENTE. THIS INFORMATION WILL BE INCLUDED IN HOMOWNER ASSOCIATION DOCUMENTS.

FIRE 1 CHECKLIST NOTES:

- FIRE HYDRANT SUPPLY LINE: THE FIRE HYDRANT SUPPLY LINE IS A 6" VATER LINE LOCATED ON THE SOUTH SIDE OF SAN CLEMENTE
- DEAD END: DEAD END STREETS RANGE IN LENGTH FROM 151.51 FEET TO 153.14 FEET A HAMMERHEAD TURNAROUND WAS APPROVED ON THE ORIGINAL PLAN (APRIL 2004) AND PLAT (JANUARY 2006), PROJECT NUMBER 1002123.
- ACCESS ROADS ARE ASPHALT CONCRETE WITH 4" COMPACTED SUB BASE AND 6" COMPACTED SUB GRADE AS APPROVED ON THE ORIGINAL PLAN
- ALL ROADS ARE LESS THAN 10 PERCENT IN GRADE.
- NO SECURITY GATES THAT EXTEND ACROSS FIRE APPARATUS ACCESS ROADS ARE TO BE INSTALLED ON THE SITE

PROJECT NUMBER: PR-2020-004225 - OLD FPC/DRB CASE #1002123

APPLICATION NUMBER: SI-2020-00717

IS AN INFRASTRUCTURE LIST REQUIRED? () YES (X) NO. IF YES, THEN A SET OF APPROVED DRC PLANS WITH A WORK ORDER IS REQUIRED FOR ANY CONSTRUCTION WITHIN PUBLIC RIGHT-OF-WAY OR FOR CONSTRUCTION OF PUBLIC IMPROVEMENTS.

ADMINISTRATIVE AMENDMENT SITE DEVELOPMENT PLAN FOR LOTS 1 thru 35 AND TRACTS A, B-1, C, D, E, F. G, H, DEL'S HIDE-A-WAY

APPROVALS

THIS PLAN IS CONSISTENT WITH THE ZONE MAP AMENDMENT APPROVAL BY THE ENVIRONMENT PLANNING COMMISSION (EPC) ON JANUARY 17, 2003 AND THAT THE FINDINGS AND CONDISTIONS IN THE OFTICIAL NOTIFICATIONS OF DECISION HAVE BEEN COMPLIED WITH.

RESIDENTIAL BUILDING DESIGN STANDARDS

THE FOLLOWING GUIDELINES ARE TO BE UTILIZED FOR TOWNHOUSES DESIGNED AND BUILT WITHIN THIS PROJECT.

- A. ARCHITECTURAL STYLE: CONTEMPORARY WITH MULTI-COLORED STUCCO ACCENTS
- B. SETBACK REQUIREMENTS:

FRONT YARD: PER SITE PLAN APPROVED 0N4/28/2004 DRIVEWAYS SHALL CONTINUE TO HAVE 20' SETBACK REAR YARD: 15' MIN. EXCEPT AS FURTHER DEFINED IN THE R-T

RESIDENTIAL ZONE FOR HOUSES WITH OFFSET REAR LOT LINES

SIDE YARD: NONE REQUIRED EXCEPT THERE SHALL BE 10' ON THE STREET SIDE OF CORNER UNITS 5,10,15,20,25,30 AND 35

C. BUILDING HEIGHT RESTRICTIONS: STRUCTURES SHALL NOT EXCEED 26' IN HEIGHT, AS DEFINED IN THE ZONING CODE AND WITH EXCEPTION PROVIDED IN PARAGRACH 14-16-3-3

D. BUILDING COLOR SCHEMES: THE FOLLOWING COLOR SCHEMES SHALL BE UTILIZED: "DRIVIT" STUCCO NUMBERS IN THE FOLLOWING CONFIGURATION: DARKER STUCCO COLOR - LIGHTER STUCCO COLOR 81582, CORAL GABLES - 110, ASH

63149, HATTERAS - 121, SANDALWOOD 135, SAHARA - 100, COLONIAL WHITE 81585, CHARLESTON - 30, SCAPSTONE 81584, SUFFOLK - 90, CANDELIGHT 63152, ASHEVILLE - 117, FAWN

ADDRESS PLATES AND METAL EYEBROW STRUCTURES SHALL BE PAINTED BRONZE PROPERTY LINE VALLS SHALL BE TAN COLORED, SMOOTH BLOCK CMU STYLE

E. LANDSCAPING INSTALL SHALL BE:

EACH LOT, FRONT YARD COMMON SOUTHWEST/DESERT PACKAGE

30 15 GALLON TREE 44 15 GALLON TREES, 35 IN FRONT YARDS, 9 IN COMMON AREAS 60 - 5 GALLON SHRUBS

7 - 2 GALLON SHRUBS 108 - 1 GALLON SHRUBS

NEW

2"-4" - ACCENT COBBLESTONE, AS PER LANDSCAPE PLAN

3/4" - GRAY CRUSHED STONE ON PLATIC, AS PER LANDSCAPE PLAN

- F. PEDESTRIAN ACCESS SHALL BE PROVIDED BY SIDEVALKS CONSTRUCTED AS SHOWN ON SITE PLAN
- G. PRIVACY WALLS: EACH LOT SHALL BE PROVIDED WITH CONCRETE BLOCK PRIVACY WALLS ON THE COMMON PROPERTY LINE. THE HEIGHT OF THE WALLS SHALL CONFORM TO THE ZONING CODE



NOT TO SCALE



DESIGN CRITERIA:

- A. ZONING DESIGN CRITERIA
- 1. LEGAL DESCRIPTION LOTS 1 thru 35 and TRACTS A,B-1,C,D,E,F,G,H & J DELS HIDE-A-WAY
- 2. ZONING CLASSIFICATION SU-1 FOR R-T USES
- 3. ACTUAL USE ATTACHED RESIDENTIAL TOWNHOUSE
- B. ARCHITECTURAL DESIGN CRITERIA
- 1. OCCUPANCY GROUP R-3
- 2. TYPE CONSTRUCTION V-N
- 3. FLOOR AREA GARAGE - DOWNSTAIRS HEATED

- UPSTAIRS HEATED

976.12 SQ. FT. 423, 91 SQ. FT. - TOTAL HEATED 1400.03 SQ. FT. - TOTAL AREA 1670.31 SQ. FT.

270.28 SQ. FT.

PARKING ANALYSIS:

NEW

NEW

REQUIRED PARKING SPACES: BASED ON R-T ZONING

1 SPACE PER BATH BUT NOT LESS THAN 1.5 SPACES PER DWELLING

70 PARKING SPACES PROVIDED

2 SPACES PER DWELLING 35 DWELLINGS 70 PARKING SPACES REQUIRED

PROVIDED PARKING SPACES: 2 SPACES PER DWELLING 35 DWELLINGS

PROJECT: DEL'S HIDEAWAY

DESCRIPTION: SITE PLAN SINGLE UNIT


SHEET # OF **03**

CLIENT: **TWILIGHT** HOMES
























PROJECT:



Landscaping General Notes:

- 1. Drip Irrigotion per City of Albuquerque Code.
 2. Maintenance of landscaping and Irrigation system to be the responsibility of the Property Owner.
 3. The owner shall existing and proposed utilities, and all site conditions prior to beginning construction.
 4. The finish grade of all planting areas shall be smooth, even and consistent, free of any humps, depressions or other grading irregularities.
 5. The owner shall not impede drainage in any way. The owner shall always maintain positive drainage away from the building.
 6. The owner shall not plant trees within 5 feet of gas lines.

Common Name	Botanical Name	Sizo	Mature height	Symbol
Purple Fineling Plum		Filten galan	25° tal = 25° spreod	
New Marico Office Print Tree	Formetiers Nagmedoons	Fire gallon .	15' tall x 15' spreod.	(O)
Overry Soge	Sohis Greggi	One galion	2' toll x 3' spread .	*
Priddy Pear Coctus	Opuntiu Speciee	Five galian	6-5 tol 1 6-5 spread	8
Russian Sage	Paravella Abblichola	One gallen	2' toll x 3' spread .	0
Red Tip Yucce	Heperalce Payellara	One galler -	2, pay x 2, abused	*
Yuece	Yacce Bets	Fire gallon .	15' tal x 5' spreed .	0
Rosemery 'Asp'	Romatica Officientia 'Ary'	One gellen .	3' toll x 3' apreed .	0
Bird of Peredien	Conscipting Giffeet	Five galan	10" toll x 10" spreed	0
Hardy Purple Cospicant	Delospermo Cooperi	One gallen	6" tall x 1'-6" spread	0
lis	iris (rédome-type)	On polon	Z' tell x Z' sprood .	0
Holly Hooks	Alone Rosse	Two gallon .	5" tall x 1"-6" spread	*
Court Willow	Orbipale Linearie	The galon	25 tal x 25 spread	60
Cobio Stones				
3/4° Grovel .				
Outlar Fires				100

AS SHOWN

RAR/ LCL RAR/ PJM

- General Notes:

 1. The intent of these drawings is to display labor and materials necessary for the completion of all work shown.

 2. In the event of an inconsistancy, specifications shall take precedence over drawings.

 3. All work and materials shall be in accordance with the 1997 UBC; State and /or local codes; laws and ordinance 4. All dimensions are to face of wall, except windows and doors are dimensioned to center line.

 5. Verify Dimensions in the field, they will take precedence over drawings.

ARCHETECH DRAFTING SERVICES

12928 EASTRIDGE DR. N.E. ALBUQUERQUE, N.M. 87112 (505)480-7423 (505)332-1748


CONSULTANTS

DEL'S HIDE-A-WAY PARK - REVISE

4326 4th STREET ALBUQUERQUE, NEW MEXICO LANDSCAPING PLAN

QuikDraw 4/04

ENGINEERING, L.L.C.



SOUTHWEST