

ADMINISTRATIVE AMENDMENT

FILE #: _____ PROJECT #: _____

APPROVED BY


DATE

Kids Empire, 10000 Coors Bypass NW, Suite EU01C, Albuquerque NM 87114


Proposed Sign - Location & Details

MOUNTING OPTIONS


Thru-Bolt Mounting




Hanger Bolts



Reverse Toggle Bolt Mounting



Masonry Lag Bolt Mounting



NOTE: All bolts shall be embedded at least 5" as per H111.2 2021 IBC

78 ft W

31 ft H

Proposed Sign

NITE-LITE SIGNS

Project Name: Kids Empire
Description: Front-Lit Channel Letters | Stacked
Address: 10000 Coors Bypass NW, Suite EU01C
City: Albuquerque
State/Zip: NM 87114
Date: 02/19/24
PID No.:
Order Taken by:

Approval: Signature: Date:

I have carefully reviewed and hereby accept the drawing(s) as shown. I realize that any changes made to these drawings prior to or after production may alter the contract price. All changes must be in writing and approved by both parties prior to production.

Dimensions Note: Front-Lit Channel Letters | Stacked

Pending survey

291.5"

94.5"

69.5"

208.5"

38"

Side Detail

UL Notes

- ALL ILLUMINATED SIGNS SHALL BE FABRICATED AND INSTALLED WITH ALL APPLICABLE CODE REQUIREMENTS AND SHALL BARE AN UNDERWRITERS LABORATORY (UL) LABEL.
- UL LABELS MUST BE POSITIONED ON THE TOP SIDE OF SIGN OR AS NECESSARY TO KEEP FROM LINE OF SIGHT.
- CUT OFF SWITCH MUST BE RECESSED IN THE TOP OF THE SIGN TO AVOID VISIBILITY.
- SCREWS MUST BE AT TOP ONLY, COUNTERSUNK & PAINTED TO MATCH SIGN.
- LIGHT LEAKS ARE PROHIBITED.
- NO EXPOSED FASTENINGS, SWITCHES, WIRING OR MANUFACTURER'S/UNDERWRITER'S LABELS, RACEWAYS, CROSSOVER OR CONDUITS - ALL MUST BE OUT OF VIEW FROM THE PUBLIC.

UL LABELS ON TOP

Acrylic Face

White LED's

Trimcap

Return

Input Type: Street Typical

Transformer

12V Output

Disconnect Switch

6-2 Wiring Behind Wall

Screw - 1/4" x 2" - Spacing Anchor - 1/4" x 1 1/4" Penetration 1.5/4" deep

Channel Letter Specs

Face: Translucent Acrylic
Return: 200° Aluminum
Back: 60° Aluminum

Illumination

Type: LED

Transformer: Self Contained
Input: 120-220 VAC / 0.26-0.63 Amp
Output: 2.1 - 3.3 VDC - 2 x 5 Amp Circuit

Mounting

Flat Connection, Flat Conduit
6 ft or less of 1/4" x 2" Screws and Expansion Anchors - 1/8" x 1 1/4"

Letter Weight

Maximum 1 LB. Per Letter

UL LISTED

Screw - 1/4" x 2" - Expansion Anchor - 1/4" x 1 1/4" Penetration 1.5/4" deep

Countersink screws painted to match

Faces

- 3M #3630-106 Brilliant Green
- 3M #3630-108 Pink
- 3M #3630-236 Turquoise
- 3M #3630-125 Golden Yellow

Digital Print (Icon)

Trimcap/Returns

Block

This is an original protected drawing created by Nite-Lite Signs (Title 17 U.S. Code). It is submitted for your personal use in conjunction with a project being planned for you by Nite-Lite Signs and shall not be reproduced or disclosed for any purpose without written permission. Electric signs produced at Nite Lite Signs conform to UL 48 standards and display the Underwriters Laboratories(UL) label.

Page 1

Proposed Sign

Quantity 1: LED illuminated channel letters and logo box;

- Front Lit, stacked.
- Flush mounted.

Sign Size: 24 ft 3.5 in W x 7 ft 10.5 in H

Sign sq/ft: 189.98 sq/ft

Leased Space Facade - West

78 ft W x 31 ft H = 2,418 sq/ft

Sign is: 8% of the leased space facade.

There are currently no signs on the leased space facade.

Per 5-12(F)(2) of the IDO, On-premise Signs in Mixed-use...."Wall Signs shall not exceed the following percentages of the facade area... Location is zoned MX-M "Signs shall not exceed 15% of the facade area inclusive of door and window openings. Proposed signs shall comply with all of the provisions of Section 5-12(F)(2).

All signs are on premise - no off premise signs are proposed.

Kids Empire, 10000 Coors Bypass NW, Suite EU01C, Albuquerque NM 87114

Map with Sign Location



Proposed Sign

Quantity 1: LED illuminated channel letters and logo box;

- Front Lit, stacked.
- Flush mounted.

Sign Size: 24 ft 3.5 in W x 7 ft 10.5 in H
Sign sq/ft: 189.98 sq/ft

Leased Space Facade - West
78 ft W x 31 ft H = 2,418 sq/ft
Sign is: 8% of the leased space facade.

There are currently no signs on the leased space facade.

Per 5-12(F)(2) of the IDO, On-premise Signs in Mixed-use...: "Wall Signs shall not exceed the following percentages of the facade area...: Location is zoned MX-M "Signs shall not exceed 15% of the facade area inclusive of door and window openings. Proposed signs shall comply with all of the provisions of Section 5-12(F)(2).

All signs are on premise - no off premise signs are proposed.

