	1	2	
		GENERAL CIVIL NOTES	
		LAWS, CODES, RULES AND REGULATIONS WHICH APPLY TO THE	A. GF AC B. PF
		B. ALL WORK DETAILED ON THESE PLANS TO BE PERFORMED UNDER CONTRACT SHALL, EXCEPT AS OTHERWISE STATED ON OR PROVIDED FOR HEREON, BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT EDITION OF THE CITY OF ALBUQUERQUE STANDARD SPECIFICATIONS FOR PUBLIC WORKS (COA SPEC.)	OF BL M/ AN SH
	D	C. NO WORK SHALL BE PERFORMED WITHOUT THE APPROPRIATE PERMITS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR OBTAINING	C. IF SH D. TH AL PL CC AC
		D. COORDINATE WORK WITH SITE PLAN, UTILITY PLAN, DEMOLITION PLAN, AND LANDSCAPE PLAN.	ES ML GF
		E. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING OBSTRUCTIONS, AND CONDITION OF ALL EXISTING INFRASTRUCTURE PRIOR TO CONSTRUCTION. REPORT ALL DISCREPANCIES AND VERIFY THE ENGINEER'S INTENT BEFORE PROCEEDING.	CC WI E. ME BE
		F. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR SITE SAFETY. G. THE CONTRACTOR SHALL MAINTAIN RECORD DRAWINGS ON SITE AT	F. AL PC EX
		ALL TIMES. H. THE CONTRACTOR SHALL OBTAIN ALL REQUIRED INSPECTIONS OF THE WORK. THE CONTRACTOR SHALL REGULARLY UPDATE OWNER AND	RC BL G. WH
		ARCHITECT REGARDING THE STATUS OF THE INSPECTIONS. I. CONSTRUCTION ACTIVITY SHALL BE LIMITED TO THE PROPERTY AND/OR PROJECT LIMITS. ANY DAMAGE TO ADJACENT STRUCTURES RESULTING FROM THE CONSTRUCTION PROCESS SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE. CONTRACTOR SHALL BE RESPONSIBLE FOR DOCUMENTING EXISTING CONDITIONS PRIOR TO CONSTRUCTION.	OF H. PA NC MA LC ST
	С	J. CONSTRUCTION EQUIPMENT SHALL NOT OBSTRUCT DRIVEWAYS. EQUIPMENT SHALL ONLY OBSTRUCT DESIGNATED TRAFFIC LANES IF APPROPRIATE BARRICADING PERMITS HAVE BEEN OBTAINED. THE CONTRACTOR SHALL NOT STORE ANY EQUIPMENT OR MATERIAL IN THE RIGHT-OF-WAY.	I. AL AN NC J. SII
		EDITION OF THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES" (MUTCD) AND LOCAL REQUIREMENTS. THE CONTRACTOR SHALL OBTAIN BARRICADING PERMITS FROM THE APPROPRIATE AUTHORITIES PRIOR TO ANY CONSTRUCTION WORK ON OR ADJACENT TO EXISTING STREETS.	PF K. ST (T ET SE L. PC FA
		L. THE CONTRACTOR SHALL MAINTAIN ALL BARRICADING AND CONSTRUCTION SIGNING AT ALL TIMES. THE CONTRACTOR SHALL VERIFY THE PROPER LOCATION OF ALL BARRICADING AT THE END AND BEGINNING OF EACH DAY.	PE RE OV IDI
		MAY NOT EXIST WHERE SHOWN OR NOT SHOWN. CONTRACTOR SHALL CONTACT NM-811 FOR UTILITY LINE SPOTS FIVE WORKING DAYS PRIOR TO CONDUCTING SITE FIELD WORK. CONTRACTOR SHALL FIELD VERIFY AND LOCATE ALL UTILITIES PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION. CONTRACTOR IS FULLY RESPONSIBLE FOR ANY AND ALL DAMAGE CAUSED BY ITS FAILURE TO LOCATE, IDENTIFY AND PRESERVE ANY AND ALL EXISTING UTILITIES, PIPELINES, AND UNDERGROUND UTILITY LINES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF NECESSARY DRY UTILITY ADJUSTMENTS.	PF M. FC CE AL SU •
	В	WHICH WILL BE PROVIDED BY THE OWNER OR ARCHITECT. ALL OTHER WORK SHALL, UNLESS OTHERWISE NOTED IN THE PLANS, BE CONSTRUCTED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS (FIRST PRIORITY), AND/OR NMDOT STANDARD SPECIFICATIONS FOR	• P. GF EN LA IN EL
		<ul> <li>P. ALL TRASH, DEBRIS, &amp; SURFACE VEGETATION SHALL BE CLEARED AND LEGALLY DISPOSED OF OFFSITE.</li> <li>Q. VIBRATORY COMPACTION SHALL NOT BE USED OVER IN-PLACE</li> </ul>	V. UF AF WI NC CE
		UTILITIES. R. SOIL TESTING AND INSPECTION SERVICES DURING SITE OPERATIONS ARE REQUIRED. CONTRACTOR SHALL ALLOW TESTING LABS TO INSPECT AND APPROVE COMPACTED SUBGRADES, BACKFILL, AND FILL LAYERS BEFORE FURTHER CONSTRUCTION WORK IS DONE. SHOULD COMPACTION TESTS INDICATE INADEQUATE DENSITY, CONTRACTOR SHALL PROVIDE ADDITIONAL COMPACTION AND TESTING AT THE CONTRACTOR'S SOLE EXPENSE.	W. SI CC SI
35 PM		S. CONTRACTOR SHALL PROVIDE CONSTRUCTION STAKING. CONTRACTOR SHALL LOCATE AND PRESERVE ALL BOUNDARY CORNERS AND REPLACE ANY LOST OR DISTURBED CORNERS AT CONTRACTOR'S SOLE EXPENSE. PROPERTY CORNERS SHALL ONLY BE RESET BY A REGISTERED LAND SURVEYOR. ADJUST ANY RIMS OF EXISTING UTILITY FEATURES AS NECESSARY TO MATCH NEW GRADES. UTILITIES IN PAVED AREAS SHALL BE HS-25 TRAFFIC RATED.	
Bobrick 1/22/2020 4:		T. CONTRACTOR SHALL COMPLY WITH LOCAL REGULATIONS FOR RESEEDING OF DISTURBED AREAS.	
–101.dwg Bryan			
'B SUBMITTAL\2334 CG	A		
2399\2334\DWG\DRL			
€1\PROJECTS\2300-			
420D803∖shart			
S1//	1	2	

3	4
GRADING NOTES	STORM DRAIN NOTES
GRADING SHALL BE PERFORMED AT THE ELEVATIONS AND IN ACCORDANCE WITH THE DETAILS SHOWN IN THIS PLANSET. PROPOSED SPOT AND CONTOUR ELEVATIONS SHOWN REPRESENT TOP OF FINISH MATERIAL (I.E. TOP OF CONCRETE, TOP OF CONCRETE BUILDING PAD, TOP OF PAVEMENT MATERIAL, TOP OF LANDSCAPING MATERIAL, ETC.). CONTRACTOR SHALL GRADE, COMPACT SUBGRADE AND DETERMINE EARTHWORK ESTIMATES BASED ON ELEVATIONS SHOWN MINUS FINISH MATERIAL THICKNESSES.	A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COMPLETE INSTALLATION OF ALL WORK RELATED TO PROPOSED STORM DRAINS SHOWN ON THIS PLAN INCLUDING: TRENCHING, BACKFILL, SUPPORTS, INLET AND MANHOLE COLLARS, MANHOLES, WATER QUALITY FEATURES, EROSION CONTROL FEATURES, TESTING, CLEANING, AND STERILIZING. ANY WORK NOT ACCEPTED BY THE ENGINEER DUE TO IMPROPER WORKMANSHIP OR LACK OF PROPER COORDINATION SHALL BE REMOVED AND CORRECTLY INSTALLED AT THE CONTRACTOR'S EXPENSE, AS DIRECTED.
IF FIELD GRADE ADJUSTMENTS ARE REQUIRED, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT.	B. MINIMUM COVER FOR STORM DRAIN PIPES SHALL BE 12", UNLESS OTHERWISE NOTED.
THE ENVIRONMENTAL PROTECTION AGENCY (EPA) AND THE CITY OF ALBUQUERQUE REQUIRE A STORM WATER POLLUTION PREVENTION PLAN (SWPPP), AN NDPES PERMIT, AND AN EROSION AND SEDIMENT CONTROL (ESC) PERMIT FOR PROJECTS WHERE CONSTRUCTION ACTIVITIES MEET THE EPA THRESHOLD. (SWPPP, NPDES PERMIT, AND ESC PLAN BY OTHERS.) A CURRENT CITY-APPROVED ESC PERMIT MUST BE SUBMITTED AND APPROVED PRIOR TO RECEIVING A ROUGH GRADING, GRADING, PAVING, BUILDING, OR WORK ORDER PERMIT. CONTRACTOR SHALL COORDINATE WITH OWNER TO DETERMINE WHO WILL PREPARE SWPPP AND INSPECT REQUIRED ELEMENTS. MEASURES REQUIRED FOR EROSION AND SEDIMENT CONTROL SHALL BE INCIDENTAL TO THE PROJECT COST. ALL NEW PAVEMENT SURFACES SHALL BE CONSTRUCTED WITH POSITIVE SLOPE AWAY FROM BUILDINGS AND POSITIVE SLOPE TOWARD EXISTING AND/OR PROPOSED DRAINAGE PATHS. PAVING AND ROADWAY GRADES SHALL BE ±0.1' FROM PLAN ELEVATION. BUILDING PAD ELEVATION SHALL BE ±0.05' FROM PLAN ELEVATION. WHERE GRADES BETWEEN NEW AND EXISTING ARE SHOWN AS 'MATCH' OR '±', TRANSITIONS SHALL BE SMOOTH. PAVEMENT GRADES IN MARKED HANDICAPPED PARKING AREAS SHALL NOT EXCEED 2.0% IN MARY DIRECTION. FOR ALL ACCESSIBLE ROUTES, MAXIMUM ALLOWABLE CROSS SLOPE IS 2.0% AND MAXIMUM LONGITUDINAL SLOPE WITHOUT RAMP IS 5.0%. FOLLOW ALL ADA ACCESSIBILITY GUIDELINES OR CITY CODES, WHICHEVER IS MORE STRINGENT. ALL EROSION PROTECTION TO BE INSTALLED AS 4'' AVG. DIA. ANGULAR FACED ROCK (F.F. ROCK) PLACED OVER GEOTEX 501 NON-WOVEN GEOTEXTILE (0.E.). SIDESLOPES STEEPER THAN 3:1 MUST HAVE PERMANENT EROSION PROTECTION INSTALLED, TYPICAL. STORMWATER QUALITY CONTROL MEASURES SHOWN ON THIS PLAN (TOP OF POND, BOTTOM OF POND, SIZE OF ORIFICE, AREA OF POND, ETC.) TO BE STRICTLY ADHERED TO FOR CERTIFICATION PURPOSES. SEE DETAIL SHEET FOR ADDITIONAL INFORMATION. POST-CONSTRUCTION MAINTENANCE FOR PRIVATE STORMWATER FACILITIES WILL BE THE RESPONSIBILITY OF THE FACILITIES OWNER. PERIODIC INSPECTION AND CERTIFICATIONS OF THE FACILITIES OWNER. PERIODIC INSPECT SITE YEARLY AND AFTER FACH RAINFALL TO IDENTIFY NEW AREAS OF EROSION AND INSTAL	<ul> <li>C. STORM DRAINS SHALL BE INSTALLED AFTER COMPLETION OF THE SITE ROUGH GRADING.</li> <li>D. STORM DRAINS SHALL BE INSTALLED PRIOR TO SURFACE IMPROVEMENTS SUCH AS PAVEMENT, SIDEWALKS, AND LANDSCAPING.</li> <li>E. CONTRACTOR SHALL BE RESPONSIBLE FOR CONNECTIONS TO ROOF DOWNSPOUTS AND ALL NECESSARY FITTINGS. FITTING COSTS SHALL BE INCIDENTAL.</li> <li>F. TRENCHING, BORING, AND JACKING SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECT. 700. ALL BACKFILL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY PER ASTM D-1557.</li> <li>G. ALL INLET AND AREA DRAIN RINGS &amp; GRATES, MANHOLE RINGS &amp; COVERS, AND OTHER SURFACE ITEMS FOR THE STORM DRAINS SHALL BE ADJUSTED TO FINISHED GRADE UNLESS OTHERWISE NOTED ON THE PLANS.</li> <li>H. ALL STORM DRAIN CROSSINGS OF WATER AND SEWER LINES SHALL HAVE 18" MIN CLEARANCE. IF 18" CLEARANCE IS NOT POSSIBLE, CONTACT THE ENGINEER IMMEDIATELY.</li> <li>I. RCP PIPES, PP PIPES, CONCRETE INLETS, MANHOLES, AND CLEANOUTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECT. 900.</li> <li>J. HDPE PIPE SHALL BE ADS N-12 (WATERTIGHT) OR ENGINEER MANUFACTURER'S RECOMMENDATIONS.</li> <li>K. PVC PIPES SHALL BE ADS N-12 (WATERTIGHT) OR ENGINEER MANUFACTURER'S RECOMMENDATIONS.</li> <li>K. PVC PIPES SHALL BE PVC SDR-35, INSTALLED PER MANUFACTURER'S RECOMMENDATIONS.</li> <li>J. STORM DRAINS SHALL BE INSTALLED AT INVERTS AND SLOPES SPECIFIED ON THE PLANS. THE PIPE SHALL DRAIN AT A CONSTANT SLOPE BIT MEEN FITTINGS AND MANHOLES. THE PIPE SHALL DRAIN TOWARD THE OUTLET AT ALL LOCATIONS.</li> </ul>
CERTIFICATE OF OCCUPANCY) CONTRACTOR SHALL PROVIDE AN AUTOCAD FORMAT AS-BUILT SURVEY PREPARED BY A LICENSED SURVEYOR WHICH INCLUDES:	PAVING NOTES
<ul> <li>AS-BUILT SPOT ELEVATIONS AT EACH DESIGN SPOT ELEVATION SHOWN ON THE APPROVED PLAN;</li> <li>TOP AND BOTTOM ELEVATIONS AS REQUIRED TO DEFINE THE PERIMETER OF PONDS (TO BE USED BY ENGINEER TO CALCULATE AS-BUILT VOLUME PROVIDED);</li> <li>POND OVERFLOW ELEVATIONS</li> <li>ALL CONSTRUCTION, INCLUDING DRAIN INLETS, PIPES AND PONDS SHOWN ON THIS PLAN MUST BE CONSTRUCTED IN SUBSTANTIAL COMPLIANCE IN ORDER TO RECEIVE ENGINEER'S CERTIFICATION.</li> <li>GRADING OF FIRST FLUSH BASINS WILL BE INSPECTED AS PART OF ENGINEER'S CERTIFICATION FOR CERTIFICATE OF OCCUPANCY. DURING LANDSCAPING, FIRST FLUSH BASINS WILL BE SMOOTHLY INTEGRATED INTO LANDSCAPING WHILE MAINTAINING REQUIRED TOP AND BOTTOM ELEVATION, VOLUME AND INLET / OVERFLOW ELEVATIONS.</li> <li>UPON WRITTEN REQUEST COORDINATED THROUGH THE PROJECT ARCHITECT, THE ELECTRONIC FILE OF THE GRADING AND DRAINAGE WILL BE PROVIDED TO THE CONTRACTOR FOR VERTICAL CONTROL. DO NOT USE THIS PLAN FOR PROJECT STAKING AS THERE IS NO CERTAINTY THAT IT IS USING THE MOST CURRENT SITE BASE.</li> <li>SITE CONSTRUCTION HORIZONTAL LAYOUT / STAKING SHALL BE COORDINATED WITH THE ARCHITECT USING THE ARCHITECT PROVIDED SITE PLAN.</li> </ul>	<ul> <li>A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COMPLETE INSTALLATION OF ALL WORK RELATED TO PROPOSED PAVING SHOWN ON THE PAVING PLANS INCLUDING: ASPHALT AND OR CONCRETE PAVING, CURBS, GUTTERS, SIDEWALKS, RAMPS, PAVEMENT MARKINGS AND SIGNAGE. ANY WORK NOT ACCEPTED BY THE ARCHITECT OR ENGINEER DUE TO IMPROPER WORKMANSHIP OR LACK OF PROPER COORDINATION SHALL BE REMOVED AND CORRECTLY INSTALLED AT THE CONTRACTOR'S EXPENSE, AS DIRECTED.</li> <li>B. ALL PAVING, INCLUDING ASPHALT PAVEMENT, CONCRETE PAVEMENT, CURBS, GUTTERS, SIDEWALKS, AND RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECTION 300.</li> <li>C. ALL PAVEMENT MARKINGS AND SIGNAGE SHALL BE INSTALLED IN ACCORDANCE WITH COA SPEC. SECTION 400.</li> <li>D. ALL PAVEMENT INSTALLATION WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECTION 400.</li> <li>D. ALL PAVEMENT INSTALLATION WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECTION 400.</li> <li>D. ALL PAVEMENT INSTALLATION WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECTION 400.</li> <li>D. ALL PAVEMENT INSTALLATION WORK SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CURRENT EDITION OF THE GITY OF ALBUQUERQUE STANDARD SPECIFICATIONS FOR PUBLIC WORKS (COA SPEC.)</li> <li>E. ADJUST ANY RIMS OR COVERS OF EXISTING UTILITY FEATURES AS NECESSARY TO MATCH NEW GRADES. RIMS AND COVERS IN PAVED AREAS SHALL BE HS-25 TRAFFIC RATED.</li> </ul>

3

## UTILITY NOTES

5

- A. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE COMPLETE INSTALLATION OF ALL WORK RELATED TO PROPOSED UTILITIES SHOWN ON THIS PLAN INCLUDING: TRENCHING, BACKFILL, SUPPORTS, CLEANOUT PADS, SERVICE STOPS AND BOXES, SERVICE LINES, TESTING, CLEANING, AND STERILIZING. ANY WORK NOT ACCEPTED BY THE ARCHITECT OR ENGINEER DUE TO IMPROPER WORKMANSHIP OR LACK OF PROPER COORDINATION SHALL BE REMOVED AND CORRECTLY INSTALLED AT THE CONTRACTOR'S EXPENSE, AS DIRECTED.
- B. MINIMUM COVER SHALL BE 36" FOR WATERLINES AND 48" FOR SANITARY SEWER, EXCEPT AT BUILDING CONNECTIONS.
- C. UTILITY LINES SHALL BE INSTALLED AFTER COMPLETION OF THE SITE ROUGH GRADING.
- D. UTILITY LINES SHALL BE INSTALLED PRIOR TO SURFACE IMPROVEMENTS SUCH AS PAVEMENT, SIDEWALKS, AND LANDSCAPING.
- E. CONTRACTOR SHALL BE RESPONSIBLE FOR CONNECTIONS TO BUILDING PLUMBING AND ALL NECESSARY FITTINGS. FITTING COSTS SHALL BE INCIDENTAL. REFER TO THE MECHANICAL AND/OR PLUMBING PLANS FOR SERVICE CONNECTIONS
- F. DRY UTILITY LOCATIONS AND DESIGN ARE NOT A PART OF THIS PLAN. CONTRACTOR SHALL COORDINATE WITH THE LOCAL DRY UTILITY COMPANIES TO DETERMINE THE SIZE, DEPTH, LOCATION, FITTINGS AND REQUIRED APPURTENANCES FOR THE DRY UTILITY SERVICE LINES ON THE SITE. REFER TO MECHANICAL AND ELECTRICAL PLANS FOR SERVICE CONNECTIONS.
- G. TRENCHING, BORING, AND JACKING SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECT. 700. ALL BACKFILL SHALL BE COMPACTED TO A MINIMUM 95% DENSITY PER ASTM D-1557.
- H. ALL WATER VALVE BOXES, MANHOLE RINGS & COVERS, AND OTHER SURFACE ITEMS FOR THE UTILITIES SHALL BE ADJUSTED TO FINISHED GRADE.
- I. ALL CROSSINGS OF WATER AND SEWER LINES SHALL HAVE 12" MIN CLEARANCE. IF 12" CLEARANCE IS NOT POSSIBLE, BOTH PIPES SHALL BE ENCASED IN CONCRETE OR AS DIRECTED BY THE ENGINEER.
- J. VALVES, METERS, SERVICE LINES, METER AND VALVE BOXES, TAPPING SLEEVES, HYDRANTS, AND OTHER WATER APPURTENANCES SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECT. 800.
- K. WATERLINES LESS THAN 4" DIAMETER SHALL BE COPPER TYPE K MEETING ASTM B 88 REQUIREMENTS. WATERLINES 4" IN DIAMETER OR LARGER SHALL BE PVC PIPE MEETING AWWA C900 DR-18 REQUIREMENTS.
- L. ALL FITTINGS AND COUPLINGS FOR WATERLINES LESS THAN 4" IN DIAMETER ARE TO BE COPPER, SOLDER JOINT FITTINGS IN ACCORDANCE WITH ASME 16.18 OR ASME B16.22.
- M. ALL FITTINGS AND COUPLINGS FOR WATERLINES 4" IN DIAMETER OR LARGER ARE TO BE MEGA LUG MECHANICAL JOINTS OR ENGINEER APPROVED EQUIVALENT.
- N. JOINTS SHALL BE RESTRAINED BY MEGA LUG HARNESSES, OR ENGINEER APPROVED EQUIVALENT. JOINT RESTRAINTS SHALL BE INSTALLED AT DISTANCES FROM THE FITTINGS AS SHOWN ON THE JOINT RESTRAINT TABLE IN THESE PLANS.
- O. BACKFLOW PREVENTERS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- P. FIRE LINES SHALL USE PIPE MATERIALS LISTED AND APPROVED FOR FIRE SERVICE BY UNDERWRITERS LABORATORIES.
- Q. FIRE DEPARTMENT CONNECTIONS SHALL MEET UL 405, NFPA 1963, LOCAL FIRE DEPARTMENT REQUIREMENTS, AND IFC 2015.
- R. ADJUST WATER AND FIRE LINES TO AVOID FOOTINGS, SEWER LINES, AND OTHER CONDUITS. INSTALL FITTINGS AS NEEDED.
- S. SEWER MANHOLES, CLEANOUTS, SEWER SERVICE TAPS, AND OTHER SEWER APPURTENANCES SHALL BE CONSTRUCTED IN ACCORDANCE WITH COA SPEC. SECT. 900 / APWA SPEC. SECT. 900 / LOCAL UTILITY COMPANY SPECIFICATIONS
- T. SEWER SERVICE LINES SHALL BE INSTALLED AT A 1% MINIMUM SLOPE, UNLESS OTHERWISE SPECIFIED ON THE PLANS. THE PIPE SHALL DRAIN AT A CONSTANT SLOPE BETWEEN FITTINGS. THE PIPE SHALL DRAIN TOWARD THE SEWER MAIN AT ALL LOCATIONS.
- U. ALL SANITARY SEWER LINE MATERIALS SHALL BE PVC SDR-35 PIPE OR PVC SCH 40 PIPE.

## **PROJECT DATA**

<u>PROPERTY</u>: THE SITE IS A PREVIOUSLY DEVELOPED PROPERTY LOCATED WITHIN C.O.A. VICINITY MAP H-13. THE SITE IS BOUND TO THE EAST AND SOUTH BY DEVELOPED COMMERCIAL PROPERTY, TO THE NORTH BY MENAUL BLVD. NW AND TO THE WEST BY 12TH STREET NW.

PROPOSED IMPROVEMENTS: THE PROPOSED IMPROVEMENTS INCLUDE MULTIPLE COMMERCIAL BUILDINGS WITH ASSOCIATED ASPHALT PAVED ACCESS, PARKING, AND LANDSCAPING.

LEGAL: A PORTION OF TRACT 84E, MRGCD MAP 35 & ADJ. VAC PORTION OF 9TH STREET.

ADDRESS: 2400 12TH STREET NW, ALBUQUERQUE, NM 87104.

4


BENCHMARK: ELEVATIONS ARE BASED ON CITY OF ALBUQUERUQUE STATION No. "7-H13", HAVING AN ELEVATION OF 4964.364, NAVD 1988

<u>OFF-SITE</u>: THIS PROPERTY HOUSES A STORM LIFT STATION THAT HAS BEEN DESIGNED TO SERVE THIS PROPERTY AS WELL AS THE PLAZA AND RETAIL PROPERTIES TO THE SOUTH.

FLOOD HAZARD: PER BERNALILLO COUNTY FIRM MAP #35001C0331H, THE SITE IS LOCATED WITHIN FLOODZONE 'X' SHADED DESIGNATED AS AREAS WITH REDUCED FLOOD RISK DUE TO LEVEE.

DRAINAGE PLAN CONCEPT: ON-SITE RUNOFF WILL BE ROUTED TO SURFACE STORMWATER QUALITY / DETENTION PONDS AND A SUB-SURFACE DETENTION SYSTEM. A PRIVATE STORM DRAIN SYSTEM WILL SLOWLY DISCHARGE TO AN EXISTING STORM LIFT STATION PRESET TO PUMP TO THE PUBLIC STORM DRAIN SYSTEM AT THE PREVIOUSLY APPROVED RATE OF 2.0 CFS WHICH INCLUDES THIS PROJECT AS WELL AS THE PLAZA AND RETAIL PROPERTIES TO THE SOUTH - SAME OWNER). SEE SHEET CG-501 FOR ADDITIONAL INFORMATION.

5



CIVIL

GENERAL NOTES

**C-100**