

## *Wintergreen Luxury Apartments (Golf Course Rd. South of Westside Blvd.) Trip Generation Data (ITE Trip Generation Manual - 10th Edition)*

USE (ITE CODE)	24 HOUR TWO-WAY VOLUME	A. M. PEAK HOUR		P. M. PEAK HOUR		
		GROSS	ENTER	EXIT	ENTER	EXIT
Units						
<b>Multifamily Housing (Mid-Rise)</b>	<b>208</b>	1,130	19	55	56	36
	Dwelling Units					

**ITE Trip Generation Equations:**

Average Vehicle Trip Ends on a Weekday (24 HOUR TWO-WAY VOLUME)

$$T = 5.44 (X) + -1.75$$

50% Enter,                      50% Exit

Average Vehicle Trip Ends on a Weekday, Peak Hour of Adjacent Street Traffic, One Hour Between 7am and 9am (A.M. PEAK HOUR)

$$T = 0.36 (X) + 0$$

26% Enter,                      74% Exit

Average Vehicle Trip Ends on a Weekday, Peak Hour of Adjacent Street Traffic, One Hour Between 4pm and 6pm (P.M. PEAK HOUR)

$$T = 0.44 (X) + 0$$

61% Enter,                      39% Exit

Comments:

Four Stories

Based on ITE Trip Generation Manual - 10th Edition