



November 12, 2021

Jolene Wolfley, Chair
Development Review Board
City of Albuquerque
PO Box 1293
Albuquerque, NM 87103

RE: 4720 Alexander Blvd NE Site Development Plan for Building Permit PR-2021-005740

Dear Chairperson Wolfley:

Scott Anderson agent for Revel requests approval of a Major Amendment to Site Plan DRB for the above referenced site.

Site location and history

The project site is located on Alexander Blvd NE. The site is bordered on the north by the elevated roadway of Montano Blvd to the east of Top Golf and on the south by a strip mall. All adjoining properties are zoned NR-BP. This is an existing structure has already been re-purposed from a big box retail store to an entertainment center. The property currently houses a mix of restaurants, performance space and sports bar. The proposed change is to increase the height of a portion of the building to 48ft 6in provide for a fly loft. The area where the new fly loft will be located will be used as storage under this DRB application. In addition to the increase in height offices and restrooms will be constructed inside the space without raising the height of the building. Eventually the storage portion of the project will be transitioned to "other indoor entertainment" as defined by the IDO but that will be achieved under a separate DRB application or Administrative Amendment and building permit as more parking becomes available.

The project has been approved by Renaissance Center.

Site Orientation and Pedestrian Circulation

The front of the building faces Alexander Blvd and remains unchanged. Pedestrian accessibility will be available to all adjacent public streets. Vehicular access to the site will be from the west, and south of the site.

Traffic Impact and On-Site Parking

The proposed site plan meets the parking required for the proposed structure with the current on-site parking configuration. There is no need for a signed agreement with code enforcement over and above DRB approval, this eliminates Transportation Development Comment 1.

Parking:

Restaurant & bar: 21,356 sf x 0.008 = 170 parking spaces (existing use)

Outdoor patio: 3,217 sf x 0.008 = 25 parking spaces (existing use)

Auditorium 15 occupants x 0.25 = 3 parking spaces (new)

Office 1,900 sf x 0.0035 = 7 parking spaces (new)

Storage = 0 spaces (new)

Parking spaces required = 205 spaces

parking provided: 224 sp on site + 8 sp at street = 232 spaces

HC parking = 7 spaces, 2 van accessible

5 motorcycle spaces required



7 bicycle spaces required

SCOTT C. ANDERSON
& associates architects

7604 rio penasco nw
albuquerque, nm 87120
andersonscottc@comcast.net
505.401.7575

Drainage and Landscaping

The existing topography is relatively flat and no new drainage is required as part of this project. The site will not be impacted by this project.

A new landscaping plan is being submitted as part of this project. The area of landscaping is not increased by this project. There are no street trees along Montano Blvd because the Montano roadway sits 20'+/- above the site. The Montano roadway elevation difference is made possible by a significant retaining wall. The retaining wall and the grade change make the planting, irrigation, and maintenance of street trees in this location impractical. Please reference the attached photos. NMDOT is "Improving the Montgomery Boulevard interchange by adding capacity to both directions of Montgomery Boulevard, adding turn lane capacity, adding advance U-turns to the frontage roads, enhancing the on and off ramps and improving active transportation access. Based on the extent of this work it is apparent that any landscaping provided at this location will be destroyed in the near future. It should be noted that there are currently no street trees along Montano at from Culture west to Renaissance. The alternate landscape plan submitted to DRB provides site trees to the greatest extent possible given the available landscape area.

Elevations

The existing building is split face CMU. The proposed fly loft addition will be stucco and have building mounted signs. The added building mass is placed as far from the existing street frontages as possible.

Neighborhood Meeting

An invitation to a zoom meeting held on July 8, 2021, was sent to the applicable neighborhood associations. One invitee declined the meeting via email. There were no attendees other than the Agent.

Summary

We are requesting approval of the proposed Major Amendment to Site Plan DRB. The proposed project furthers numerous policies of applicable plans and provides for an increase in services and employment opportunities for area residents. The proposed plan amendment is consistent with the spirit and intent of the ABC Comp, Plan. The proposed changes comply with the IDO if it were applied to this site. The proposed plan amendment promotes the efficient use of public facilities by providing services within the city's core and does not require expansion of public utilities and infrastructure. The plan amendment promotes health, safety and general welfare by redeveloping a structure that was vacant for years into a vibrant community space that promotes the arts and quality of life.

If you have any questions or need additional information regarding this project, please do not hesitate to contact me.

Respectfully,

Scott C. Anderson AIA