DEVELOPMENT REVIEW BOARD - **HYDROLOGY SECTION**

Ernest Armijo, P.E., Principal Engineer | 505-924-3986 earmijo@cabq.gov

DRB Project Number: 2022-006614 Hearing Date: **6-15-2022**

Project: 6508 Jade Dr Agenda Item No: **10**

☐ Sketch Plat	☐ Minor Preliminary / Final Plat	☐ Preliminary Plat	☐ Final Plat
☐ Temp Sidewalk Deferral	☐ Sidewalk Waiver/Variance	☐ Site Plan for Bldg. Permit ☐ Site Plan for Subdivision	☐ Bulk Land Plat
☐ SIA Extension	☐ DPM Variance	☒ Vacation of Public Easement	☐ Vacation of Public Right of Way

ENGINEERING COMMENTS:

- The 60" RCP is centered between the 25' easement to the north and the 25' easement to the south, which is in question with this request. Both of these easements are required to remain in place to allow access to the 60" RCP. Hydrology has reviewed the figure provided to determine if even a portion of the easement can be vacated and unfortunately the figure proves that the entire easement is required for access to this line and cannot approve of the vacation of this easement.

RESOLUTION/COMMENTS:

Water:

Code:

Parks:

Transportation:

Planning:

☐ APPROVED
☐ DENIED

DELEGATED TO: ☐ TRANS ☐ HYD ☐ WUA ☐ PRKS ☐ PLNG
Delegated For: _____
SIGNED: ☐ I.L. ☐ SPSD ☐ SPBP ☐ FINAL PLAT
DEFERRED TO _____