MORRIS 12 FEEDER RELOCATION FROM NEIGHBORHOOD TO MORRIS STREET

Approx. 1050’ of underground distribution feeder to avoid conflicts with multiple curb cut access points to parking lots and circulation for apartments along Morris Street.

Remove approx. 550’ of overhead distribution feeder line and two poles from inside the neighborhood.

Existing overhead distribution lines.

Existing overhead distribution feeder line.

Approx. 600’ of overhead distribution feeder line and 4 new poles in Morris Street Right-of-Way.

Approx. 300’ of overhead distribution feeder line fand 2 new poles in Morris Street Right-of-Way.

Existing overhead distribution feeder lines.