



Luminaire Schedule									
Symbol	Qty	Label	Arrangement	Description	Tag	ILF	Luminaire Lumens	Luminaire Watts	Total Watts
	20	A	Single	Kuzco, Vesta - AT7950 - BK	EMULATE MOD HAYLEN	0.900	3215	56.5	1130
	4	B2	Single	ILP #S4S-6L-U-30-T2-HSS		0.900	4977	45.8	183.2
	11	B5	Single	ILP #S4S-9L-U-30-T3SS		0.900	8973	69.9	768.9
	4	C	Single	OCL-WET-030K-14-GW-XXX-LED2_35K-UINV		0.900	2145	25	100
	1	W1	Single	ILP #SWM-3L-U-40-T3 (EM)		0.900	3168	20.7	20.7

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
EAST<SFT	Illuminance	Fc	0.01	0.1	0.0	N.A.	N.A.
NORTH<SFT	Illuminance	Fc	0.1	0.6	0.0	N.A.	N.A.
PARKING LOT	Illuminance	Fc	1.63	7.3	0.0	N.A.	N.A.
PROPERTY LINE AT GRADE	Illuminance	Fc	0.00	0.0	0.0	N.A.	N.A.
SOUTH<SFT	Illuminance	Fc	0.04	0.1	0.0	N.A.	N.A.
WEST<SFT	Illuminance	Fc	0.00	0.1	0.0	N.A.	N.A.