



# City of Albuquerque Stormwater Construction Site Inspection Report

## General Information

ESC File No.	C12E004	Project Name:	Kiddie Academy Westside		
NPDES Id. No.	NMR100370	Location:	4590 Paradise Blvd. NW		
5/7/2021	Owner			Contractor	
Operator	Azaan Holdings			Snyder Construction	
Contact name & title	Aleem Hasham			Benny Saiz	
e-mail	<a href="mailto:aleemhasham@kiddieacademy.net">aleemhasham@kiddieacademy.net</a>			<a href="mailto:bsaiz@snyder-const.com">bsaiz@snyder-const.com</a>	
Contact Phone #	501-256-9687			505-263-0961	
COA Inspector	Thomas Evans	Start/End Time:	10:20 AM/10:55 AM		
Construction Phase:	Building construction				
Type of Inspection:	Regular	Storm Event	Past Storm Event >0.25"	311/Complaint	Follow Up
Weather at time of inspection?	clear	Temperature:	~ 74		
Estimated date of last storm 0.25" or greater	5/3/2021				
Item Number	Deficiency/ Corrective Action				
1	Sediment discharge off of site after water truck sprayed water on the pavement of the site entrance. Remove trackout and sediment from the streets prior to any watering.				
2	Holes in silt fences. Repair/replace damaged silt fences to prevent sediment from exiting the site.				
3	Rasping debris and construction waste on the ground. Remove and dispose of construction waste in approved waste containers (CGP 2.3.3e). Remove rasping debris continuously with a vacuum and enclose the work area with plastic sheeting.				
4	Washout on the ground. Direct wash water from concrete, paint, and stucco into a leak-proof container per CGP 2.3.4. Remove and dispose of hardened concrete with other waste in per CGP 2.2.3.				
5					
2.1	Discharge off site? (Y/N)	Yes			
4	Self Inspection Reports	Requested	Latest report Date:	8/27/2020	

Notes: The inlet closest to the site is further to the south on Nunzio Rd. It did not have any inlet protection. The white foam that was on the site was also in the sediment in the street. The water truck was spraying the full length of the road down to the roundabout. I called Benny Saiz to notify him of the discharge, and he said he would get his crew on it. I returned at 11:29 AM and the water truck was continuing to spray and nobody was out cleaning up any sediment.

City of Albuquerque Stormwater Inspector Signature and date:

Contact information: Thomas Evans (505-803-6215)  
[tevans@cabq.gov](mailto:tevans@cabq.gov)

*Thomas Evans* 05/10/2021