

CITY OF ALBUQUERQUE



April 29, 2019

Scott C. Anderson
Scott Anderson
7604 Rio Penasco NW
Albuquerque, NM 87120

Re: Daniel's Warehouse
8308 Washington St NE
Traffic Circulation Layout
Engineer's/Architect's Stamp **04-11-2019** (C17D017)

Dear Mr. Anderson,

1. Please list the width and length for all existing and proposed parking spaces. Some dimensions are not shown.
2. The handicap accessible spaces must be a minimum of 8.5 ft. in width.
3. The handicap accessible spaces must include an access aisle. Van accessible aisles should be 8ft wide; all others should be 5ft wide.
4. The ADA access aisles shall have the words **"NO PARKING"** in capital letters, each of which shall be at least one foot high and at least two inches wide, placed at the rear of the parking space so as to be close to where an adjacent vehicle's rear tire would be placed. (66-1-4.1.B NMSA 1978)

Resubmit a revised plan along with fully completed Drainage Transportation Information Sheet to front counter personnel for log in and evaluation by Transportation. PDF copies of the plans and submittal package must be emailed to PLNDRS@cabq.gov at time of resubmittal. If you have any questions, please contact me at 924-3675.

Sincerely,

Mojgan Maadandar, E.I.
Associate Engineer, Planning Dept.
Development Review Services

/MM via: email
C: CO Clerk, File