

CITY OF ALBUQUERQUE



March 29, 2019

Treveston Elliot Architect
Treveston Eliot
811 12th St. NW
Albuquerque, NM 88102

Re: **Rexel Corp**
5300 Eagle Rock Ave.
Traffic Circulation Layout
Engineer's/Architect's Stamp **03-25-2019** (C18D037C)

Dear Mr. Elliot,

Based upon the information provided in your submittal received 03-25-19, the above referenced plan cannot be approved for Building Permit until the following comments are addressed:

1. List the number of parking spaces required by the zoning code as well as the proposed number of parking spaces including bicycle and motorcycle parking. Make sure parking table reflects actual uses in the building, for example gym, offices, recreation, etc.
2. Please list the width and length for all existing and proposed parking spaces. Some dimensions are not shown.
3. Label the compact parking spaces by placing the words "**COMPACT**" on the pavement of each space.
4. The handicap accessible spaces must be a minimum of 8.5 ft. in width.
5. The handicap accessible spaces must include an access aisle. Van accessible aisles should be 8ft wide; all others should be 5ft wide.
6. The ADA accessible parking sign must have the required language per 66-7-352.4C NMSA 1978 "**Violators Are Subject to a Fine and/or Towing.**" Please call out detail and location of HC signs.
7. The ADA access aisles shall have the words "**NO PARKING**" in capital letters, each of which shall be at least one foot high and at least two inches wide, placed at the rear of the parking space so as to be close to where an adjacent vehicle's rear tire would be placed. (66-1-4.1.B NMSA 1978)
8. Show all drive aisle widths and radii. Some dimensions are not shown.
9. Per the zoning code, a 6 ft. wide ADA accessible pedestrian pathway is required from the public sidewalk to the building entrances. Please clearly show this pathway and provide details.

PO Box 1293

Albuquerque


NM 87103

www.cabq.gov

10. Per DPM, a 6 ft. wide ADA accessible pedestrian pathway is required from the HC parking stall access aisles to the building entrances. Please clearly show this pathway and provide details.
11. Please provide a sight distance exhibit

Resubmit a revised plan along with fully completed Drainage Transportation Information Sheet to front counter personnel for log in and evaluation by Transportation. PDF copies of the plans and submittal package must be emailed to PLNDRS@cabq.gov at time of resubmittal. If you have any questions, please contact Racquel Michel @ (505) 924-3991 or me at 924-3675.

Sincerely,



Racquel M. Michel, P.E.
Traffic Engineer, Planning Dept.
Development Review Services

Mojgan Maadandar, E.I.
Associate Engineer, Planning Dept.
Development Review Services

/MM via: email
C: CO Clerk, File