

CITY OF ALBUQUERQUE



January 17, 2017

Shakeel Rizvi, Nazish LLC: shaky1424@yahoo.com

Re: Drainage Control Ordinance (14-5-2-1) and NPDES CGP Violations for Erosion and Sediment Control

Dear Mr. Rizvi,

At today's SWPPP inspection, there were no sediment BMPs to prevent sediment from entering the City street and the newly installed inlet(s) in Signal Ave.

Photos are shown below:



No BMPs including: silt fence, filter sock/wattle or track-out pad.

PO Box 1293

Albuquerque

New Mexico 87103

www.cabq.gov

CITY OF ALBUQUERQUE



No inlet protection and sediment in gutter.

PO Box 1293

Albuquerque

New Mexico 87103

www.cabq.gov

Required mitigation:

1. Install inlet protection on both inlets. Inlet protection should allow some drainage to enter. A filter/mulch sock that covers the throat and curves around to the edge of the gutter pan should work.
2. A sediment BMP is required along the northern edge of the site that keeps sediment on-site. Either a staked-down wattle/filter sock or silt fence should work.
3. If site work is to continue prior to the street going under construction, a tack-out pad is required.

The above listed violations are to be mitigated within seven days to be in compliance with the EPA NPDES Construction General Permit.

In addition, if violations are not mitigated within 30 days or are found again after 30 days, the property owner is subject to a fine of \$500/day per the City's Drainage Control Ordinance.

If you have any questions, you can contact me at 924-3420.

Sincerely,


Curtis Cherne, P.E.

Principal Engineer, Stormwater Quality
Planning Dept.