

Bank of Albuquerque
(Carmel Ave. / Wyoming Blvd.)
Queuing Analysis / Access Study

—◆—
June 11, 2007

Terry O. Brown, P.E.

Presented to:

**Transportation Development Division
City of Albuquerque**

Prepared for:

**Claudio Vigil & Architects
1801 Rio Grande Blvd. NW
Albuquerque, NM 87104**



Terry O. Brown

Terry O. Brown, P.E.
P. O. Box 92051
Albuquerque, NM 87199
(505) 883-8807

Terry O. Brown, P.E.

P. O. Box 92051
Albuquerque, NM 87199-2051
(505) 883-8807 - Voice
(505) 212-0267 - FAX
e-mail: tobe@swcp.com



Monday, March 20, 2006

Tony Loyd

City of Albuquerque Transportation Development
600 2nd St. NW
Albuquerque, NM 87102

Re: Queuing Analysis for Bank of Albuquerque (Carmel Ave. / Wyoming Blvd.)

Dear Tony:

As you requested, attached is the queuing analysis and other transportation analysis provided for the purpose of providing sufficient information for the City to determine whether or not a full access driveway will be approved at the northwest corner of the proposed Bank of Albuquerque. Also, data and analysis are provided for the purpose of determining whether or not it would be prudent to approve the proposed right-turn-in, right-turn-out driveway on Wyoming Blvd. at the south end of the Bank of Albuquerque site.

To determine the forecast queue lengths at the intersection of Carmel Ave. / Wyoming Blvd., recent turning movement counts were taken at the intersection for the AM and PM Peak Hour periods. The volumes were then grown to the year 2008 using an annual 3% growth rate. To those volumes, the trips generated by the proposed Bank of Albuquerque was added. An analysis of the signalized intersection of Carmel Ave. / Wyoming Blvd. was performed using TEAPAC's Signal 2000, version 2.0 software. The computer modeling reports the level-of-service and delays for the 2008 AM and PM Peak Hour BUILD Conditions for the intersections. It also reports approximate queue lengths. However, the queues for this intersection were determined using the standard City of Albuquerque methodology (Poisson's Arrivals – 95% probable comfort level). Next, the proposed driveway(s) on the project were analyzed to determine unsignalized intersection levels-of-service / delays and queue lengths for the 2008 AM and PM Peak Hour BUILD Conditions. The above described procedure was performed for two different Cases as defined below:

Case A – Case "A" assumes that the only driveway (Driveway "A") accessing the proposed Bank of Albuquerque will be on Carmel Ave. at the northwest corner of the project. It is assumed to be a full access driveway.

Case B – Case "B" assumes that there will be two driveways accessing the proposed Bank of Albuquerque. One access will be Driveway "A" as previously described. The second access (Driveway "B") will be an unsignalized right-turn-in, right-turn-out only driveway on Wyoming Blvd. at the south edge of the project. (See Appendix Page A-2). Discussion of the analysis of the two Cases follows.

Re: Queuing Analysis for Bank of Albuquerque (Carmel Ave. / Wyoming Blvd.)

Case "A"

All of the entering and exiting traffic utilizes Driveway "A" on Carmel Ave. The centerline of Driveway "A" is located approximately 250 feet west of the stop bar for eastbound traffic on Carmel Ave. at Wyoming Blvd.

Under this condition, the projected 2008 AM and PM Peak Hour levels-of-service for the intersection of Carmel Ave. / Wyoming Blvd. is summarized in the following table:

Carmel Ave. / Wyoming Blvd.	2008 BUILD Conditions	
	AM Peak	PM Peak
CASE "A"	B – 12.4	C – 20.6

The projected level-of-service and delay at the intersection are acceptable in both periods for Case "A". The calculated queue length by Signal 2000 for the PM Peak Hour for the eastbound approach is 53 feet for the left turn lane and 220 feet for the thru / right turn lane. The queuing for the eastbound thru / right turn movement appears to be approaching the location of Driveway "A". If possible, measures should be taken to reduce the eastbound queue. The queue length calculated using the City's standard methodology for queuing (Poisson's Arrivals) results in a 100 feet long queue for the eastbound left turn lane and a 300 feet long queue for the thru / right turn lane. This calculation shows the queue in the thru / right turn lane to be slightly beyond Driveway "A".

The projected 2008 AM and PM Peak Hour levels-of-service for the unsignalized Driveway "A" are summarized in the following table:

Carmel Ave. / Driveway "A"	2008 BUILD Conditions	
	AM Peak	PM Peak
CASE "A"	A – 9.3	B – 11.1

The projected level-of-service and delay at the intersection are acceptable in both periods for Case "A". Using HCM methodology for calculating the queue length for the westbound left turn movement into Driveway "A" results in a queue of less than 1 vehicle. The projected westbound left turn volume at Driveway "A" under Case "A" is 22 vehicles per hour during the AM Peak Hour and 55 vehicles per hour during the PM Peak Hour. Under this scenario, the westbound left turn lane should be constructed to a length of greater than one vehicle. According to the HCM analysis, though, the one vehicle length should work at least 95% of the time.

Re: Queuing Analysis for Bank of Albuquerque (Carmel Ave. / Wyoming Blvd.)

Case "B"

The entering and exiting traffic under Case "B" will be able to access the site via two driveways (Driveway "A" on Carmel Ave. and Driveway "B" on Wyoming Blvd.). Driveway "B" is proposed to be a right-turn-in, right-turn-out only driveway. Under Case "B", entering traffic approaching the bank from the east or from the north will have the option to use Driveway "B" to access. Also, traffic exiting the bank desiring to travel south on Wyoming will have the option to use Driveway "B" to access Wyoming Blvd. southbound.

Under Case "B", the projected 2008 AM and PM Peak Hour levels-of-service for the intersection of Carmel Ave. / Wyoming Blvd. is summarized in the following table:

Carmel Ave. / Wyoming Blvd.	2008 BUILD Conditions	
	AM Peak	PM Peak
CASE "B"	B – 12.2	B – 19.8

The projected level-of-service and delay at the intersection are acceptable in both periods for Case "B", and constitute a slight improvement over Case "A". The calculated queue length by Signal 2000 for the PM Peak Hour for the eastbound approach is 55 feet for the left turn lane and 185 feet for the thru / right turn lane. The queuing for the eastbound thru / right turn movement appears to be approaching the location of Driveway "A", but still a few vehicle lengths short of it. Implementation of Driveway "B" as a right-turn-in, right-turn-out access to the site reduces the eastbound queue on Carmel Ave. at Wyoming by about 16%. The queue length calculated using the City's standard methodology for queuing (Poisson's Arrivals) results in a 100 feet long queue for the eastbound left turn lane and a 250 feet long queue for the thru / right turn lane. This calculation shows the queue in the thru / right turn lane to be at Driveway "A". To further reduce the queue on eastbound Carmel Ave. at Wyoming Blvd., a short eastbound right turn lane should be constructed at the intersections. It appears from the architectural plan for this project that there is enough pavement width at the eastbound approach to stripe a 30 feet long eastbound right turn lane on Carmel. This would not only decrease the queue length for eastbound Carmel, but it would also permit a higher percentage of right turns on red for that approach. Considering the short eastbound right turn lane, the queue length for eastbound Carmel Ave. thru / right turn movement would be approximately 225 feet or less based on the City of Albuquerque's standard method of calculating queue lengths at signalized intersections. The 225 feet long queue length assumes that the 30 feet long eastbound right turn lane is in place and also assumes a 130-second cycle length for the signal. A shorter cycle length would result in shorter queues.

The projected 2008 AM and PM Peak Hour levels-of-service for the unsignalized Driveway "A" are summarized in the following table:

Carmel Ave. / Driveway "A"	2008 BUILD Conditions	
	AM Peak	PM Peak
CASE "A"	A – 9.5	B – 11.2

The projected level-of-service and delay at the intersection are acceptable in both periods for Case "B". Using HCM methodology for calculating the queue length for the westbound left turn movement into Driveway "A" results in a queue of less than 1 vehicle. The projected westbound

Re: Queuing Analysis for Bank of Albuquerque (Carmel Ave. / Wyoming Blvd.)

left turn volume at Driveway "A" under Case "B" is 17 vehicles per hour during the AM Peak Hour and 40 vehicles per hour during the PM Peak Hour. This again is a slight reduction of the projected westbound left turn volumes under Case "A". Under this scenario, the westbound left turn lane should be constructed to a length of greater than one vehicle. According to the HCM analysis, though, the one vehicle length should work at least 95% of the time.

The projected southbound right turn volume turning into Driveway "B" is 5 vehicles per hour during the AM Peak Hour and 11 vehicles per hour during the PM Peak Hour. The projected right turn volumes are not sufficient to warrant a right turn deceleration lane. However, in the future, if this driveway is shared with the development to the south, the southbound right turn deceleration lane may be warranted.


Case "B" provides a reduction in calculated queue lengths for the eastbound approach on Carmel Ave. at Wyoming Blvd. and a reduction of westbound left turn volume at proposed Driveway "A" on Carmel Ave. into the proposed Bank of Albuquerque. Thus, this report has demonstrated a definite benefit to implementing a right-turn-in, right-turn-out unsignalized driveway on Wyoming Blvd. at the south side of this project.

Based on the analysis contained in this study, the following recommendations are made:

- 1) Driveway "A" located at the northwest corner of the proposed Bank of Albuquerque should be a full access unsignalized driveway.
- 2) Driveway "A" should be located as far to the west of Wyoming Blvd. as is possible.
- 3) A westbound left turn lane should be constructed on Carmel Ave. at Driveway "A" to a length of 25 feet plus transition (enough for a one-vehicle queue). See conceptual drawing on Appendix Page A-3.
- 4) The eastbound left turn lane on Carmel Ave. at Wyoming should maintain a length of 150 feet plus transition. The transition should utilize a 125' - 125' radius reverse curve.
- 5) A new right-turn-in, right-turn-out unsignalized driveway should be constructed on Wyoming Blvd. at the south end of the Bank of Albuquerque project (approximately 250 south of Carmel Ave. centerline to centerline).
- 6) A southbound right turn deceleration lane is not warranted at Driveway "B" at this time.


Please call me if you have questions or if you need additional information.

Sincerely Yours,




Terry O. Brown



Attachments: Appendix Pages A-1 thru A-46





CASE A




CASE B



CASE A



CASE B




Bank of Albuquerque
 (Carmel Ave / Wyoming Blvd)
 2008 NO BUILD Volumes - AM(PM)


Terry O. Brown, P.E.
 P.O. Box 92051
 Albuquerque, NM 87199-2051
 (505)883-8807 (Voice)








NTS



CASE A



CASE B




CASE A


CASE B

Bank of Albuquerque
 (Carmel Ave / Wyoming Blvd)
 Trips Generated Volumes - AM(PM)


Terry O. Brown, P.E.
 P.O. Box 92051
 Albuquerque, NM 87199-2051
 (505)883-8807 (Voice)




CASE A




CASE B



CASE A




CASE B




Bank of Albuquerque
 (Carmel Ave / Wyoming Blvd)
 2008 BUILD Volumes - AM(PM)

Terry O. Brown, P.E.
 P.O. Box 92051
 Albuquerque, NM 87199-2051
 (505)883-8807 (Voice)





Recommended Configuration Carmel Ave. @ Driveway "A"




Bank of Albuquerque
Carmel Ave / Wyoming Blvd
Aerial Photo - 2004

SITE

CARMEL AVE


WYOMING BLVD



Draft 2004 Traffic Flows for the Greater Albuquerque Area

Prepared by the
Mid-Region Council of Governments
in cooperation with the
New Mexico Department of Transportation,
the local governments in the
Albuquerque Metropolitan Planning Area,
and the U.S. Department of Transportation,
Federal Highway Administration.





Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Trip Generation Data

USE (ITE CODE)	24 HOUR TWO-WAY VOLUME		A.M. PEAK HOUR		P.M. PEAK HOUR
	GROSS	ENTER	EXIT	ENTER	EXIT
Drive-In Bank (912)	Units				
	3.00	1,067	34	24	77
Drive-In Windows					

ITE Trip Generation Equations:

Average Vehicle Trip Ends on a Weekday (24 HOUR TWO-WAY VOLUME)

$$\ln(T) = 1.326 \ln(X) + 5.516$$

50% Enter, 50% Exit

Average Vehicle Trip Ends on a Weekday, Peak Hour of Adjacent Street Traffic, One Hour Between 7am and 9am (A.M. PEAK HOUR)

$$T = 19.38 (X) + 0$$

58% Enter, 42% Exit

Average Vehicle Trip Ends on a Weekday, Peak Hour of Adjacent Street Traffic, One Hour Between 4pm and 6pm (P.M. PEAK HOUR)


$$T = 51.08 (X) + 0$$

50% Enter, 50% Exit

Comments:
Tract No.

Based on ITE Trip Generation Manual - 7th Edition

Historic Growth Chart Wyoming Blvd North of Paseo del Norte (2000-2004)




Bank of Albuquerque

(Carmel Ave / Wyoming Blvd)

Growth Rate Map (%)



NTS



* Generic growth rate of 3% used
where rate is negative or
unavailable

Terry O. Brown, P.E.
P.O. Box 92051
Albuquerque, NM 87199-2051
(505)883-8807 (Voice)
(505)212-0267 (Fax)



DATA ANALYSIS SUBZONE (DASZ) MAP
Bank of Albuquerque (Carmel Ave / Wyoming Blvd)

Trip Distribution Table
Bank of Albuquerque (Carmel Ave / Wyoming Blvd)

Data Analysis Subzone Population Data for determination of Local Trip Distribution for Proposed Retail Commercial Trips

2000 and 2025 Data Taken from Mid-Region Council of Governments' 2025 Socioeconomic
2025 Socioeconomic Forecasts by Data Analysis Subzones for the Mid-Region of New Mexico (S-03-01)

DASZ #	% Sub Area In Study	2000 Population	2025 Population	Interpolated Population for the Year 2008	Population In Study	Population / Distance	Percent Population	(WN) Wyoming Blvd North		(CE) Carmel Ave East		(WS) Wyoming Blvd South		(CW) Carmel Ave West	
								% Utilizing	% Population Utilizing	% Utilizing	% Population Utilizing	% Utilizing	% Population Utilizing	% Utilizing	% Population Utilizing
Boundary Specified on DASZ Map															
6051	25%	0	0	0	0	0	0.00%	0%	0.00%	0	0.00%	0	0.00%	0	0.00%
6052	100%	0	9	3	3	3	0.01%	0%	0.00%	0	0%	0	0.00%	1	80%
6053	100%	0	14	4	4	4	0.01%	0%	0%	0	0%	0	0.00%	1	80%
6054	100%	2	2	2	2	2	0.01%	0%	0%	0	0%	0	0.00%	0	80%
6055	5%	0	7	2	0	0	0.00%	0%	0%	0	0%	0	0.00%	0	0.00%
6056	85%	0	23	7	7	7	0.02%	0%	0%	0	0%	0	0.00%	1	80%
6058	20%	52	57	54	11	11	0.03%	0%	0.00%	0	0%	0	0.01%	2	80%
6512	50%	3	379	123	62	62	0.17%	20%	0.03%	12	0%	0	0.00%	0	0%
6523	15%	602	633	612	92	92	0.25%	20%	0.05%	18	0%	0	0.00%	0	0%
6525	100%	387	453	408	408	408	1.12%	20%	0.22%	82	0%	0	0.00%	0	0%
6526	100%	1330	1263	1309	1,309	1,309	3.56%	20%	0.72%	262	0%	0	0.00%	262	80%
6527	30%	0	2	1	0	0	0.00%	0%	0.00%	0	0%	0	0.00%	0	0%
7111	100%	1176	1184	1,179	1,179	1,179	3.23%	0%	0.00%	0	0%	0	0.00%	0	0%
7112	100%	5	10	7	7	7	0.02%	0%	0.00%	0	0%	0	0.00%	0	0%
7113	100%	893	1145	974	974	974	2.67%	0%	0.00%	0	0%	0	0.00%	0	0%
7114	100%	1486	1408	1,461	1,461	1,461	4.00%	0%	0.00%	0	0%	0	0.00%	0	0%
7115	100%	1541	1450	1,512	1,512	1,512	4.14%	0%	0.00%	0	0%	0	0.00%	0	0%
7116	100%	1275	1372	1,308	1,308	1,308	3.57%	0%	0.00%	0	0%	0	0.00%	0	0%
7121	100%	952	920	942	942	942	2.58%	0%	0.00%	0	0%	0	0.00%	0	0%
7122	100%	1310	1269	1,297	1,297	1,297	3.55%	0%	0.00%	0	0%	0	0.00%	0	0%
7123	100%	1288	1729	1,416	1,416	1,416	3.87%	0%	0.00%	0	0%	0	0.00%	0	0%
7124	100%	1473	1491	1,479	1,479	1,479	4.05%	0%	0.00%	0	0%	0	0.00%	0	0%
7125	100%	1384	1297	1,356	1,356	1,356	3.71%	0%	0.00%	0	10%	0	0.37%	148	90%
7126	100%	0	1209	387	387	387	1.06%	0%	0.00%	0	0%	0	0.00%	0	0%
7141	45%	1475	1372	1,442	649	649	1.78%	0%	0.00%	0	10%	0	0.18%	65	90%
7142	100%	1441	1359	1,415	1,415	1,415	3.87%	0%	0.00%	0	10%	0	0.39%	142	90%
7143	100%	2109	1934	2,053	2,053	2,053	5.82%	0%	0.00%	0	10%	0	0.59%	205	90%
7144	95%	78	462	201	191	191	0.52%	0%	0.00%	0	10%	0	0.05%	19	90%
7145	50%	500	1628	922	461	461	1.26%	0%	0.00%	0	10%	0	0.13%	46	90%
7151	25%	1029	964	1,008	252	252	0.69%	0%	0.00%	0	0%	0	0.00%	0	0%
7152	55%	1418	1324	1,366	763	763	2.09%	0%	0.00%	0	0%	0	0.00%	0	0%
7153	100%	1420	1336	1,393	1,393	1,393	3.81%	0%	0.00%	0	0%	0	0.00%	0	0%
7154	85%	1262	1156	1,228	1,044	1,044	2.86%	0%	0.00%	0	0%	0	0.00%	0	0%
7155	90%	902	836	881	793	793	2.17%	0%	0.00%	0	0%	0	0.00%	0	0%
7156	100%	1525	1415	1,490	1,490	1,490	4.08%	0%	0.00%	0	0%	0	0.00%	0	0%
7157	95%	736	1232	895	850	850	2.33%	0%	0.00%	0	0%	0	0.00%	0	0%
7201	100%	1826	2475	2,034	2,034	2,034	5.57%	0%	0.00%	0	0%	0	0.00%	0	0%
7202	100%	106	214	141	141	141	0.39%	0%	0.00%	0	0%	0	0.00%	0	0%
7203	100%	294	1362	636	636	636	1.74%	50%	0.87%	318	0%	0	0.00%	0	0%
7204	100%	360	1666	778	778	778	2.13%	50%	1.09%	399	0%	0	0.00%	0	0%
7231	15%	0	0	0	0	0	0.00%	100%	0.00%	0	0%	0	0.00%	0	0%
7241	100%	0	647	207	207	207	0.57%	0%	0.00%	0	0%	0	0.00%	0	0%
7242	100%	34	371	142	142	142	0.39%	50%	0.19%	71	0%	0	0.00%	0	0%
7251	100%	117	374	199	199	199	0.54%	100%	0.54%	199	0%	0	0.00%	0	0%
7252	100%	252	620	370	370	370	1.01%	50%	0.51%	185	50%	0	0.00%	0	0%
7253	100%	1109	1249	1,154	1,154	1,154	3.16%	100%	3.16%	1,154	0%	0	0.00%	0	0%
7254	100%	1631	1645	1,635	1,635	1,635	4.47%	50%	2.24%	818	50%	0	0.00%	0	0%
7255	100%	894	2022	1,255	1,255	1,255	3.43%	25%	0.85%	314	75%	0	0.00%	0	0%
7261	95%	333	475	378	359	359	0.98%	100%	0.98%	359	0%	0	0.00%	0	0%
7262	45%	188	259	211	95	95	0.26%	100%	0.26%	95	0%	0	0.00%	0	0%
7263	95%	192	518	286	281	281	0.77%	100%	0.77%	141	50%	0	0.00%	0	0%
7264	100%	548	999	692	692	692	1.89%	50%	0.95%	346	50%	0	0.00%	0	0%
		40,285	38,546	38,546	38,546	38,546	100.00%	4,762	13.03%	3,191	8.73%	16,114	44.09%	12,479	34.15%


Bank of Albuquerque

(Carmel Ave / Wyoming Blvd)

Trip Distribution Map (%)



NTS



Terry O. Brown, P.E.

P.O. Box 92051
Albuquerque, NM 87199-2051
(505)883-8807 (Voice)
(505)212-0267 (Fax)

2008 Peak Hour Existing Conditions


Case A – without RI-RO driveway

Bank of Albuquerque

(Carmel Ave / Wyoming Blvd)

Trip Assignments (% Entering)

Case A - w/o RI-RO driveway



-  SIGNALIZED INTERSECTION
-  UNSIGNALIZED INTERSECTION

Terry O. Brown, P.E.
P.O. Box 92051
Albuquerque, NM 87199-2051
(505)883-8807 (Voice)
(505)212-0267 (Fax)

Bank of Albuquerque


(Carmel Ave / Wyoming Blvd)

Trip Assignments (% Exiting)

Case A - w/o RI-RO driveway



NTS



Terry O. Brown, P.E.

P.O. Box 92051

Albuquerque, NM 87199-2051

(505)883-8807 (Voice)

(505)212-0267 (Fax)



Bank of Albuquerque (Carmel Ave / Wyoming Blvd)

Projected Turning Movements SUMMARY

PROPOSED DEVELOPMENT (2008) - 100% Development

Case A - w/o RI-RO driveway

INTERSECTION: Summary

Carmel Ave / Wyoming Blvd

(1)

3.0% Truck

Existing (2006)

2008 (NO BUILD - A.M.)

2008 (BUILD - A.M.)

0.71			0.95			0.86			0.87			PHF
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)			
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
15	21	12	144	48	84	33	443	45	96	671	13	
16	22	13	153	51	89	35	470	48	102	711	14	
19	24	24	153	54	89	50	470	48	102	711	18	

Existing (2006)

2008 (NO BUILD - P.M.)

2008 (BUILD - P.M.)

0.72			0.88			0.95			0.95			PHF
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)			
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
30	87	26	247	42	127	113	731	72	169	453	9	
32	92	28	262	45	135	120	775	76	179	480	10	
42	99	62	262	52	135	154	775	76	179	480	20	

Carmel Ave / Driveway 'A'

(2)

3.0% Truck

Existing (2006)

2008 (NO BUILD - A.M.)

2008 (BUILD - A.M.)

0.71			0.71			0.85			0.85			PHF
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')			
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
0	48	0	0	94	0	0	0	0	0	0	0	
0	51	0	0	100	0	0	0	0	0	0	0	
0	51	12	22	100	0	8	0	16	0	0	0	

Existing (2006)

2008 (NO BUILD - P.M.)

2008 (BUILD - P.M.)

0.72			0.72			0.85			0.85			PHF
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')			
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
0	143	0	0	164	0	0	0	0	0	0	0	
0	152	0	0	174	0	0	0	0	0	0	0	
0	152	26	51	174	0	26	0	51	0	0	0	

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Projected Turning Movements Worksheet
Carmel Ave / Wyoming Blvd

Case A - w/o RI-RO driveway

INTERSECTION:

E-W Street: **Carmel Ave**
 N-S Street: **Wyoming Blvd**

(1)

Year of Existing Counts
 Implementation Year

2006

2008

Growth Rates

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - A.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total AM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
15	21	12	144	48	84	33	443	45	96	671	13
1	1	1	9	3	5	2	27	3	6	40	1
16	22	13	153	51	89	35	470	48	102	711	14
16	22	13	153	51	89	35	470	48	102	711	14
0.00%	0.00%	0.00%	0.00%	8.73%	0.00%	44.09%	0.00%	0.00%	0.00%	0.00%	13.03%
13.03%	8.73%	44.09%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
3	2	11	0	3	0	15	0	0	0	0	4
19	24	24	153	54	89	50	470	48	102	711	18

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - P.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total PM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
30	87	26	247	42	127	113	731	72	169	453	9
2	5	2	15	3	8	7	44	4	10	27	1
32	92	28	262	45	135	120	775	76	179	480	10
32	92	28	262	45	135	120	775	76	179	480	10
0.00%	0.00%	0.00%	0.00%	8.73%	0.00%	44.09%	0.00%	0.00%	0.00%	0.00%	13.03%
13.03%	8.73%	44.09%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
10	7	34	0	7	0	34	0	0	0	0	10
42	99	62	262	52	135	154	775	76	179	480	20

Number of Commercial Trips Generated

Entering

34

24

A.M.

100% Commercial Development

77

77


P.M.

2006 AM Peak Hr. Volumes


2006 PM Peak Hr. Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
15	21	12	144	48	84	33	443	45	96	671	13
30	87	26	247	42	127	113	731	72	169	453	9


2008
BUILD



Trips



2008
NO BUILD



Carmel Ave / Wyoming Blvd

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
 Projected Turning Movements Worksheet
Carmel Ave / Driveway 'A'

Case A - w/o RI-RO driveway

INTERSECTION:

E-W Street: **Carmel Ave**
 N-S Street: **Driveway 'A'**

(2)

Year of Existing Counts
 Implementation Year

2006

2008

Growth Rates

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - A.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total AM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	48	0	0	94	0	0	0	0	0	0	0
0	3	0	0	6	0	0	0	0	0	0	0
0	51	0	0	100	0	0	0	0	0	0	0
0	51	0	0	100	0	0	0	0	0	0	0
0.00%	0.00%	34.15%	65.85%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	34.15%	0.00%	65.85%	0.00%	0.00%	0.00%
0	0	12	22	0	0	8	0	16	0	0	0
0	51	12	22	100	0	8	0	16	0	0	0

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - P.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total PM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	143	0	0	164	0	0	0	0	0	0	0
0	9	0	0	10	0	0	0	0	0	0	0
0	152	0	0	174	0	0	0	0	0	0	0
0	152	0	0	174	0	0	0	0	0	0	0
0.00%	0.00%	34.15%	65.85%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	34.15%	0.00%	65.85%	0.00%	0.00%	0.00%
0	0	26	51	0	0	26	0	51	0	0	0
0	152	26	51	174	0	26	0	51	0	0	0

Number of Commercial Trips Generated

Entering

Exiting

34

24

A.M.

100% Commercial Development

77

77


P.M.

2006 AM Peak Hr. Volumes


2006 PM Peak Hr. Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	48	0	0	94	0	0	0	0	0	0	0
0	143	0	0	164	0	0	0	0	0	0	0


2008
BUILD



Trips



2008
NO BUILD



Carmel Ave / Driveway 'A'

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
 Projected Turning Movements Worksheet
Driveway 'B' / Wyoming Blvd

INTERSECTION:

E-W Street: Driveway 'B' (3)

N-S Street: Wyoming Blvd

Year of Existing Counts 2006

Implementation Year 2008

Growth Rates

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - A.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total AM Peak Hour BUILD Volumes

-1.00%			-1.00%			-1.00%			-1.00%		
Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	0	0	0	0	0	0	521	0	0	827	0
0	0	0	0	0	0	0	-10	0	0	-17	0
0	0	0	0	0	0	0	511	0	0	810	0
0	0	0	0	0	0	0	511	0	0	810	0
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0	0	0	0	0	0	0	0	0	0	0	0
0	0	0	0	0	0	0	511	0	0	810	0

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - P.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total PM Peak Hour BUILD Volumes

Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	0	0	0	0	0	0	916	0	0	726	0
0	0	0	0	0	0	0	-18	0	0	-15	0
0	0	0	0	0	0	0	898	0	0	711	0
0	0	0	0	0	0	0	898	0	0	711	0
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0	0	0	0	0	0	0	0	0	0	0	0
0	0	0	0	0	0	0	898	0	0	711	0

Number of Commercial Trips Generated

Entering 34 Exiting 24

77 77

A.M.

100% Commercial Development


P.M.

2006 AM Peak Hr. Volumes


2006 PM Peak Hr. Volumes

Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	0	0	0	0	0	0	521	0	0	827	0
0	0	0	0	0	0	0	916	0	0	726	0


2008
BUILD



Trips



2008
NO BUILD




Driveway 'B' / Wyoming Blvd

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Analysis of Carmel Ave / Wyoming Blvd - [1A_08ABX]
2008 AM Peak BUILD Conditions-Case A (w/o RT-RO drive)

03/19/06
15:16:40

SIGNAL 2000/TEAPAC (Ver 2.70.07) - HCM Input Worksheet

Intersection # 1 - Area Location Type: NONCBD



	SB	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT	EB	TH	LT
Heavy veh, %HV	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Pk-hr fact, PHF	.87	.87	.87	.87	.87	.87	.87	.87	.87	.87	.87	.87	.87	.87	.87
Pretimed or Act	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A
Startup lost, t1	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Ext eff grn, e	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Arrival typ, AT	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Ped vol, vped	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bike vol, vbic	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Parking locatns	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Park mnvrs, Nm	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bus stops, NB	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Grade, %G	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0


Sq 11 LD/LD	Phase 1	Phase 2	Phase 3	Phase 4	Phase 5	Phase 6
	North	North				
C=100"	G= 73.9" Y+R= 5.0"	G= 16.1" Y+R= 5.0"	G= 0.0" Y+R= 0.0"	G= 0.0" Y+R= 0.0"	G= 0.0" Y+R= 0.0"	G= 0.0" Y+R= 0.0"

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Analysis of Carmel Ave / Wyoming Blvd - [1A_08ABX]
2008 AM Peak BUILD Conditions-Case A (w/o RT-RO drive)

03/19/06
15:16:40

SIGNAL 2000/TEAPAC (Ver 2.70.07) - Capacity Analysis Summary


Intersection Averages for Int # 1 - Degree of Saturation (V/c) 0.31 Vehicle Delay 12.4 Level of Service B+




C=100 sec G= 90.0 sec = 90.0% Y=10.0 sec = 10.0% Ped= 0.0 sec = 0.0%

Lane Group	Width/ Lanes	Reqd	g/C	Used	Service Rate @D (vph) @E	Adj Volume	V/c	HCM Delay	Queue Model 1
SB Approach								4.5	A
RT+TH	24/2	0.253	0.739	0.739	2586	838	0.324	4.5	*A
LT	12/1	0.202	0.739	0.739	574	117	0.204	4.2	A
NB Approach								4.1	A
RT+TH	24/2	0.193	0.739	0.739	2560	603	0.236	4.2	A
LT	12/1	0.151	0.739	0.739	437	58	0.132	3.9	A
WB Approach								46.6	D
RT	12/1	0.090	0.161	0.161	198	235	0.373	38.4	D+
TH	12/1	0.053	0.161	0.161	239	282	0.192	36.6	D+
LT	12/1	0.161	0.161	0.161	162	194	0.759	54.8	*D
EB Approach								36.9	D+
RT+TH	12/1	0.065	0.161	0.161	219	259	0.247	37.1	D+
LT	12/1	0.000	0.161	0.161	164	196	0.126	36.2	D+


SIGNAL/2000/TEAPAC(Vol 2/2007) - HCM Input Worksheet



	SB	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT
Heavy veh, %HV	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Pk-hr fact, PHF	.95	.95	.95	.95	.88	.88	.88	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95
Pretimed or Act	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A
Startup lost, t1	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Ext eff grn, e	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Arrival typ, AT	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Ped vol, vped	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bike vol, vbic	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Parking locatns	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Park mnvrs, Nim	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bus stops, NB	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Grade, %G	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0



SIGNAL/2000/TEAPAC(Vol 2/2007) - Capacity Analysis Summary



C=100 sec G= 90.0 sec = 90.0% Y=10.0 sec = 10.0% Ped= 0.0 sec = 0.0%

Lane Group	Width/ Lanes	Reqd	g/C Used	Service Rate @D (vph)	Adj Volume	v/c	HCM Delay	Queue Model 1
------------	--------------	------	----------	-----------------------	------------	-----	-----------	---------------

SB Approach	RT+TH LT	24/2 12/1	0.171 0.451	0.562 0.562	1962 248	526 188	0.268 0.701	14.6 B+
NB Approach	RT+TH LT	24/2 12/1	0.271 0.253	0.562 0.562	1947 435	896 162	0.460 0.361	13.1 B+ 12.5 B+

WB Approach	RT+TH LT	24/2 12/1	0.132 0.054	0.338 0.338	493 589	153 298	0.289 0.095	24.6 C+ 22.7 C+ 55.4 *E+ 416 ft
EB Approach	RT+TH LT	12/1 12/1	0.162 0.073	0.338 0.338	552 410	224 58	0.381 0.129	25.6 C+ 23.0 C+ 220 ft 53 ft

Queueing Analysis Summary Sheet

Project:
Intersection:

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Carmel Ave / Wyoming Blvd

CASE "A"

2008

Eastbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	15	200	1	15	200	1	21	Cont	0	12	0
AM NO BUILD Queue	1	16	50	1	16	50	1	22	50	0	13	50
AM BUILD Queue	1	19	50	1	19	50	1	24	50	0	24	50
Existing Lane Length	1	30	200	1	30	200	1	87	Cont	0	26	0
PM NO BUILD Queue	1	32	75	1	32	75	1	92	175	0	28	75
PM BUILD Queue	1	42	100	1	42	100	1	99	175	0	62	125
Westbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	144	190	1	144	190	1	48	Cont	1	84	0
AM NO BUILD Queue	1	153	200	1	153	200	1	51	100	1	89	125
AM BUILD Queue	1	153	200	1	153	200	1	54	100	1	89	125
Existing Lane Length	1	247	190	1	247	190	1	42	Cont	1	127	0
PM NO BUILD Queue	1	262	375	1	262	375	1	45	100	1	135	225
PM BUILD Queue	1	262	375	1	262	375	1	52	100	1	135	225
Northbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	33	250	1	33	250	2	443	Cont	0	45	0
AM NO BUILD Queue	1	35	75	1	35	75	2	470	300	0	48	75
AM BUILD Queue	1	50	100	1	50	100	2	470	300	0	48	75
Existing Lane Length	1	113	250	1	113	250	2	731	Cont	0	72	0
PM NO BUILD Queue	1	120	200	1	120	200	2	775	550	0	76	150
PM BUILD Queue	1	154	250	1	154	250	2	775	550	0	76	150
Southbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	96	N/A	1	96	N/A	2	671	Cont	0	13	0
AM NO BUILD Queue	1	102	150	1	102	150	2	711	425	0	14	50
AM BUILD Queue	1	102	150	1	102	150	2	711	425	0	18	50
Existing Lane Length	1	169	N/A	1	169	N/A	2	453	Cont	0	9	0
PM NO BUILD Queue	1	179	275	1	179	275	2	480	375	0	10	50
PM BUILD Queue	1	179	275	1	179	275	2	480	375	0	20	50

Cycle Length: **AM** 100 **PM** 130

CHAPTER 17 - TWSC - UNSIGNALIZED INTERSECTIONS WORKSHEET

Analysis Summary

General Information

Site Information

Analyst	Nancy	Jurisdiction/Date	City of ABQ 3/2/2006
Agency or Company	Terry Brown, P.E.	Major Street	Carmel Ave
Analysis Period/Year	AM Peak Hour 2008	Minor Street	Driveway 'A'
Comment	2008 AM Peak BUILD Conditions-Case A (w/o RI-RO drive)		

Input Data

Lane Configuration	EB			WB			NB			SB		
Lane 1 (curb)	TR			LT			LR					
Lane 2												
Lane 3												
Lane 4												
Lane 5												
	EB			WB			NB			SB		
Movement	1 (LT)	2 (TH)	3 (RT)	4 (LT)	5 (TH)	6 (RT)	7 (LT)	8 (TH)	9 (RT)	10 (LT)	11 (TH)	12 (RT)
Volume (veh/h)		51	12	22	100		8		16			
PHF		0.71	0.71	0.71	0.71		0.85		0.85			
Percent of heavy vehicles, HV		3	3	3	3		3		3			
Flow rate		72	17	31	141		9		19			
Flare storage (# of vehs)												
Median storage (# of vehs)							1					
Signal upstream of Movement 2				Movement 5								
Length of study period (h)	0.25											

Output Data

	Lane	Movement	Flow Rate (veh/h)	Capacity (veh/h)	v/c	Queue Length (veh)	Control Delay (s)	LOS	Approach Delay and LOS
NB	1	LR	28	869	0.032	0	9.3	A	9.3
	2								A
	3								
SB	1								
	2								
	3								
EB	①								
WB	④		31	1501	0.021	0	7.4	A	

HiCAP™ 2.0.0.1
©Catalina Engineering, Inc.

2 - 2A_08ABX
1 of 1

CHAPTER 17 - TWSC - UNSIGNALIZED INTERSECTIONS WORKSHEET

Analysis Summary

General Information

Analyst Nancy
 Agency or Company Terry Brown, P.E.
 Analysis Period/Year PM Peak Hour 2008
 Comment 2008 PM Peak BUILD Conditions-Case A (w/o RI-RO drive)

Site Information

Jurisdiction/Date City of ABQ 3/2/2006
 Major Street Carmel Ave
 Minor Street Driveway 'A'

Input Data

Lane Configuration	EB			WB			NB			SB		
Lane 1 (curb)	TR			LT			LR					
Lane 2												
Lane 3												
Lane 4												
Lane 5												
	EB			WB			NB			SB		
Movement	1 (LT)	2 (TH)	3 (RT)	4 (LT)	5 (TH)	6 (RT)	7 (LT)	8 (TH)	9 (RT)	10 (LT)	11 (TH)	12 (RT)
Volume (veh/h)		152	26	51	174		26		51			
PHF		0.72	0.72	0.72	0.72		0.85		0.85			
Percent of heavy vehicles, HV		3	3	3	3		3		3			
Flow rate		211	36	71	242		31		60			
Flare storage (# of vehs)												
Median storage (# of vehs)							1					
Signal upstream of Movement 2				ft			Movement 5			ft		
Length of study period (h)	0.25											

Output Data

	Lane	Movement	Flow Rate (veh/h)	Capacity (veh/h)	v/c	Queue Length (veh)	Control Delay (s)	LOS	Approach Delay and LOS
NB	1	LR	91	679	0.134	0	11.1	B	11.1
	2								B
	3								
SB	1								
	2								
	3								
EB	①								
WB	④		71	1313	0.054	0	7.9	A	

2008 Peak Hour Existing Conditions

Case B – with RI-RO driveway

Bank of Albuquerque


(Carmel Ave / Wyoming Blvd)

Trip Assignments (% Entering)

Case B - with RI-RO driveway



NTS



SIGNALIZED INTERSECTION



UNSIGNALIZED INTERSECTION

Terry O. Brown, P.E.

P.O. Box 92051

Albuquerque, NM 87199-2051

(505)883-8807 (Voice)

(505)212-0267 (Fax)



Bank of Albuquerque


(Carmel Ave / Wyoming Blvd)

Trip Assignments (% Exiting)

Case B - with RI-RO driveway



NTS



SIGNALIZED INTERSECTION



UNSIGNALIZED INTERSECTION

Terry O. Brown, P.E.

P.O. Box 92051

Albuquerque, NM 87199-2051

(505)883-8807 (Voice)

(505)212-0267 (Fax)



Bank of Albuquerque (Carmel Ave / Wyoming Blvd)

Projected Turning Movements SUMMARY

PROPOSED DEVELOPMENT (2008) - 100% Development

Case B - with RI-RO driveway

INTERSECTION: Summary

Carmel Ave / Wyoming Blvd		0.71			0.95			0.86			0.87			PHF
(1)		Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)			
	3.0% Truck	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
Existing (2006)		15	21	12	144	48	84	33	443	45	96	671	13	
2008 (NO BUILD - A.M.)		16	22	13	153	51	89	35	470	48	102	711	14	
2008 (BUILD - A.M.)		19	24	15	154	52	89	50	470	48	102	714	15	

	0.72			0.88			0.95			0.95			PHF
	Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)			
	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
Existing (2006)	30	87	26	247	42	127	113	731	72	169	453	9	
2008 (NO BUILD - P.M.)	32	92	28	262	45	135	120	775	76	179	480	10	
2008 (BUILD - P.M.)	42	99	35	265	48	135	154	775	76	179	488	12	

Carmel Ave / Driveway 'A'		0.71			0.71			0.85			0.85			PHF
(2)		Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')			
	3.0% Truck	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
Existing (2006)		0	48	0	0	94	0	0	0	0	0	0	0	0
2008 (NO BUILD - A.M.)		0	51	0	0	100	0	0	0	0	0	0	0	0
2008 (BUILD - A.M.)		0	51	12	17	100	0	8	0	7	0	0	0	0

			0.72			0.72			0.85			0.85	PHF	
			Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
			Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Existing (2006)			0	143	0	0	164	0	0	0	0	0	0	0
2008 (NO BUILD - P.M.)			0	152	0	0	174	0	0	0	0	0	0	0
2008 (BUILD - P.M.)			0	152	26	40	174	0	26	0	24	0	0	0

Driveway 'B' / Wyoming Blvd		0.85			0.85			0.86			0.86			PHF
(3)		Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)			
	3.0% Truck	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
Existing (2006)		0	0	0	0	0	0	0	521	0	0	827	0	
2008 (NO BUILD - A.M.)		0	0	0	0	0	0	0	552	0	0	877	0	
2008 (BUILD - A.M.)		0	0	8	0	0	0	0	567	0	0	879	5	

	0.85			0.85			0.95			0.95			PHF
	Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)			
	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	
Existing (2006)	0	0	0	0	0	0	0	916	0	0	726	0	
2008 (NO BUILD - P.M.)	0	0	0	0	0	0	0	971	0	0	770	0	
2008 (BUILD - P.M.)	0	0	27	0	0	0	0	1,005	0	0	777	11	

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
 Projected Turning Movements Worksheet
Carmel Ave / Wyoming Blvd

Case B - with RI-RO driveway
 (1)

INTERSECTION:

E-W Street: **Carmel Ave**
 N-S Street: **Wyoming Blvd**

Year of Existing Counts: 2006
 Implementation Year: 2008

Growth Rates

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - A.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total AM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
15	21	12	144	48	84	33	443	45	96	671	13
1	1	1	9	3	5	2	27	3	6	40	1
16	22	13	153	51	89	35	470	48	102	711	14
16	22	13	153	51	89	35	470	48	102	711	14
0.00%	0.00%	0.00%	4.40%	4.33%	0.00%	44.09%	0.00%	0.00%	0.00%	10.00%	3.03%
13.03%	8.73%	9.09%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
3	2	2	1	1	0	15	0	0	0	3	1
19	24	15	154	52	89	50	470	48	102	714	15

Existing Volumes

Background Traffic Growth

Subtotal

Subtotal (NO BUILD - P.M.)

Percent Commercial Trips Generated(Entering)

Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total PM Peak Hour BUILD Volumes

Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
30	87	26	247	42	127	113	731	72	169	453	9
2	5	2	15	3	8	7	44	4	10	27	1
32	92	28	262	45	135	120	775	76	179	480	10
32	92	28	262	45	135	120	775	76	179	480	10
0.00%	0.00%	0.00%	4.40%	4.33%	0.00%	44.09%	0.00%	0.00%	0.00%	10.00%	3.03%
13.03%	8.73%	9.09%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
10	7	7	3	3	0	34	0	0	0	8	2
42	99	35	265	48	135	154	775	76	179	488	12

Number of Commercial Trips Generated


Entering Exiting
 34 24 A.M. 100% Commercial Development
 77 77 P.M.

2006 AM Peak Hr. Volumes


2006 PM Peak Hr. Volumes

Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
15	21	12	144	48	84	33	443	45	96	671	13
30	87	26	247	42	127	113	731	72	169	453	9

2008
BUILD




Trips



Carmel Ave / Wyoming Blvd

2008
NO BUILD



Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
 Projected Turning Movements Worksheet
Carmel Ave / Driveway 'A'

Case B - with RI-RO driveway

(2)

INTERSECTION:

E-W Street: **Carmel Ave**
 N-S Street: **Driveway 'A'**

Year of Existing Counts: 2006
 Implementation Year: 2008

Growth Rates

Existing Volumes
 Background Traffic Growth
 Subtotal

Subtotal (NO BUILD - A.M.)

Percent Commercial Trips Generated(Entering)
 Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total AM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	48	0	0	94	0	0	0	0	0	0	0
0	3	0	0	6	0	0	0	0	0	0	0
0	51	0	0	100	0	0	0	0	0	0	0
0	51	0	0	100	0	0	0	0	0	0	0
0.00%	0.00%	34.15%	51.45%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	34.15%	0.00%	30.85%	0.00%	0.00%	0.00%
0	0	12	17	0	0	8	0	7	0	0	0
0	51	12	17	100	0	8	0	7	0	0	0

Existing Volumes
 Background Traffic Growth
 Subtotal

Subtotal (NO BUILD - P.M.)

Percent Commercial Trips Generated(Entering)
 Percent Commercial Trips Generated(Exiting)

Total Trips Generated

Total PM Peak Hour BUILD Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	143	0	0	164	0	0	0	0	0	0	0
0	9	0	0	10	0	0	0	0	0	0	0
0	152	0	0	174	0	0	0	0	0	0	0
0	152	0	0	174	0	0	0	0	0	0	0
0.00%	0.00%	34.15%	51.45%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%
0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	34.15%	0.00%	30.85%	0.00%	0.00%	0.00%
0	0	26	40	0	0	26	0	24	0	0	0
0	152	26	40	174	0	26	0	24	0	0	0

Number of Commercial Trips Generated

Entering: 34 A.M.
 Exiting: 24 P.M.
 77 77
 100% Commercial Development




2006 AM Peak Hr. Volumes
 2006 PM Peak Hr. Volumes

3.00%			3.00%			3.00%			3.00%		
Eastbound (Carmel Ave)			Westbound (Carmel Ave)			Northbound (Driveway 'A')			Southbound (Driveway 'A')		
Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
0	48	0	0	94	0	0	0	0	0	0	0
0	143	0	0	164	0	0	0	0	0	0	0

2008
BUILD

Trips

2008
NO BUILD



Carmel Ave / Driveway 'A'

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
 Projected Turning Movements Worksheet
Driveway 'B' / Wyoming Blvd

Case B - with RI-RO driveway

(3)

INTERSECTION:

E-W Street: **Driveway 'B'**
 N-S Street: **Wyoming Blvd**

Year of Existing Counts: 2006
 Implementation Year: 2008

Growth Rates

	3.00%			3.00%			3.00%			3.00%		
	Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Existing Volumes	0	0	0	0	0	0	0	521	0	0	827	0
Background Traffic Growth	0	0	0	0	0	0	0	31	0	0	50	0
Subtotal	0	0	0	0	0	0	0	552	0	0	877	0
Subtotal (NO BUILD - A.M.)	0	0	0	0	0	0	0	552	0	0	877	0
Percent Commercial Trips Generated(Entering)	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	44.09%	0.00%	0.00%	0.00%	14.40%
Percent Commercial Trips Generated(Exiting)	0.00%	0.00%	35.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	9.09%	0.00%
Total Trips Generated	0	0	8	0	0	0	0	15	0	0	2	5
Total AM Peak Hour BUILD Volumes	0	0	8	0	0	0	0	567	0	0	879	5


	Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
Existing Volumes	0	0	0	0	0	0	0	916	0	0	726	0
Background Traffic Growth	0	0	0	0	0	0	0	55	0	0	44	0
Subtotal	0	0	0	0	0	0	0	971	0	0	770	0
Subtotal (NO BUILD - P.M.)	0	0	0	0	0	0	0	971	0	0	770	0
Percent Commercial Trips Generated(Entering)	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	44.09%	0.00%	0.00%	0.00%	14.40%
Percent Commercial Trips Generated(Exiting)	0.00%	0.00%	35.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	0.00%	9.09%	0.00%
Total Trips Generated	0	0	27	0	0	0	0	34	0	0	7	11
Total PM Peak Hour BUILD Volumes	0	0	27	0	0	0	0	1,005	0	0	777	11

Number of Commercial Trips Generated


Entering	34	24	A.M.	100% Commercial Development
Exiting	77	77	P.M.	

	Eastbound (Driveway 'B')			Westbound (Driveway 'B')			Northbound (Wyoming Blvd)			Southbound (Wyoming Blvd)		
	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right	Left	Thru	Right
2006 AM Peak Hr. Volumes	0	0	0	0	0	0	0	521	0	0	827	0
2006 PM Peak Hr. Volumes	0	0	0	0	0	0	0	916	0	0	726	0


2008
BUILD



Trips




2008
NO BUILD




Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Analysis of Carmel Ave / Wyoming Blvd - [1B_08ABX]
2008 AM Peak BUILD Conditions-Case B (with RT-RO drive)

03/19/06
15:36:17

SIGNAL 2000/TEAPAC (Ver 2.70.07) - HCM Input Worksheet



	SB	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT
Heavy veh, %HV	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
PK-hr fact, PHF	.87	.87	.87	.95	.95	.95	.86	.86	.86	.71	.71	.71	.71	.71	.71
Pretimed or Act	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A
Startup lost, l1	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Ext eff gm, e	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Arrival typ, AT	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Ped vol, vped	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bike vol, vbic	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Parking locatns	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Park mnvrs, Nm	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bus stops, NB	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Grade, %G	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0




C=100"	G= 74.0"	G= 16.0"	G= 0.0"	G= 0.0"	G= 0.0"	G= 0.0"
	Y+R= 5.0"	Y+R= 5.0"	Y+R= 0.0"	Y+R= 0.0"	Y+R= 0.0"	Y+R= 0.0"
	G= 0.0"	G= 0.0"	G= 0.0"	G= 0.0"	G= 0.0"	G= 0.0"
	Y+R= 0.0"	Y+R= 0.0"	Y+R= 0.0"	Y+R= 0.0"	Y+R= 0.0"	Y+R= 0.0"

Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Analysis of Carmel Ave / Wyoming Blvd - [1B_08ABX]
2008 AM Peak BUILD Conditions-Case B (with RT-RO drive)

03/19/06
15:36:17

SIGNAL 2000/TEAPAC (Ver 2.70.07) - Capacity Analysis Summary

Intersection Averages for Int # 1 -
Degree of Saturation (v/c) 0.31 Vehicle Delay 12.2 Level of Service B+



C=100 sec G= 90.0 sec = 90.0% Y=10.0 sec = 10.0% Ped= 0.0 sec = 0.0%

Lane Group	Width/Lanes	g/c	Reqd	Used	Service Rate @D (vph) @E	Adj Volume	V/c	HCM Delay	Queue Model 1
------------	-------------	-----	------	------	--------------------------	------------	-----	-----------	---------------

SB Approach

RT+TH	24/2	0.253	0.740	0.740	2592	838	0.323	4.5	*A
LT	12/1	0.202	0.740	0.740	575	117	0.203	4.1	A

NB Approach

RT+TH	24/2	0.193	0.740	0.740	2564	603	0.235	4.1	A
LT	12/1	0.151	0.740	0.740	438	58	0.132	3.9	A

WB Approach

RT	12/1	0.090	0.160	0.160	196	233	0.376	38.5	D+
TH	12/1	0.051	0.160	0.160	237	280	0.186	36.7	D+
LT	12/1	0.160	0.160	0.160	163	195	0.761	55.0	*D

EB Approach

RT+TH	12/1	0.054	0.160	0.160	221	262	0.198	36.8	D+
LT	12/1	0.000	0.160	0.160	163	195	0.127	36.3	D+


Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Analysis of Carmel Ave / Wyoming Blvd - [1B_08PBX]
2008 PM Peak BUILD Conditions-Case A (w/o RT-RO drive)

03/19/06
15:37:18

SIGNAL2000/TEAPAC Ver 2.70.071 - HCM Input Worksheet

Intersection # 1 -

Area Location Type: NONCBD



	SB	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT	RT	TH	LT
Heavy veh, %HV	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0	3.0
Pk-hr fact, PHF	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95
Prelim or Act	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A	A
Strup lost, l1	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Ext eff grn, e	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Arrival typ, AT	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3
Ped vol, vped	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bike vol, vbic	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Parking locatns	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO	NO
Park mnvrs, Nm	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Bus stops, NB	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Grade, %G	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0	.0

Sq 11 LD/LD	Phase 1	Phase 2	Phase 3	Phase 4	Phase 5	Phase 6
C=100"	G= 58.2" Y+R= 5.0"	G= 31.8" Y+R= 5.0"	G= 0.0" Y+R= 0.0"	G= 0.0" Y+R= 0.0"	G= 0.0" Y+R= 0.0"	G= 0.0" Y+R= 0.0"


Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
Analysis of Carmel Ave / Wyoming Blvd - [1B_08PBX]
2008 PM Peak BUILD Conditions-Case A (w/o RT-RO drive)

03/19/06
15:37:18

SIGNAL2000/TEAPAC Ver 2.70.071 - Capacity/Analysis Summary

Intersection Averages for Int # 1 -

Degree of Sat (v/c) 0.44 Vehicle Delay 19.8 Level of Service B



C=100 sec G= 90.0 sec = 90.0% Y=10.0 sec = 10.0% Ped= 0.0 sec = 0.0%

Lane Group	Width/ Lanes	Reqd	g/C	Used	Service Rate @D (vph) @E	Adj Volume	v/c	HCM Delay	Queue Model 1
------------	-----------------	------	-----	------	-----------------------------	---------------	-----	--------------	------------------

SB Approach

RT+TH LT	24/2 12/1	0.171 0.441	0.582 0.582	2035 265	2035 284	527 188	0.259 0.662	10.4 19.9	B+ *B
-------------	--------------	----------------	----------------	-------------	-------------	------------	----------------	--------------	----------

NB Approach

RT+TH LT	24/2 12/1	0.271 0.251	0.582 0.582	2015 456	2015 468	896 162	0.445 0.346	12.0 11.4	B+ B+
-------------	--------------	----------------	----------------	-------------	-------------	------------	----------------	--------------	----------

WB Approach

RT TH	12/1 12/1	0.132 0.051	0.318 0.318	459 548	499 587	153 55	0.307 0.094	26.1 24.0	C+ *C+
----------	--------------	----------------	----------------	------------	------------	-----------	----------------	--------------	-----------

EB Approach

RT+TH LT	12/1 12/1	0.138 0.073	0.318 0.318	525 384	564 424	187 58	0.332 0.137	26.3 24.4	C+ C+
-------------	--------------	----------------	----------------	------------	------------	-----------	----------------	--------------	----------

Queueing Analysis Summary Sheet

Project: Bank of Albuquerque (Carmel Ave / Wyoming Blvd)
 Intersection: Carmel Ave / Wyoming Blvd

CASE "B"

2008

Eastbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	15	200	1	15	200	1	21	Cont	0	12	0
AM NO BUILD Queue	1	16	50	1	16	50	1	22	50	0	13	50
AM BUILD Queue	1	19	50	1	19	50	1	24	50	0	15	50
Existing Lane Length	1	30	200	1	30	200	1	87	Cont	0	26	0
PM NO BUILD Queue	1	32	75	1	32	75	1	92	175	0	28	75
PM BUILD Queue	1	42	100	1	42	100	1	99	175	0	35	75

Westbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	144	190	1	144	190	1	48	Cont	1	84	0
AM NO BUILD Queue	1	153	200	1	153	200	1	51	100	1	89	125
AM BUILD Queue	1	154	200	1	154	200	1	52	100	1	89	125
Existing Lane Length	1	247	190	1	247	190	1	42	Cont	1	127	0
PM NO BUILD Queue	1	262	375	1	262	375	1	45	100	1	135	225
PM BUILD Queue	1	265	375	1	265	375	1	48	100	1	135	225

Northbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	33	250	1	33	250	2	443	Cont	0	45	0
AM NO BUILD Queue	1	35	75	1	35	75	2	470	300	0	48	75
AM BUILD Queue	1	50	100	1	50	100	2	470	300	0	48	75
Existing Lane Length	1	113	250	1	113	250	2	731	Cont	0	72	0
PM NO BUILD Queue	1	120	200	1	120	200	2	775	550	0	76	150
PM BUILD Queue	1	154	250	1	154	250	2	775	550	0	76	150

Southbound				Left Turns			Thru Movements			Right Turns		
Approach	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)	# Lanes	Vol.	Length (Ft.)
Existing Lane Length	1	96	N/A	1	96	N/A	2	671	Cont	0	13	0
AM NO BUILD Queue	1	102	150	1	102	150	2	711	425	0	14	50
AM BUILD Queue	1	102	150	1	102	150	2	714	425	0	15	50
Existing Lane Length	1	169	N/A	1	169	N/A	2	453	Cont	0	9	0
PM NO BUILD Queue	1	179	275	1	179	275	2	480	375	0	10	50
PM BUILD Queue	1	179	275	1	179	275	2	488	375	0	12	50

Cycle Length: **AM** 100 **PM** 130

CHAPTER 17 - TWSC - UNSIGNALIZED INTERSECTIONS WORKSHEET

Analysis Summary

General Information

Analyst Nancy
 Agency or Company Terry Brown, P.E.
 Analysis Period/Year AM Peak Hour 2008
 Comment 2008 AM Peak BUILD Conditions-Case B (with RI-RO drive)

Site Information

Jurisdiction/Date City of ABQ 3/19/2006
 Major Street Carmel Ave
 Minor Street Driveway 'A'

Input Data

Lane Configuration	EB			WB			NB			SB		
Lane 1 (curb)	TR			LT			LR					
Lane 2												
Lane 3												
Lane 4												
Lane 5												
	EB			WB			NB			SB		
Movement	1 (LT)	2 (TH)	3 (RT)	4 (LT)	5 (TH)	6 (RT)	7 (LT)	8 (TH)	9 (RT)	10 (LT)	11 (TH)	12 (RT)
Volume (veh/h)		51	12	17	100		8		7			
PHF		0.71	0.71	0.71	0.71		0.85		0.85			
Percent of heavy vehicles, HV		3	3	3	3		3		3			
Flow rate		72	17	24	141		9		8			
Flare storage (# of vehs)												
Median storage (# of vehs)							1					
Signal upstream of Movement 2												
Length of study period (h)	0.25											

Output Data

	Lane	Movement	Flow Rate (veh/h)	Capacity (veh/h)	v/c	Queue Length (veh)	Control Delay (s)	LOS	Approach Delay and LOS
NB	1	LR	17	820	0.021	0	9.5	A	9.5 A
	2								
	3								
SB	1								
	2								
	3								
EB	①								
WB	④		24	1501	0.016	0	7.4	A	

CHAPTER 17 - TWSC - UNSIGNALIZED INTERSECTIONS WORKSHEET

Analysis Summary

General Information

Analyst Nancy
 Agency or Company Terry Brown, P.E.
 Analysis Period/Year PM Peak Hour 2008
 Comment 2008 PM Peak BUILD Conditions-Case B (with RI-RO drive)

Site Information

Jurisdiction/Date City of ABQ 3/19/2006
 Major Street Carmel Ave
 Minor Street Driveway 'A'

Input Data

Lane Configuration	EB			WB			NB			SB		
Lane 1 (curb)	TR			LT			LR					
Lane 2												
Lane 3												
Lane 4												
Lane 5												
	EB			WB			NB			SB		
Movement	1 (LT)	2 (TH)	3 (RT)	4 (LT)	5 (TH)	6 (RT)	7 (LT)	8 (TH)	9 (RT)	10 (LT)	11 (TH)	12 (RT)
Volume (veh/h)		152	26	40	174		26		24			
PHF		0.72	0.72	0.72	0.72		0.85		0.85			
Percent of heavy vehicles, HV		3	3	3	3		3		3			
Flow rate		211	36	56	242		31		28			
Flare storage (# of vehs)												
Median storage (# of vehs)							1					
Signal upstream of Movement 2												
Length of study period (h)	0.25											

Output Data

	Lane	Movement	Flow Rate (veh/h)	Capacity (veh/h)	v/c	Queue Length (veh)	Control Delay (s)	LOS	Approach Delay and LOS
NB	1	LR	59	640	0.092	0	11.2	B	11.2
	2								B
	3								
SB	1								
	2								
	3								
EB	①								
WB	④		56	1313	0.042	0	7.9	A	

CHAPTER 17 - TWSC - UNSIGNALIZED INTERSECTIONS WORKSHEET

Analysis Summary

General Information

Analyst Nancy
 Agency or Company Terry Brown, P.E.
 Analysis Period/Year AM Peak Hour 2008
 Comment 2008 AM Peak BUILD Conditions-Case B (with RI-RO drive)

Site Information

Jurisdiction/Date City of ABQ 3/19/2006
 Major Street Wyoming Blvd
 Minor Street Driveway 'B'

Input Data

Lane Configuration	NB			SB			WB			EB		
Lane 1 (curb)	T			TR						R		
Lane 2	T			T								
Lane 3												
Lane 4												
Lane 5												
Movement	1 (LT)	2 (TH)	3 (RT)	4 (LT)	5 (TH)	6 (RT)	7 (LT)	8 (TH)	9 (RT)	10 (LT)	11 (TH)	12 (RT)
Volume (veh/h)		567			879	5						8
PHF		0.86			0.86	0.86						0.85
Percent of heavy vehicles, HV		3			3	3						3
Flow rate		659			1022	6						9
Flare storage (# of vehs)												
Median storage (# of vehs)										1		
Signal upstream of Movement 2												
Length of study period (h)	0.25											

Output Data

	Lane	Movement	Flow Rate (veh/h)	Capacity (veh/h)	v/c	Queue Length (veh)	Control Delay (s)	LOS	Approach Delay and LOS
WB	1								
	2								
	3								
EB	1	R	9	503	0.018	0	12.3	B	12.3
	2								B
	3								
NB	①								
SB	④								

CHAPTER 17 - TWSC - UNSIGNALIZED INTERSECTIONS WORKSHEET

Analysis Summary

General Information

Analyst Nancy
 Agency or Company Terry Brown, P.E.
 Analysis Period/Year PM Peak Hour 2008
 Comment 2008 PM Peak BUILD Conditions-Case B (with RI-RO drive)

Site Information

Jurisdiction/Date City of ABQ 3/19/2006
 Major Street Wyoming Blvd
 Minor Street Driveway 'B'

Input Data

Lane Configuration	NB			SB			WB			EB		
Lane 1 (curb)	T			TR						R		
Lane 2	T			T								
Lane 3												
Lane 4												
Lane 5												
	NB			SB			WB			EB		
Movement	1 (LT)	2 (TH)	3 (RT)	4 (LT)	5 (TH)	6 (RT)	7 (LT)	8 (TH)	9 (RT)	10 (LT)	11 (TH)	12 (RT)
Volume (veh/h)		1005			777	11						27
PHF		0.95			0.95	0.95						0.85
Percent of heavy vehicles, HV		3			3	3						3
Flow rate		1058			818	12						32
Flare storage (# of vehs)												
Median storage (# of vehs)										1		
Signal upstream of Movement 2												
Length of study period (h)	0.25											

Output Data

	Lane	Movement	Flow Rate (veh/h)	Capacity (veh/h)	v/c	Queue Length (veh)	Control Delay (s)	LOS	Approach Delay and LOS
WB	1								
	2								
	3								
EB	1	R	32	584	0.055	0	11.5	B	11.5
	2								B
	3								
NB	①								
SB	④								

HiCAP™ 2.0.0.1
 ©Catalina Engineering, Inc.

3 - 3B_08PBX
 1 of 1

Traffic Count Data Sheet

Year Counts Taken: 2006 Bank of Albuquerque
 E-W Street Carmel Speed Limit (Carmel)= 25 MPH
 N-S Street Wyoming Speed Limit (Wyoming)= 40 MPH
 Date of Count: 2/14/06
 UNSIGNALIZED

Begin Time	End Time	Eastbound (Carmel)			Westbound (Carmel)			Northbound (Wyoming)			Southbound (Wyoming)		
		L	T	R	L	T	R	L	T	R	L	T	R
7:00 AM	7:15 AM	2	2	3	30	14	17	0	131	5	16	171	4
7:15 AM	7:30 AM	5	2	4	41	6	23	3	104	7	22	168	3
7:30 AM	7:45 AM	5	9	3	34	15	24	21	120	10	28	191	4
7:45 AM	8:00 AM	3	8	2	39	13	20	9	88	23	30	141	2
8:00 AM	8:15 AM	2	9	1	44	8	17	9	85	17	29	137	2
8:15 AM	8:30 AM	3	9	2	57	9	16	14	105	15	34	98	2
8:30 AM	8:45 AM	2	4	3	56	8	7	14	70	27	24	110	3
8:45 AM	9:00 AM	11	18	11	60	0	15	9	96	21	34	142	4
AM Peak Hour Volumes		15	21	12	144	48	84	33	443	45	96	671	13
% of Total Traffic		0.9%	1.3%	0.7%	8.9%	3.0%	5.2%	2.0%	27.3%	2.8%	5.9%	41.3%	0.8%
% Directional			3.0%			17.0%			32.1%			48.0%	
AM Peak Hour Factor			0.71			0.95			0.86			0.87	

Begin Time	End Time	Eastbound (Carmel)			Westbound (Carmel)			Northbound (Wyoming)			Southbound (Wyoming)		
		L	T	R	L	T	R	L	T	R	L	T	R
4:00 PM	4:15 PM	4	10	2	73	16	16	15	157	17	38	89	0
4:15 PM	4:30 PM	8	24	7	61	11	27	25	152	25	35	118	1
4:30 PM	4:45 PM	2	9	5	59	10	37	21	127	15	39	137	3
4:45 PM	5:00 PM	3	21	7	41	16	30	26	191	23	39	125	2
5:00 PM	5:15 PM	12	19	4	77	6	35	27	171	21	51	104	3
5:15 PM	5:30 PM	5	21	1	77	6	35	24	183	16	45	110	2
5:30 PM	5:45 PM	10	26	14	52	14	27	36	186	12	34	114	2
5:45 PM	6:00 PM	6	17	2	65	10	42	29	182	20	48	93	2
PM Peak Hour Volumes		30	87	26	247	42	127	113	731	72	169	453	9
% of Total Traffic		1.4%	4.1%	1.2%	11.7%	2.0%	6.0%	5.4%	34.7%	3.4%	8.0%	21.5%	0.4%
% Directional			6.8%			19.8%			43.5%			30.0%	
PM Peak Hour Factor			0.72			0.88			0.95			0.95	

Intersection Data SheetIntersection: **Carmel Ave / Wyoming Blvd**Posted Speed Limit (E-W Street): 30E / 25WDate: 3/1/2006**Eastbound Approach:** **Carmel Ave**

Left Turn Lanes	Thru/Left Lanes	Thru Lanes	Thru/Right Lanes	Right Turn Lanes
1	0	0	1	0

Length: 175'

Length:

Left Turn Arrow?	Thru Green?	Right Turn Arrow?
N	Y	N

Is there a right turn slip lane that by-passes the traffic signal?

No

Westbound Approach: **Carmel Ave**

Left Turn Lanes	Thru/Left Lanes	Thru Lanes	Thru/Right Lanes	Right Turn Lanes
1	0	1	0	1

Length: 190'

Length:

Left Turn Arrow?	Thru Green?	Right Turn Arrow?
N	Y	N

Is there a right turn slip lane that by-passes the traffic signal?

No

Posted Speed Limit (N-S Street): 40**Northbound Approach:** **Wyoming Blvd**

Left Turn Lanes	Thru/Left Lanes	Thru Lanes	Thru/Right Lanes	Right Turn Lanes
1	0	1	1	0

Length:

Length:

Left Turn Arrow?	Thru Green?	Right Turn Arrow?
N	Y	N

Is there a right turn slip lane that by-passes the traffic signal?

No

Southbound Approach: **Wyoming Blvd**

Left Turn Lanes	Thru/Left Lanes	Thru Lanes	Thru/Right Lanes	Right Turn Lanes
1	0	1	1	0

Length:

Length:

Left Turn Arrow?	Thru Green?	Right Turn Arrow?
N	Y	N

Is there a right turn slip lane that by-passes the traffic signal?

No