



GENERAL NOTES

1. SEE SHEETS C12 AND C13 FOR MORE TEMPORARY BYPASS DETAILS

WYOMING AND EAGLE ROCK LIMITS OF PAVEMENT REMOVAL

NUMBERED NOTES

1 SOIL CEMENT BERM TOE OF SLOPE-APPROXIMATE

2 REMOVE AND DISPOSE ~800 CY GROUTED RIP RAP NOTE: MAY DISPOSE OF CLEAN RIP RAP TO AMAFCA AT NORTH DOMINGO BACA DAM

3 REMOVE AND SALVAGE TO AMAFCA 15 LF OF GUARD RAIL

4 REMOVE AND SALVAGE TO AMAFCA 118' PIPE FENCE/GATE

5 SOIL CEMENT BERM, SEE SECTION D ON C11 FOR SOIL CEMENT BERM REMOVAL (PARTIAL).

6 REMOVE AND DISPOSE OF PIPE RAIL

7 REMOVE EXISTING ELM TREES

8 CLEAR & GRUB AND REVEGETATE

9 REMOVE SOIL CEMENT CHANNEL LINING & REVEGETATE

10 SAW CUT 2.5 FEET OF SILL WALL AND REMOVE. REATTACH PIPE RAIL TO NEW SILL WALL, AND SUPPORT RAIL DURING CONSTRUCTION. COST INCIDENTAL TO CHANNEL LINING CONSTRUCTION

11 EXISTING CUTT-OFF WALL TO BE REMOVED

12 REMOVE AND REPLACE LANDSCAPING AS NECESSARY, COST INCIDENTAL TO CLEARING AND GRUBBING

13 SWALE, GRADE TO DRAIN

14 REMOVE 150 FT OF 3' CUTOFF WALL BOTH LT AND RT CENTERED ON ARROYO

AS-BUILT INFORMATION

CONTRACTOR	DATE

BENCH MARKS

CONTRACTOR	DATE

SURVEY INFORMATION

DATE	BY

FIELD NOTES

NO.	BY

ENGINEER'S SEAL

REVISIONS

No.	Date	By	REMARKS

Designed By: MDS DATE: 08/2007
Drawn By: RAO, MDS DATE: 08/2007
Checked By: EVD DATE: 08/2007

Resource Technology, Inc.

Civil Engineering 5501 Jefferson Blvd. NE, Suite 200
Environmental Sciences Albuquerque, New Mexico 87109
Water Resources E-mail: rti@nm.net
Landscape Architecture Telephone: (505) 243-7300
Planning Facsimile: (505) 243-7400

CITY OF ALBUQUERQUE
DEPARTMENT OF MUNICIPAL DEVELOPMENT

LA CUEVA ARROYO DIP REPLACEMENT
GRADING, DEMOLITION & CONSTRUCTION LIMITS

Design Review Committee **APPROVED** OCT 17 2007 DESIGN REVIEW COMMITTEE

City Engineer Approval **APPROVED** OCT 17 2007 CITY ENGINEER

City Project No. 7848.02 Zone Map No. C-19 Sheet C4 Of 25