



Environmental Health Department - Air Quality Program
Physical Address: One Civic Plaza NW, 3rd Floor, Room 3047, Albuquerque, New Mexico 87102
Mailing Address: P.O. Box 1293, Albuquerque, New Mexico 87103
(505) 768 - 1972 (Voice) 1-800-659-8331 (New Mexico Relay) (505) 768 - 1977 (Fax)



Application for a
Fugitive Dust Control Programmatic Permit
for Routine Surface Disturbance within Bernalillo County

Albuquerque - Bernalillo County Air Quality Control Board Regulation 20.11.20 NMAC

Effective Date of this Application Form: **01/01/2020**

Department Use Only

Submittal Date: 5/22/2020

Received by: Elizabeth Pomo

Permit #: 0455-P

Program Receipt Stamp Below this Line

A Programmatic Permit is a fugitive dust control permit, valid for up to five years, issued to a Permittee that performs routine maintenance or routine active operations on land or at facilities of $\frac{1}{4}$ of an acre or more, which does not include full depth reconstruction of a roadway or substantial removal & replacement of a manmade facility.

This application shall include a Fugitive Dust Control Plan (Part B or attached alternative Plan) that may utilize reasonably available control measures to mitigate fugitive dust to meet objectives of 20.11.20 NMAC – Fugitive Dust Control.

PART A - FACILITY INFORMATION AND GENERAL ACTIVITIES

If permittee wishes to include multiple facility locations under same permit, submit required information for each individual site by submitting additional copies of Parts A, B & C, as necessary

AN 8 1/2" X 11" OR LARGER SITE MAP MUST ACCOMPANY APPLICATION FOR EACH FACILITY LOCATION

1. Fugitive Dust Facility/Site Name: Rosa Parks Rd NW & Kimmick Dr NW Stockpile
2. Street Address of Facility (if available): NW Corner of Rosa Parks Rd NW & Kimmick Dr NW
3. Nearest Major Cross Streets or Intersection to Facility: Paseo Del Norte
4. Total Acres of Facility: 13 acres
5. Total Acres of Facility Subject to Routine Maintenance/Active Operations: 10 - 13
6. Total Miles of Roads/Easements for Facility Subject to Routine Maintenance/Active Operations: 0
7. Total Miles of Roads/Easements for Facility Converted to Acres: 0
8. Description of Facility's Operation(s): Stockpile Area for Material Import/Export.
9. Describe Type of Activities at Facility That May Generate Fugitive Dust: Importing/Exporting Materials.
10. Provide name of individual to be notified of a High Wind Event who will be responsible to ensure High Wind Event control measures are started (see Part B for description):

Name: Eddie Gonzales Title: Project Manager Email Address: eddie@guzmanacs.com

Page 1 of 5 (FUGITIVE DUST CONTROL PROGRAMMATIC PERMIT APPLICATION), EFFECTIVE 01/01/20

Department Review by EP

Initials of Permittee EG

PART B – FUGITIVE DUST CONTROL PLAN

“Permittee” is required to comply with Part B, Fugitive Dust Control Plan (plan), detailing reasonably available control measures to be used to mitigate release of fugitive dust from routine active operations & maintenance.

If permittee chooses to submit, as an attachment to application, an alternative Fugitive Dust Control Plan in lieu of using any reasonably available control measures given below or from 20.11.20.23 NMAC – Fugitive Dust Control, the alternative plan (i.e. storm water pollution prevention plan) must include detailed information that addresses: 1) reasonably available control measures to mitigate release of fugitive dust from routine active operations & maintenance; & 2) action(s) to be taken to mitigate property damage (refer to Part B2 below). If submitting an alternative plan permittee must still complete Parts A, C, D & E of application.

When a **High Wind Event** is called by Department, **ALL Active Operations** capable of producing fugitive dust **MUST cease; however**, project must continue using reasonably available control measures & implement High Wind Event measures. A High Wind Event is a condition announced by Department of wind speeds of approximately 30 miles per hour that, when accompanied by dry soil conditions, is likely to result in widespread reduced visibility due to blowing fugitive dust & may result in elevated atmospheric particulate levels.

B1. Permittee shall include in permit application one or more applicable reasonably available control type measures listed below (abbreviated list), or one or more other (alternative) fugitive dust control measures, including measures taken to comply with any other statute or regulation that would also effectively control fugitive dust during routine active operations & maintenance & inactive operations. For an expanded list of control type measures, refer to 20.11.20.23 NMAC – Fugitive Dust Control.

Use underlined headings below when filling in control measures in column D of Part C Table. These measures may reduce release of fugitive dust from facility or reduce amount of acreage/miles requiring control if applied as permanent stabilization (i.e.: maintained pavement)

PAVING

- Paving using well-maintained recycled asphalt, asphaltic concrete, concrete, or petroleum products legal for such use;
- Using paved or gravel entry/exit aprons with devices, such as steel grates, capable of knocking mud & bulk material off vehicle tires;
- Surfacing with gravel or other mulch material of a size & density sufficient to prevent surface material from becoming airborne

WATERING

- Using wet suppression;
- Watering site at beginning &/or end of each day sufficient to stabilize area;
- Using dust suppressants applied in amounts, rates, & frequencies & maintained as recommended by manufacturer (submit manufacturer's data with application)

WINDBREAKS

- Installing upwind windbreaks, including fabric fences with bottom of fence sufficiently anchored to ground to prevent material from blowing underneath fence; all windbreaks & fabric fences should be maintained in an upright & functional condition at all times; all accumulated material on windward side of windbreak should be periodically removed to prevent failure of windbreak;
- Installing permanent perimeter & interior walls;
- For Salvage Yards - using salvaged vehicles arranged in rows with minimum spacing between vehicles;
- For Construction or Storage Yards – using construction materials, equipment, trailers, buildings or structures to create a windbreak;
- Using dense hedges, shrubbery or trees;
- Using sand fences, board rail fences, or similar fences that have openings on approximately 50% of surface;
- Natural barriers

TRAFFIC

- Using traffic controls, including decreased speed limits with appropriate enforcement; other traffic calming methods, vehicle access restrictions & controls; road closures or barricades; off-road vehicle access controls & closures;
- Cleaning up spillage & track out as necessary to prevent particulates from being pulverized & entrained into atmosphere;
- Performing regularly scheduled vacuum street cleaning or wet sweeping;
- Using properly secured tarps or cargo covering that covers entire surface area of load;
- Installing fencing to limit vehicle access to property

LANDSCAPING

- Reseeding using native grasses as specified in 20.11.20.24 NMAC – NATIVE GRASS SEEDING AND MULCH SPECIFICATIONS;
- Xeriscaping;
- Mulching & crimping of straw or hay as specified in 20.11.20.24 NMAC;
- Conventional landscaping techniques

B2. Summarize, in detail, how Reasonably Available Control Measures currently in place will be used to limit or prevent release of Fugitive Dust from routine active operations &/or maintenance at facility (i.e. credit can be taken for: existing trees or shrubbery along at least 50% of perimeter of facility as a windbreak; salvaged vehicles, materials, or equipment at a salvage yard that forms an effective windbreak; or existing fencing that prevents vehicle access to property as a traffic control). Describe height, length, locations, types, amounts, etc. for all methods to be used as control measures. As a general rule, Department will allow credit for windbreaks for a lateral distance equal to 10 times height of windbreak. (i.e. a 6-foot high windbreak will be credited with reducing dust emissions for a distance of 60 feet from fence:

We will reduce the speed of Heavy Equipment within site and on haul roads to minimize particulates from being pulverized and entrained into atmosphere. Will prohibit traffic in inactive areas and water as needed. Pre-wet disturbed areas with approximate 2000 gallon water truck and additional water truck will be available as backup equipment. Wet down stockpile at the end of each day when material is being hauled in/out. Maximum height of Stockpile will not exceed 15'. Track out pads will be maintained throughout any active operations.

B3. Describe in detail what High Wind Event fugitive dust control measures will be used at this facility:

We will cease all operations and wet down site.

B4. Describe action(s) to be taken to mitigate claims of property damage by fugitive dust generated at/from facility:

We will respond to reasonable claims of property damage and address accordingly.

PART C. – SOURCE CLASSIFICATION & FEE TABLE

A	B	C	D	E
Source Classification (See Definitions Below)	Acres, Rounded to Nearest Whole Number, to be Controlled for Each Source Classification (Convert Miles to Acres)	Emission Control Factor Multiplier (20.11.2.15 G. NMAC)	General Description of Reasonably Available Control Measure(s) Currently in Place or to be Used to Maintain Acreage for Each Source Classification (Refer to Part B1 for Reasonably Available Control Measures) (i.e. Traffic, Windbreaks, etc.)	Total Fee Per Classification [Column B Times (x) Column C]
LOW IMPACT PE-1901		.1		
MODERATE IMPACT PE-1902		.5		
HIGH IMPACT PE-1903	13	.9	Watering, Traffic, Landscaping	11.7
Sum of Column E				11.7
PER ACRE FEE (BASED ON 20.11.20.2.G. NMAC)				X \$148.00
ANTICIPATED ANNUAL PERMIT FEE				\$ 1,731.60

ABBREVIATED DEFINITIONS OF SOURCE CLASSIFICATIONS

NO IMPACT - active & inactive disturbed surface areas that produce virtually no fugitive dust. Such land surfaces are exempt from fugitive dust control regulation & requirements to pay fees

LOW IMPACT - active & inactive disturbed surface areas that are approximately 90% controlled

MODERATE IMPACT - active & inactive disturbed surface areas that are approximately 50% controlled

HIGH IMPACT - active & inactive disturbed surface areas that are approximately 10% controlled

Upon receipt of application, Department will review & verify information submitted. Once Department has determined application is complete, Department will sign application & return a completed copy to permittee as official permit. Subsequently, an invoice will be sent to permittee for initial payment of permit fee. Each year thereafter, Department will send an invoice for annual fees due. Application may be sent by mail to address at top of page 1 or may be hand-delivered to same address between hours of 7:00am - 4:30pm, Monday - Friday.

PART D – SIGNATURE AUTHORITY OF PERMITTEE

A "permittee" is a person, owner or operator & all legal heirs, successors, & assigns who has applied for & obtained a Fugitive Dust Control Permit approved by Department. "Permittee" agrees to take all actions required by Fugitive Dust Control Permit issued by Department to prevent a violation of 20.11.20 NMAC – Fugitive Dust Control, including stopping active operations, if necessary. **"Permittee" is responsible for complying with Fugitive Dust Control Permit, Fugitive Dust Control Plan, & all requirements of 20.11.20 NMAC - Fugitive Dust Control. Failure to comply shall be a violation of 20.11.20 NMAC – Fugitive Dust Control.**

By signing below, applicant certifies that information provided in application for a Fugitive Dust Control Programmatic Permit is true, accurate & complete, & applicant agrees to be "permittee".

Permittee shall make permit available & explain requirements of permit to appropriate employees, agents, contractors, & any other person involved in active Operations or Maintenance at facility to assist in maintaining compliance with 20.11.20 – Fugitive Dust Control.

Permittee is responsible for maintaining control measures that prevent or abate unreasonable interference with public welfare, visibility & reasonable use of property.

Permittee must initial bottom right corner of all pages to ensure that all application information provided has been reviewed.

[One Set of Signature Pages is Adequate for Multiple Facility (Site) Locations
to be Permitted Under Same Permittee & Owner]

(Complete All Applicable **Permittee** Information)

Group II V26 VC LLC

If a Business, Print Business Name

Rudy Guzman

Managing Member

Name

Title




Initials

05/27/2020
Date Signed

2400 Louisiana Blvd NE, Bldg 3

Albuquerque

NM

87105

Mailing Address

City

State

Zip Code

505-452-0663

505-459-3128

505-452-0664

Office Phone Number

Cell Phone Number

Fax Number

rudy@guzmancs.com

Email Address

PART E – FACILITY OWNER INFORMATION

If Permittee fails to comply with provisions of 20.11.20 NMAC – Fugitive Dust Control, Owner, if different from Permittee, shall be responsible for complying with Permit. If permittee fails to take all required actions to prevent a violation of 20.11.20 NMAC – Fugitive Dust Control, Owner shall be responsible to take all actions required to prevent or satisfactorily resolve a violation of 20.11.20 NMAC – Fugitive Dust Control, including stopping all active operations, if necessary. To mitigate fugitive dust, all Inactive Disturbed Surface Areas must be stabilized & maintained in stable condition by Owner, Permittee OR Person responsible for maintenance of facility. Failure to comply shall be a violation of 20.11.20 NMAC – Fugitive Dust Control.

(Complete All Applicable Owner Information)

Group II V26 VC LLC

Business Name (if applicable)

Rudy Guzman

Managing Member

Name

Title



RG

05/27/2020

Signature

Initials

Date Signed

2400 Louisiana Blvd NE, Bldg 3

Albuquerque

NM

87105

Mailing Address

City

State

Zip Code

505-452-0663

505-459-3128

505-452-0664

Work Phone

Cell Phone

Fax Number

rudy@guzmancs.com

Email Address

GENERAL PROVISIONS of 20.11.20 NMAC – Fugitive Dust Control, states that it shall be a violation of 20.11.20 NMAC to allow fugitive dust, track-out, or transported material from any active operation, open storage pile, stockpile, paved or unpaved roadway, disturbed surface area, or inactive disturbed surface area to cross or be carried beyond property line, right-of-way, easement or any other area under control of person generating or allowing fugitive dust, if fugitive dust may:



- 1) With reasonable probability injure human health or animal or plant life;
- 2) Unreasonably interfere with public welfare, visibility or reasonable use of property;
- 3) Be visible for a total of 15 minutes or more during any consecutive one-hour observation period using visible fugitive dust detection method in 20.11.20.26 (visual determination of fugitive dust emissions violations) or an equivalent method approved in writing by Department.

Pursuant to Air Quality Control Act, Chapter 74, Article 2 New Mexico Statutes Annotated 1978, as amended, Albuquerque Joint Air Quality Control Board Ordinance, 9-5-1-1 ROA 1994, Bernalillo County Joint Air Quality Control Board Ordinance, Bernalillo County Ordinance 94-5, & Albuquerque/Bernalillo County Air Quality Control Board (A/BCAQCB) Regulation Title 20, Chapter 11, Part 20, New Mexico Administrative Code (NMAC), (20.11.20 NMAC) - Fugitive Dust Control, & upon authorized signatures below, this application, together with associated drawings, plans, appended documents, other data, and any conditions attached to the Permit by the Department, will become Fugitive Dust Control Programmatic Permit.

Area Below For Department Use

If Department approval below includes approval for any bulk material stockpiles to exceed 15 feet, maximum height allowed: _____ feet

GPS Coordinates (center of operations, at least 4 decimals): N 35.178499 W -106.709130

APPLICATION REVIEWED BY:	DEEMED COMPLETE DATE	PERMIT ISSUED BY:	ISSUE DATE	EXPIRATION DATE
Elizabeth Pomo  SIGNATURE	5 / 29 /20 20	Elizabeth Pomo  SIGNATURE	5 / 29 /20 20	5 / 29 /20 25

Google Maps Rosa Parks Rd NW & Kimmick Dr NW



TOTAL ACRES OF FACILITY: 13 Acres within the indicated boundaries

Imagery ©2020 Google, Map data ©2020 200 ft