CITY OF ALBUQUERQUE

Planning Department Brennon Williams, Director



Mayor Timothy M. Keller

April 21, 2021

David Soule, P.E. Rio Grande Engineering PO Box 93924 Albuquerque, New Mexico 87199

RE: Lot 12 Block 2 Unit 22 SAD 228 6319 Camino Alto NW Volcano Cliffs Subdivision Grading and Drainage Plan Engineers Stamp Date 4/21/2021 (D10D003C12)

Mr. Soule,

PO Box 1293 Based upon the information provided in your submittal received 4/21/2021, this plan is approved for Grading Permit.

Prior to Building permit approval a Pad Certification will be required, provided by the Engineer or a registered Land Surveyor.

Albuquerque

Advise the owner contractor not to use dirt as a ramp to climb the curb, use lumber or crusher fines for this purpose.

NM 87103

Reiterate to the Owner/Contractor that a separate permit for a garden/retaining wall must be obtained with the approved G&D plan and Pad Certification. Also, if a swimming pool is to be placed the grading and drainage plan will change and will need to be resubmitted.

www.cabq.gov

Prior to Certificate of Occupancy release, Engineer Certification per the DPM checklist is required.

If you have any questions, please contact me at 924-3986 or Rudy Rael at 924-3977.

Sincerely,

Ernest Armijo, P.E. Principal Engineer, Planning Dept. Development Review Services

ALL PROPERTY	LBU	
ELC		
N.		

City of Albuquerque

Planning Department

Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (REV 6/2018)

Project Title: 6319 CAMINO ALTO NW	Building Permit	#:		gy File #:
DRB#: LOT 12 BLOCK 8				
	VOLCANO CL	IFFS UNIT 22	_	
City Address:				
Applicant:			Contact:	
Address:				
Phone#:	Fax#:		E-mail: _	
Other Contact: RIO GRANDE ENGINE	ERING		Contact:	DAVID SOULE
Address: PO BOX 93924 ALB NM			•	
Phone#: 505.321.9099	Fax#: 505.872.	0999	E-mail: ^{da}	vid@riograndeengineering.com
TYPE OF DEVELOPMENT: PLAT				
Check all that Apply:				
DEPARTMENT: <u> </u>		TYPE OF APPROVA X BUILDING PERI CERTIFICATE C	MIT APPRO	OVAL
TYPE OF SUBMITTAL:	PPLIC	PRELIMINARY SITE PLAN FOR SITE PLAN FOR FINAL PLAT AI SIA/ RELEASE O FOUNDATION H GRADING PERM SO-19 APPROV PAVING PERMI ARADING/ PAD WORK ORDER A CLOMR/LOMR FLOODPLAIN D OTHER (SPECII	R SUB'D A BLDG. PI PPROVAL OF FINANG PERMIT AN MIT APPRO AL IT APPROVAL PEVELOPM	PPROVAL ERMIT APPROVAL CIAL GUARANTEE PPROVAL OVAL VAL CATION
DATE SUBMITTED:	By:	<u>.</u>		
COA STAFF:	ELECTRONIC SUBN	IITTAL RECEIVED:		

Weighted E Method														
												100-Year	r, 6-hr.	24 hour
Basin	Area	Area	Treat	ment A	Treat	ment B	Treat	ment C	Treatr	nent D	Weighted E	Volume	Flow	Volume
	(sf)	(acres)	%	(acres)	%	(acres)	%	(acres)	%	(acres)	(ac-ft)	(ac-ft)	cfs	(ac-ft)
ALLOWED	12707.00	0.292	0%	0	20%	0.058	46%	0.1342	34%	0.099	1.259	0.031	0.94	0.034
PROPOSED	12707.00	0.292	0%	0	20%	0.058	36%	0.105	44%	0.128	1.357	0.033	0.98	0.038
COMPARISON												0.002		0.004

Equations:

Weighted E = Ea*Aa + Eb*Ab + Ec*Ac + Ed*Ad / (Total Area)


Volume = Weighted D * Total Area

Flow = Qa * Aa + Qb * Ab + Qc * Ac + Qd * Ad

Where for 100-year, 6-ho	ur storm- zone 1	
•	Ea= 0.44	Qa= 1.29
	Eb= 0.67	Qb= 2.03
	Ec= 0.99	Qc= 2.87
	Ed= 1.97	Qd= 4.37
ONSITE Conditons DRAINAGE SUMMARY		
	REQUIRED	PROVIDED
	(CF)	(CF)
WATER QUALITY	0	198
FLOOD CONTROL	152	198

Narrative

This site is within the SAD 228 Master Drainage plan boundaries. The site is to maintain existing patterns and drain to the roadway to the east per the master drainage plan. The site does exceed the SAD 228 developed conditions assumptions, therefore ponding of 152 CF is required. The pad is elevated to accommodate shallow rock. location to the northwest minor upland flow enters the site and is allowed to pass thru. This plan is in conformance to the master drainage plan



CAUTION:

EXISTING UTILITIES ARE NOT SHOWN. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT ALL NECESSARY FIELD INVESTIGATIONS PRIOR TO ANY EXCAVATION TO DETERMINE THE ACTUAL LOCATION OF UTILITIES & OTHER IMPROVEMENTS.

EROSION CONTROL NOTES:


1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A TOPSOIL DISTURBANCE PERMIT PRIOR TO BEGINNING WORK.

2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RUN-OFF ON SITE DURING CONSTRUCTION.

3. CONTRACTOR IS RESPONSIBLE FOR CLEANING ALL SEDIMENT THAT GETS INTO EXISTING RIGHT-OF-WAY.

4. REPAIR OF DAMAGED FACILITIES AND CLEANUP OF SEDIMENT ACCUMULATIONS ON ADJACENT PROPERTIES AND IN PUBLIC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR.

5. ALL EXPOSED EARTH SURFACES MUST BE PROTECTED FROM WIND AND WATER EROSION PRIOR TO FINAL ACCEPTANCE OF ANY PROJECT.



PO BOX 93924 ALBUQUERQUE, NM 87199 (505) 321-9099

JOB #

× PK TBM 5330.56

<u>PROJECT B.M.</u> ELEV. = 5330.56'

Ē

) <u>=</u>

DAVID SOULE P.E. #14522

 G_{E}

SCALE: 1"=10'