# CITY OF ALBUQUERQUE

*Planning Department* Brennon Williams, Director



Mayor Timothy M. Keller

May 4, 2021

David Soule, P.E. Rio Grande Engineering PO Box 93924 Albuquerque, New Mexico 87199

RE: Lot 4 Block 10 Unit 18 SAD 228 6500 Picardia NW Volcano Cliffs Subdivision Grading and Drainage Plan Engineers Stamp Date 5/1/2021 (D10D003P4)

Mr. Soule,

PO Box 1293 Based upon the information provided in your submittal received 5/4/2021, this plan is approved for Grading Permit.

Prior to Building permit approval a Pad Certification will be required, provided by the Engineer or a registered Land Surveyor.

Albuquerque

Advise the owner contractor not to use dirt as a ramp to climb the curb, use lumber or crusher fines for this purpose.

NM 87103

www.cabq.gov

Reiterate to the Owner/Contractor that a separate permit for a garden/retaining wall must be obtained with the approved G&D plan and Pad Certification. Also, if a swimming pool is to be placed the grading and drainage plan will change and will need to be resubmitted.

Prior to Certificate of Occupancy release, Engineer Certification per the DPM checklist is required.

If you have any questions, please contact me at 924-3986 or Rudy Rael at 924-3977.

Sincerely,

Ernest Armijo, P.E. Principal Engineer, Planning Dept. Development Review Services

C. S.	LBUAS	ta.
EA	(706)	
		-

## City of Albuquerque

Planning Department Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (REV 6/2018)

Project Title: 6500 PICARDIA	Building Permit	: #:	Hydrol	Hydrology File #			
DRB#: <u>NA</u> Legal Description: <u>LOT 4</u> , BLOCK	10, VOLCANO	CLIFFS UNI	г 18_				
City Address:6500 PICARDIA							
Applicant:			Contact:				
Address:							
Phone#:	Fax#:		E-mail:				
Other Contact: RIO GRANDE ENGI	NEERING		Contact:	DAVID SOULE			
Address: PO BOX 93924 ALB N	M 87199						
Phone#:	<b>Fax#:</b> 505.872	.0999	E-mail: <sup>d</sup>	avid@riograndeengineering.com			
TYPE OF DEVELOPMENT: PLA	T <u>X</u> RESIDE	NCE D	RB SITE	ADMIN SITE			
Check all that Apply:							
DEPARTMENT: X HYDROLOGY/ DRAINAGE TRAFFIC/ TRANSPORTATION		TYPE OF APPRO	PERMIT APPF				
TYPE OF SUBMITTAL:   ENGINEER/ARCHITECT CERTIFICATION   PAD CERTIFICATION   CONCEPTUAL G & D PLAN    XGRADING PLAN   DRAINAGE REPORT   DRAINAGE MASTER PLAN   FLOODPLAIN DEVELOPMENT PERMIT   ELEVATION CERTIFICATE   CLOMR/LOMR   TRAFFIC CIRCULATION LAYOUT (TO   TRAFFIC IMPACT STUDY (TIS)   STREET LIGHT LAYOUT   OTHER (SPECIFY)   PRE-DESIGN MEETING?    IS THIS A RESUBMITTAL?:YesX	F APPLIC CL)	FINAL PLA'	FOR SUB'D A FOR BLDG. F F APPROVAL SE OF FINAN ON PERMIT A PERMIT APPR OVAL RMIT APPROVAL PAD CERTIF ER APPROVAL MR	APPROVAL PERMIT APPROVAL JCIAL GUARANTEE APPROVAL ROVAL ICATION			
DATE SUBMITTED:							
COA STAFF:		BMITTAL RECEIVED:		-			

Weighted E Method														
												100-Yea	r, 6-hr.	24 hour
Basin	Area	Area	Treat	ment A	Treat	ment B	Treat	ment C	Treatr	nent D	Weighted E	Volume	Flow	Volume
	(sf)	(acres)	%	(acres)	%	(acres)	%	(acres)	%	(acres)	(ac-ft)	(ac-ft)	cfs	(ac-ft)
ALLOWED	15246.00	0.350	0%	0	20%	0.070	46%	0.161	34%	0.119	1.259	0.037	1.12	0.041
PROPOSED	15246.00	0.350	0%	0	20%	0.070	43%	0.1505	37%	0.130	1.289	0.038	1.14	0.043
COMPARISON												0.001		0.001

Equations:

Weighted E = Ea\*Aa + Eb\*Ab + Ec\*Ac + Ed\*Ad / (Total Area)


Volume = Weighted D \* Total Area


Flow = Qa \* Aa + Qb \* Ab + Qc \* Ac + Qd \* Ad


Where for 100-year, 6-ho	ur storm- zone 1	
•	Ea= 0.44	Qa= 1.29
	Eb= 0.67	Qb= 2.03
	Ec= 0.99	Qc= 2.87
	Ed= 1.97	Qd= 4.37
ONSITE Conditons		
FIRST FLUSH WATER Q	UALITY VOLUME	
	REQUIRED	PROVIDED
	(CF)	(CF)
WATER QUALITY	0	<b>122</b>
FLOOD CONTROL	55	122

#### Narrative

This site is within the SAD 228 Master Drainage plan boundaries. The site is to maintain existing patterns and drain as much as possible to the adjacent roadway per the master drainage plan. The site does exceed the SAD 228 developed conditions assumptions, therefore ponding is required. No measurable upland flow enters the site This plan is in conformance to the master drainage plan







NTS

### **CAUTION:**

EXISTING UTILITIES ARE NOT SHOWN. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT ALL NECESSARY FIELD INVESTIGATIONS PRIOR TO ANY EXCAVATION TO DETERMINE THE ACTUAL LOCATION OF UTILITIES & OTHER IMPROVEMENTS.

### **EROSION CONTROL NOTES:**

1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A TOPSOIL DISTURBANCE PERMIT PRIOR TO BEGINNING WORK.


2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RUN-OFF ON SITE DURING CONSTRUCTION.

3. CONTRACTOR IS RESPONSIBLE FOR CLEANING ALL SEDIMENT THAT GETS INTO EXISTING RIGHT-OF-WAY.


4. REPAIR OF DAMAGED FACILITIES AND CLEANUP OF SEDIMENT ACCUMULATIONS ON ADJACENT PROPERTIES AND IN PUBLIC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR.

5. ALL EXPOSED EARTH SURFACES MUST BE PROTECTED FROM WIND AND WATER EROSION PRIOR TO FINAL ACCEPTANCE OF ANY PROJECT.

2" LAYER OF GRAVEL AT FLOW LINE



-----



P.E. #14522