## CITY OF ALBUQUERQUE

Planning Department David Campbell, Director



Mayor Timothy M. Keller

March 28, 2019

David Soule, P.E. Rio Grande Engineering PO Box 93924 Albuquerque, New Mexico 87199

RE: Lot 2 Block 3, Volcano Cliffs, Unit 22, SAD 228 6332 Camino Alto NW Grading and Drainage Plan Engineers Stamp Date 3/27/19 (D10D003R2)

Dear Mr. Soule,

Based upon the information provided in your submittal received 3/27/19, this plan is approved for Grading Permit.

PO Box 1293 Prior to Building permit approval a Pad Certification will be required, provided by the Engineer or a registered Land Surveyor.

Albuquerque Please inform the builder/owner to attach a copy of this approved plan and letter to the construction sets in the permitting process prior to sign-off by Hydrology.

Reiterate to the Owner/Contractor that a separate permit for a garden/retaining wall must be obtained with the approved G&D plan and Pad Certification.

Prior to Certificate of Occupancy release, Engineer Certification per the DPM checklist is required.

www.cabq.gov

NM 87103

If you have any questions, please contact me at 924-3986 or Rudy Rael at 924-3977.

Sincerely,

Huller

James D. Hughes, E.É. Principal Engineer, Hydrology Planning Department

RR/JDH C: File D10D003R2

1999	ALBU	
<b>V</b>		

# City of Albuquerque

Planning Department Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (REV 6/2018)

Project Title:6332 CAMINO ALTO		Hydrology File #:
DRB#:	_ EPC#:	Work Order#:
Legal Description: LOT 2 , BLOCK	3 VOLCANO CLIFFS UNIT	<u>r 22</u>
City Address: 6332 CAMINO ALTO	- 1941	
Applicant: Phil Herrera		Contact:
Address:	· · · · · · · · · · · · · · · · · · ·	
Phone#:	_Fax#:	E-mail:
Other Contact: RIO GRANDE ENGIN	EERING	Contact: DAVID SOULE
Address: PO BOX 93924 ALB NM		- davideriograndeengineering oo
		E-mail: E-mail:
TYPE OF DEVELOPMENT: PLAT	X RESIDENCE 1	DRB SITE ADMIN SITE
Check all that Apply:		
DEPARTMENT: <u> </u>	<u> </u>	ROVAL/ACCEPTANCE SOUGHT: PERMIT APPROVAL ATE OF OCCUPANCY
TYPE OF SUBMITTAL:   ENGINEER/ARCHITECT CERTIFICATION   X PAD CERTIFICATION   CONCEPTUAL G & D PLAN   GRADING PLAN   DRAINAGE REPORT   DRAINAGE MASTER PLAN   FLOODPLAIN DEVELOPMENT PERMIT A   ELEVATION CERTIFICATE   CLOMR/LOMR   TRAFFIC CIRCULATION LAYOUT (TCL)   TRAFFIC IMPACT STUDY (TIS)   STREET LIGHT LAYOUT   OTHER (SPECIFY)   PRE-DESIGN MEETING?    IS THIS A RESUBMITTAL?:YesXN	SITE PLAN SITE PLAN FINAL PLA FINAL PLA SIA/ RELE GRADING GRADING DAVING P X GRADING WORK ORI CLOMR/LO FLOODPLA OTHER (SI	ERMIT APPROVAL / PAD CERTIFICATION DER APPROVAL
DATE SUBMITTED:		
COA STAFF:	ELECTRONIC SUBMITTAL RECEIVED:	

Weighted E Method														
												100-Year	, 6-hr.	
Basin	Area	Area	Treat	ment A	Treat	ment B	Treatr	ment C	Treat	ment D	Weighted E	Volume	Flow	
	(sf)	(acres)	%	(acres)	%	(acres)	%	(acres)	%	(acres)	(ac-ft)	(ac-ft)	cfs	
ALLOWED	13446.00	0.309	0%	0	20%	0.062	46%	0.142	34%	0.105	1.259	0.032		0.99
PROPOSED	13446.00	0.309	0%	0	30%	0.093	43%	0.1327	27%	0.083	1.159	0.030		0.93
COMPARISON												-0.003		

#### Equations:

Weighted E = Ea\*Aa + Eb\*Ab + Ec\*Ac + Ed\*Ad / (Total Area)

Volume = Weighted D \* Total Area

Flow = Qa \* Aa + Qb \* Ab + Qc \* Ac + Qd \* Ad

Where for 100-year, 6-hou	ur storm- zone 1	
-	Qa= 1.29	
	Eb= 0.67	Qb= 2.03
	Ec= 0.99	Qc= 2.87
	Ed= 1.97	Qd= 4.37
ONSITE Conditons FIRST FLUSH WATER Q	REQUIRED	PROVIDED
WATER QUALITY FLOOD CONTROL	(CF) 103	(CF) 745 745

#### Narrative

This site is within the SAD 226 Master Drainage plan boundaries. The site is to maintain existing patterns and drain as much as possible to the adjacent roadway to the south per the master drainage plan. We are ponding the water harvest volume generated by the site there is not measurable upland flow. This plan does not exceed the allowed impervious area therefore we are notrrequried to retain. This plan is in conformance to the master drainage plan

> CONSTRUCT 18.50' DRIVEWAY AND SIDEWALK PER COA STD DWG #2405, 2425, 2430

CAUTION: EXISTING UTILITIES ARE NOT SHOWN. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT ALL NECESSARY FIELD INVESTIGATIONS PRIOR TO ANY EXCAVATION TO DETERMINE THE ACTUAL LOCATION OF UTILITIES & OTHER IMPROVEMENTS.

### EROSION CONTROL NOTES:


1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A TOPSOIL DISTURBANCE PERMIT PRIOR TO BEGINNING WORK.


2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RUN-OFF ON SITE DURING CONSTRUCTION.

3. CONTRACTOR IS RESPONSIBLE FOR CLEANING ALL SEDIMENT THAT GETS INTO EXISTING RIGHT-OF-WAY.

4. REPAIR OF DAMAGED FACILITIES AND CLEANUP OF SEDIMENT ACCUMULATIONS ON ADJACENT PROPERTIES AND IN PUBLIC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR.

5. ALL EXPOSED EARTH SURFACES MUST BE PROTECTED FROM WIND AND WATER EROSION PRIOR TO FINAL ACCEPTANCE OF ANY PROJECT.





### LEGEND

	EXISTING CONTOUR
	EXISTING INDEX CONTOUR
XXXX	PROPOSED CONTOUR
	PROPOSED INDEX CONTOUR
►	SLOPE TIE
× XXXX	EXISTING SPOT ELEVATION
× XXXX	PROPOSED SPOT ELEVATION
	BOUNDARY
	CENTERLINE
	RIGHT-OF-WAY
============	EXISTING CURB AND GUTTER
× × × × × × × × × × × × × × × × × × ×	PROPOSED CMU SCREEN WALL (12" MAX. RETAINAGE)
× <u>·····</u>	PROPOSED RETAINING WALL-DESIGN BY OTHERS

