CITY OF ALBUQUERQUE

Planning Department
Alan Varela, Interim Director



Mayor Timothy M. Keller

December 13, 2021

David Soule, P.E. Rio Grande Engineering PO Box 93924 Albuquerque, New Mexico 87199

RE: Lot 9 Block 1 Unit 5
6701 Rim Rock Cir. NW
Grading and Drainage Plan
Engineers Stamp Date 7/30/2021 (D10D22)
Pad Certification Date 12/10/2021

Mr. Soule,

Based upon the information provided in your submittal received 12/10/2021, this plan is approved for Building Permit.

Please inform the builder/owner to attach a copy of this approved plan and this letter to the construction sets in the permitting process prior to sign-off by Hydrology.

Reiterate to the Owner/Contractor that a separate permit for a garden/retaining wall must be obtained, with the approved G&D plan. Also, advise the owner/contractor not to use dirt as a ramp to climb the curb. If dirt is used it will cause a delay in permitting.

Prior to Certificate of Occupancy release, Engineer Certification per the DPM checklist of this plan will be required.

If you have any questions, please contact me at 924-3986 or Rudy Rael at 924-3977.

Sincerely,

Ernest Armijo, P.E.

Principal Engineer, Planning Dept.

Development Review Services



City of Albuquerque

Planning Department

Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (REV 6/2018)

Project Title: 6701 RIM ROCK	Building Permit #	#: Hydrol	ogy File #:
DRB#:	_EPC#:	Work (Order#:
Legal Description: LOT 9, BLOCK 1	UNSER CLIFE	· S	
City Address: 6701 RIM ROCK			
Applicant: LITTLE BUBBAS		Contact:	
Address:			
Phone#:	Fax#:	E-mail:	
Other Contact: RIO GRANDE ENGINE		Contact:	DAVID SOULE
Address: PO BOX 93924 ALB NM			
Phone#: 505.321.9099	Fax#: 505.872.0	1999 E-mail : di	avid@riograndeengineering.com
TYPE OF DEVELOPMENT: PLAT			
Check all that Apply:			
DEPARTMENT:	•	TYPE OF APPROVAL/ACCEI	PTANCE SOUGHT:
X HYDROLOGY/ DRAINAGE		× BUILDING PERMIT APPR	
TRAFFIC/ TRANSPORTATION	_	CERTIFICATE OF OCCUP	
TYPE OF SUBMITTAL:			
ENGINEER/ARCHITECT CERTIFICATION	1 _	PRELIMINARY PLAT AP	PROVAL
\underline{X} PAD CERTIFICATION	_	SITE PLAN FOR SUB'D A	APPROVAL
CONCEPTUAL G & D PLAN	_	SITE PLAN FOR BLDG. P	ERMIT APPROVAL
GRADING PLAN	_	FINAL PLAT APPROVAI	_
DRAINAGE REPORT			
DRAINAGE MASTER PLAN	_	SIA/ RELEASE OF FINAN	ICIAL GUARANTEE
FLOODPLAIN DEVELOPMENT PERMIT A	.PPLIC _	FOUNDATION PERMIT A	APPROVAL
ELEVATION CERTIFICATE	_	GRADING PERMIT APPR	OVAL
CLOMR/LOMR	_	SO-19 APPROVAL	
TRAFFIC CIRCULATION LAYOUT (TCL)		PAVING PERMIT APPRO	VAL
TRAFFIC IMPACT STUDY (TIS)	_	GRADING/ PAD CERTIFI	CATION
STREET LIGHT LAYOUT	_	WORK ORDER APPROVAL	_
OTHER (SPECIFY)	_	CLOMR/LOMR	
PRE-DESIGN MEETING?	- -	FLOODPLAIN DEVELOPM	MENT PERMIT
IS THIS A RESUBMITTAL?: X Yes No	-	OTHER (SPECIFY)	
DATE SUBMITTED:			
COA STAFF:	ELECTRONIC SUBM	ITTAL RECEIVED:	
	FEE PAID:		

Weighted E Method

												100-Yea	ar, 6-hr.
Basin	Area	Area	Treat	ment A	Treat	ment B	Treat	ment C	Treati	ment D V	Veighted I	Volume	Flow
	(sf)	(acres)	%	(acres)	%	(acres)	%	(acres)	%	(acres)	(ac-ft)	(ac-ft)	cfs
ALLOWED	13475.00	0.309	0%	0	26%	0.080	40%	0.1237	34%	0.105	1.240	0.032	0.98
PROPOSED	13475.00	0.309	0%	0	26%	0.080	39%	0.1206	35%	0.108	1.250	0.032	0.98
total													

Weighted $E = Ea^*Aa + Eb^*Ab + Ec^*Ac + Ed^*Ad / (Total Area)$

Volume = Weighted D * Total Area

Flow = Qa * Aa + Qb * Ab + Qc * Ac + Qd * Ad

Where for 100-year, 6-hour storm-zone 1

•	Ea= 0.44	Qa= 1.2
	Eb= 0.67	Qb= 2.0
	Ec= 0.99	Qc= 2.8
	Ed= 1.97	Qd= 4.3

ONSITE Conditions PONDING REQUIREMENTS

	REQUIRED	PROVIDED
	(CF)	(CF)
WATER QUALITY	0	1375
FLOOD CONTROL	11	1375

Additional ponding and low slopes are utilized to maintain as low of pad as possible due to height restrictions


Narrative

This site is within the SAD 227 Master Drainage plan boundaries. The site is to maintain existing patterns and drain to the the adjacent roadway per the master drainage plan. We are ponding the water harvest volume generated by the site The site is not impacted by upland flow. This plan has a shallow water harvest pond in excess of the drainage regulations. This plan generate flow in excess of the allowed in the master drainage plan developed conditions assumption. Therefore ponding is of 11 CF is required. I, DAVID SOULE HAVE PERSONALLY INPECTED THE SITE. I HEREBY CERTIFY THE PAD HAS BEEN CONSTRUCTED SUCH THAT IT IS IN SUBSTANTIAL CONFORMANCE TO THE APPROVED GRADING PLAN DATED 7/30/21




EROSION CONTROL NOTES:

- 1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A TOPSOIL DISTURBANCE PERMIT PRIOR TO BEGINNING WORK.
- 2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RUN-OFF ON SITE DURING CONSTRUCTION.
- 3. CONTRACTOR IS RESPONSIBLE FOR CLEANING ALL SEDIMENT THAT GETS INTO EXISTING RIGHT-OF-WAY.
- 4. REPAIR OF DAMAGED FACILITIES AND CLEANUP OF SEDIMENT ACCUMULATIONS ON ADJACENT PROPERTIES AND IN PUBLIC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR.
- 5. ALL EXPOSED EARTH SURFACES MUST BE PROTECTED FROM WIND AND WATER EROSION PRIOR TO FINAL ACCEPTANCE OF ANY PROJECT.



VICINITY MAP: D-10-Z



FIRM MAP:

LEGAL DESCRIPTION:

LOT 9 BLOCK 1 UNSER CLIFFS SUBDIVISION CITY OF ALBUQUERQUE, BERNAILILLO COUNTY, NEW MEXICO


NOTES:


- 1. ALL SPOT ELEVATIONS REPRESENT FLOWLINE ELEVATION UNLESS OTHERWISE NOTED.
- 2. ALL SLOPES SHALL BE 3:1 MAX. AND GRAVEL OR NATIVE SEEDING PRIOR TO CO.
- 3. ANY PERIMETER WALLS MUST BE PERMITED SEPARATELY ALL RETAINING WALL DESIGN SHALL BE BY OTHERS.

4. SURVEY INFORMATION PROVIDED BY COMMUNITY SCIENCES CORPORATION USING NAVD


5. A PAD ELEVATION CERTIFICATION SHALL BE REQUIRED PRIOR TO RELEASE OF BUILDING

LEGEND





SCALE: 1"=20'



DAVID SOULE P.E. #14522

7/30/21

6701 RIM ROCK CIRCLE GRADING AND

DRAINAGE PLAN




Lot 9 Blk 1 Unser Cliffs Sub .DWG SHEET# C1 JOB#

DRAWN

 BY DEM

DATE 7-29-21



______ PLACE 2" LAYER OF

CONSTRUCT ALL SWALES AND EROSION PROTECTION

(SHOWN HATCHED) BELOW ADJACENT GRADE TO ENDSURE RUNOFF CAN BE CAPTURED AND CONVEYED PROPERLY.

EARTHEN SWALE

GRAVEL AT FLOW LINE

CAUTION:

EXISTING UTILITIES ARE NOT SHOWN. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT ALL NECESSARY FIELD INVESTIGATIONS PRIOR TO ANY EXCAVATION TO DETERMINE THE ACTUAL LOCATION OF UTILITIES & OTHER IMPROVEMENTS.