

SCALE: 1"=50'

$Q_{100} = \frac{Q_{100} \times 0.5}{0.002 \text{ ft/sec}} = (\quad) \text{ ac-ft}$

LEGAL DESCRIPTION:

Lot 2-A being a replat of Tract 2 of the Mann Tracts.

GENERAL NOTES:

1) Planning history: DRB-88-496, AX-87-36, Z-87-168

2) This plan is for the subdivision of land only.

3) The temporary bench mark on site is located at the southwest corner of the southerly inlet structure of the Corrales Main Canal.

4) The site is currently undeveloped vacant land. Also, there are no structure within 25 feet.

5) No buildings are proposed at this time.

6) Lots G, H, & I are proposed to to have interim desilting facilities. Permanent desilting facilities are to be designed and approved with the development of lots G, H, & I. The criteria for desilting is established in the North Coors Drainage Management Plan. Additional requirements are:

Min. pond storage area = .0024 acft/ acre upstream area
Velocity of sediment fall = .002 ft/sec @50% of Q100
Max. horizontal velocity in pond = .5 ft/sec @ 50% Q100
Retention time in pond = depth ft. / .002

7) The drainage information for this site is located in separate document titled Drainage Information for Bosque Del Pueblo.

8) Erosion control is proposed to be addressed in two phases; 1 rough grading and 2 permanent construction. Rough grading erosion control would consist of disk crimped straw or seeding and/or sand bagging and/or silt fencing. The permanent phase uses the drainage structures located at the east of the site, and facilities identified in note 6. Erosion control during construction will be the responsibility of the Contractor. Erosion control plans for construction must be provided by the Contractor prior to construction.

9) All desilting ponds are private and to be maintained by the owners and will require an excuted drainage covenant.

AS BUILT INFORMATION
CONTRACTOR
WORK STARTED ON
WORK COMPLETED ON
ACCEPTED BY
DATE
FINAL INSPECTION BY
DATE
SEAL/SIGNATURE OF PROFESSIONAL ENGINEER
DATE
MICRO-FILM INFORMATION
MICROFILMED BY
DATE

SURVEY INFORMATION
BENCH MARKS
K. ALVARADO B-2
0.4 MI. SW FROM THE INTERSECTION OF PARADISE BLVD. AND COORS RD., 650 FT. WEST FROM THE EDGE OF COORS RD., 187 FT. SW FROM THE 2ND POWER POLE FROM THE EAST, AND 30 FT. EAST FROM THE CENTERLINE OF THE ROAD R/W.
ELEVATION: 5056.28

FIELD NOTES
NO. DATE BY

ENGINEER'S SEAL
NEW MEXICO
JAMES E. KAUFMAN
10278
REGISTERED PROFESSIONAL ENGINEER
1-18-89
FOR REVIEW ONLY
Not for construction or recordation

NO.	DATE	REMARKS
	12-15-88	REVISIONS
	12-15-88	DESIGN
		DRAWN BY
		CHECKED BY

DESIGNED BY J.B.
DRAWN BY J.K.

RECEIVED
JAN 19 1989
HYDROLOGY SECTION

LEGEND

5000	EXISTING CONTOUR
95	PROPOSED CONTOUR
	LOT LINE
	CURB AND GUTTER
	DRAINAGE SWALE
	NEW PAVING
	EXISTING EDGE OF PAVEMENT
	TYPE "B" DROP INLET
	PROPOSED DRAINAGE AREA BOUNDARY
	EXISTING DRAINAGE AREA BOUNDARY

Greiner Engineering
8211 Jefferson Blvd N.E.
Suite 101
Albuquerque, New Mexico 87109
(505) 345-3990

CITY OF ALBUQUERQUE
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

TITLE BOSQUE DEL PUEBLO
FINAL GRADING & DRAINAGE PLAN

APPROVALS	ENGINEER	DATE	APPROVALS	ENGINEER	DATE
City Engineer			Liquid Waste		
A.C.E. - Design			Traffic		
A.C.E. - Hydrology			Water		

DRAWING NO. 3688 | MAP NO. D-13 | SHEET 4 OF 12



VICINITY MAP ZONE MAP G-13

BERNALILLO COUNTY SOILS MAP 10

FEMA PANEL 350002 0008