CITY OF ALBUQUERQUE

Planning Department Brennon Williams, Director



Mayor Timothy M. Keller

June 8, 2021

David Soule, P.E. Rio Grande Engineering PO Box 93924 Albuquerque, New Mexico 87199

RE: Lot 11 Block 3 S.A.D. 227 Unit 2 5605 Kimberlite Dr. NW Grading and Drainage Plan Engineers Stamp Date 6/7/2021 (E10D106)

Dear Mr. Soule,

Based upon the information provided in your submittal received 6/89/2021, this plan is approved for Grading Permit. Please inform the builder/owner to attach a copy of this approved plan and letter into the construction sets in the permitting process prior to sign-off by Hydrology. PO Box 1293 Reiterate to the Owner/Contractor that a separate permit for any garden/retaining wall must be obtained, with the approved G&D plan. Advise the owner contractor not to use dirt as a ramp to climb the curb, use lumber or crusher fines for this purpose. Albuquerque Also, let the owner/contractor know that if a pool is to be added in the future the G&D plan will need to be modified showing the location of the pool and the land treatment differences. NM 87103 Prior to Building Permit approval, a Pad Certification will be required. Inform the contractor/owner not to pile dirt in the street as a ramp to climb the curb. If dirt is found in the street the pad cert. will be denied. www.cabq.gov

Prior to **Certificate of Occupancy release**, Engineer Certification per the DPM checklist of this plan will be required.

If you have any questions, please contact me at 924-3986 or Rudy Rael at 924-3977.

Sincerely,

Ernest Armijo, P.E. Principal Engineer, Planning Dept. Development Review Services



City of Albuquerque

Planning Department Development & Building Services Division

DRAINAGE AND TRANSPORTATION INFORMATION SHEET (REV 6/2018)

Project Title: 5605 KIMBERLITE	Building Permit	#:	Hydrology File #:				
DRB#:	_ EPC#:		Work Order#:				
DRB#:LOT 11, Block	3 VOLCANC	CLIFFS UNIT	2				
City Address: 5605 KIMBERLITE							
Applicant:			Contact:				
Address:							
Phone#:			_E-mail:				
Other Contact: RIO GRANDE ENGINE	ERING		Contact: DAVID SOULE				
ALL DO DOV 02024 ATD MM	97100						
Phone#: 505.321.9099	Fax#: 505.872	.0999	E-mail: com				
TYPE OF DEVELOPMENT: PLAT							
Check all that Apply:							
DEPARTMENT: <u>×</u> HYDROLOGY/ DRAINAGE TRAFFIC/ TRANSPORTATION		EVILLING PE	AL/ACCEPTANCE SOUGHT: MIT APPROVAL OF OCCUPANCY				
TYPE OF SUBMITTAL: ENGINEER/ARCHITECT_CERTIFICATION PAD CERTIFICATION CONCEPTUAL G & D PLAN X GRADING PLAN DRAINAGE REPORT DRAINAGE MASTER PLAN FLOODPLAIN DEVELOPMENT PERMIT A ELEVATION CERTIFICATE CLOMR/LOMR TRAFFIC CIRCULATION LAYOUT (TCL) TRAFFIC IMPACT STUDY (TIS) STREET LIGHT LAYOUT OTHER (SPECIFY) PRE-DESIGN MEETING? IS THIS A RESUBMITTAL?: Yes X No	PPLIC	SITE PLAN FC	OF FINANCIAL GUARANTEE PERMIT APPROVAL MIT APPROVAL /AL IIT APPROVAL O CERTIFICATION APPROVAL				
DATE SUBMITTED:							
COA STAFF:	ELECTRONIC SUB	MITTAL RECEIVED:					

Weighted E Method															
												100-Yea	r, 6-hr.		24 hour
Basin	Area	Area	Treat	ment A	Treat	ment B	Treati	ment C	Treatr	ment D	Weighted E	Volume	Flow		Volume
	(sf)	(acres)	%	(acres)	%	(acres)	%	(acres)	%	(acres)	(ac-ft)	(ac-ft)	cfs		(ac-ft)
ALLOWED	11225.00	0.258	0%	0	20%	0.052	46%	0.1185	34%	0.088	1.259	0.027		0.83	0.030
PROPOSED	11225.00	0.258	0%	0	20%	0.052	41%	0.1057	39%	0.100	1.308	0.028		0.85	0.032
COMPARISON												0.001			0.002

Equations:

Weighted E = Ea*Aa + Eb*Ab + Ec*Ac + Ed*Ad / (Total Area)


Volume = Weighted D * Total Area


Flow = Qa * Aa + Qb * Ab + Qc * Ac + Qd * Ad

Where for 100-year, 6-hou	r storm- zone 1	
-	Ea= 0.44	Qa= 1.29
	Eb= 0.67	Qb= 2.03
	Ec= 0.99	Qc= 2.87
	Ed= 1.97	Qd= 4.37
ONSITE Conditons FIRST FLUSH WATER QL	JALITY VOLUME	
	REQUIRED	PROVIDED
	(CF)	(CF)
WATER QUALITY	0	564
FLOOD CONTROL	67	564

Narrative

This site is within the SAD 227 Master Drainage plan boundaries. The site is to maintain existing patterns. Due to city height restrictions we must maintain the lowest possible grade. The site does exceed the SAD 228 developed conditions assumptions therefore ponding is required. No significant upland flow enters the site. The building requires gutters to direct developed flow to street. This plan is in conformance to the master drainage plan





CAUTION:

EXISTING UTILITIES ARE NOT SHOWN. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO CONDUCT ALL NECESSARY FIELD INVESTIGATIONS PRIOR TO ANY EXCAVATION TO DETERMINE THE ACTUAL LOCATION OF UTILITIES & OTHER IMPROVEMENTS.

EROSION CONTROL NOTES:


1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING A TOPSOIL DISTURBANCE PERMIT PRIOR TO BEGINNING WORK.

2. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING RUN-OFF ON SITE DURING CONSTRUCTION.

3. CONTRACTOR IS RESPONSIBLE FOR CLEANING ALL SEDIMENT THAT GETS INTO EXISTING RIGHT-OF-WAY.


4. REPAIR OF DAMAGED FACILITIES AND CLEANUP OF SEDIMENT ACCUMULATIONS ON ADJACENT PROPERTIES AND IN PUBLIC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR.

5. ALL EXPOSED EARTH SURFACES MUST BE PROTECTED FROM WIND AND WATER EROSION PRIOR TO FINAL ACCEPTANCE OF ANY PROJECT.



PO BOX 93924 ALBUQUERQUE, NM 87199 (505) 321-9099

JOB #



DAVID SOULE P.E. #14522